

L.1 MARKER/PROJECTION BOARD OFFICE: BASIS OF DESIGN DALITE IDEA SCREEN 4'-6"
L.2 HIGH, WIDTH NOTED

L.3 RECESSED CEILING MOUNTED PROJECTION SCREEN

L.4 CEILING MOUNTED PROJECTOR ABOVE

L.5 SAFETY SHOWER AND EYEWASH

L.6 115131 CHEMICAL FUME HOOD W/ STORAGE BELOW. TYPICAL FUME HOOD TO HAVE
L.7 ELECTRIC AND UTILITIES AS NOTED

L.8 WOOD LAB CASEWORK MICROSCOPE CAB

L.9 WOOD LAB CASEWORK BOOK BAG STORAGE. TALL CABINET WITH OPEN CUBBIES
L.10 FOR BACKPACKS/BOOKS

L.11 115133 CHEMICAL FUME HOOD - ACCESSIBLE - WITH MOBILE STORAGE BELOW.
L.12 TYPICAL FUME HOOD TO HAVE ELECTRIC, AND UTILITIES AS INDICATED.

L.13 CABS BELOW WHITEBOARD

L.14 CAMERA FOR SKYPE INTERVIEW

L.15 GAS CYLINDER STORAGE

L.16 RECESSED MOUNTED ROOM DARKENING / BLACKOUT SHADES. USE DOUBLE
L.17 SHADES AT WEST CLASSROOMS LEVEL 02 AND LECTURE HALL. REFER TO
L.18 REFLECTED CEILING PLANS

L.19 LCD MONITOR

L.20 MOVABLE LABORATORY CASEWORK: MOVEABLE "C" FRAME CART" WITH
L.21 COUNTERTOP. WOOD BASE CABINETS SUSPENDED BELOW AND ADJUSTABLE METAL
L.22 LIFTING SUSPENSION SYSTEM FROM ABOVE

L.23 MOVABLE WOOD LABORATORY CASEWORK: TABLE WITH MODIFIED EPOXY
L.24 COUNTERTOP. CABINETS SUSPENDED BELOW AS INDICATED

L.25 MOVABLE WOOD LABORATORY CASEWORK: BASE CABINET WITH MODIFIED EPOXY
L.26 COUNTERTOP. WALL CABINETS AS SHOWN ON ELEVATION

L.27 SEE CEILING PLAN FOR CEILING MOUNTED UNISTRUT SYSTEM SUPPORTED BY
L.28 STEEL BRACE

L.29 6" x 6" TRENCH WITH METAL COVER TO RECEIVE FLOOR FINISH TO MATCH ADJACENT
L.30 FLOOR

L.31 FIXED WOOD LABORATORY CASEWORK: WOOD BASE AND WALL CABINETS WHERE
L.32 SHOWN, MODIFIED EPOXY COUNTERTOP



© Cannon Design 2015