

Webb Engineering Services, Inc.
Plumbing & Fire Protection
1400 S. 3rd Street, Suite 201
St. Louis, MO 63104
314.588.0600

C.1 122413 TYPE 1 SHADES: MOTORIZED ROLLER SHADES IN CONTINUOUS RECESSED POCFI (CFCI)

C.2 122413 TYPE 2 SHADES MOTORIZED DOUBLE ROLLER SHADES: SURFACE MOUNTED W/ CUSTOM COLO FASCIA

C.3 122413 TYPE 3 SHADES: MANUAL SHADES IN RECESSED POCFI

C.4 122413 TYPE 4 SHADES: MOUNTED LON COUNDED SHED IN CONTINUOUS POCFI

C.5 CEILING MOUNTING SUSPENSION FOR LOO D SCREEN- PROVIDE STEEL SUPPORT ABOVE CEILING

C.6 EXHAUST HOOD LOCATION - REFER TO FOOD SERVICE DRAWINGS

C.7 FUME HOOD LOCATION - HOOD ENCLOSURE EXTENDS 6" ABOVE CEILING

C.8 CYPED STRUCTURE

C.9 083333 SLATE CEILING DOOD TRACK

C.10 ACUSTICAL PANEL CEILING ABOVE WOOD GRILLE CEILING. 1" THICK ARMSTRONG OPTIMA PANELS FIT TO GRID FOR WOOD GRILLE CEILING

C.11 122413 TYPE 5 SHADES: MOTORIZED DOUBLE ROLLER SHADES: SURFACE MOUNTED W/ CUSTOM COLO FASCIA

C.12 122413 TYPE 6 SHADES: MOTORIZED DOUBLE ROLLER SHADES IN RECESSED POCFI - PROVIDE BLOCKING

C.13 RECESSED DRAPERY TRACK AND CURTAINS - CFCI - PROVIDE BLOCKING

C.14 122413 TYPE 7 MOTORIZED DOUBLE ROLLER SHADES IN RECESSED POCFI WOOD CEILING AT BOTTOM OF STAIRS - REFER TO STAIR 1 DRAWINGS AND DETAIL SHEET A501

C.15 WOOD CEILING AT BOTTOM OF STAIRS - REFER TO STAIR 1 DRAWINGS AND DETAIL SHEET A501

C.16 CONTINUOUS PANEL LIGHTING FIXTURE TAPED INTO GYP BOARD CEILING - REFER TO ELECTRICAL LIGHTING DRAWINGS AND TO DETAIL AT WALL SHEET A042

C.18 CEILING IN COV ROOM BY COLD ROOM MFG

C.19 C57500 MET ALUM BEAM CEILING

C.20 UNISTRUT MOUNTED TO CEILING W/ STEEL ANGLE HANGERS AND KICKER ABOVE FOR SUPPORT

C.21 STAIRS IN COV ROOM CAPTURE HOOD ABOVE AUTOCLAVE

C.22 REFER TO DETAIL B4042

C.23 122413 TYPE 6 SHADES: MANUAL SHADES IN RECESSED POCFI AT INTERIOR GLAZING: POCFI CONTINUOUS ACROSS OPENING

C.24 INSULATED GLAZING UNIT - 1/2" SHW SECT A040

C.25 CEILING MOUNTED SURGICAL LIGHT - SEE EQUIPMENT LIST (CFCI) - PROVIDE STRUCTURAL STEEL SUPPORT TO CEILING - 4 - 2X2X 1/4" STEEL ANGLE HANGER WITH 4 - ANGLE KICKERS 2 X 2 X 1/4" AND MOUNTING PLATE PER MANUFACTURER DETAIL Q1491A

C.26 CONTROL JOINT LOCATION

C.27 ABOVE CEILING WHERE INDICATED WITH DASHED LINE: PROVIDE 2 HOUR RATED HORIZONTAL GYP BOARD ENCLOSURE AND DUCTS SERVING FLOOR GRILLS ON LEVEL ABOVE - REFER TO DETAIL SHEET A1002

C.28 ABOVE CEILING WHERE INDICATED WITH DASHED LINE: PROVIDE 2 HOUR RATED HORIZONTAL GYP BOARD ENCLOSURE AROUND STANDPIPE RUN. REFER TO DETAIL SHEET A1002

C.29 PROVIDE 2 HOUR RATED HORIZONTAL GYP BOARD ENCLOSURE AT BOTTOM OF SHAFT - REFER TO DETAIL SHEET A1002

C.30 122413 TYPE 7 SHADES: MOTORIZED DOUBLE ROLLER SHADES: SURFACE MOUNTED W/ CUSTOM COLO FASCIA

C.31 122413 TYPE 8 MOTORIZED DOUBLE ROLLER SHADE IN RECESSED POCFI SPECIAL ACUSTICAL SEPARATION CEILING: APPLY KINETIC NOISE CONTROL JOINT Q1491A

C.32 122413 TYPE 9 SHADES: MANUAL SHADES - STEPPED WITH SLOPE IN CLOPED OPENING

C.33 REVEAL TRIM AROUND DIAGONAL BRACE PENETRATION THROUGH CEILING

C.34 122413 TYPE 10 SHADES: MOTORIZED DOUBLE ROLLER SHADES: SURFACE MOUNTED W/ CUSTOM COLO FASCIA

C.35 LABORATORY OVERHEAD SERVICE CARRIER - REFER TO ENLARGED FLOOR PLANS

C.36 EMERGENCY SAFETY SHOWER - PIPING TO HEAD ABOVE CEILING

C.37 122413 TYPE 3 SHADES: MANUAL SHADES - STEPPED WITH SLOPE IN CLOPED OPENING

C.38 122413 TYPE 9 SHADES: DOUBLE MANUAL SHADES IN RECESSED POCFI

APC-1	2' x 2' - ARMSTRONG OPTIMA TEGULAR 1" THICK IN 9/16" GRID
APC-2	2' x 4' - ARMSTRONG ULTIMA TEGULAR IN 9/16" SILHOUETTE XL 1/8" GRID
APC-3	2' x 4' - ARMSTRONG ULTIMA TEGULAR 1" THICK IN 9/16" GRID
APC-38	2' x 2' - ARMSTRONG ULTIMA HEALTH ZONE TEGULAR 9/16" GRID
APC-39	NOT USED
APC-4	2' x 2' - ARMSTRONG FINE FISURED IN 15/16" GRID
APC-40	ARMSTRONG ACOUSTICAL GLASS (BAYVIEW) 60/50/90 OVER 1/2" INSULATION OVER GYP BOARD
APC-7	2' x 4' - ARMSTRONG ULTIMA TEGULAR IN 9/16" SILHOUETTE XL GRID W/ 6" PANEL INSERTS A SHOWN
APC-8	2' x 4' - ARMSTRONG OPTIMA TEGULAR - 1" THICK NRC - 90 IN 9/16" SILHOUETTE XL 1/8" GRID
APC-9	MATCH APC-8 WITH 1" RISE AT JOINTS FOR SPECIAL TREATMENT OF SPECIAL JOINTS
APC-10	ACOUSTIC MATERIAL TO TOP SIDE OF PANELS AND PROVIDE ISOLATORS FOR CEILING HANGERS.

WDC-1 09 5426 WOOD GRILLE CEILING W/ 3/4" x 2 1/4" MEMBERS - 6 PER FOOT - NINEWOOD GRILLE
1400 W/ 1" THICK ARMSTRONG OPTIMA PANELS FIT TO GRID SUPPORT ABOVE

WDC-2 06 4216 FLUSH WOOD PANEL SOFFIT - MATCH WVP-1

WDC-3 06 4216 OPAQUE WOOD PANEL TO MATCH WOOD ACOUST WALL PANEL

GWB-1 PAINTED GYP. BOARD

GWB-2 GYP. BOARD W/ COATING TO MATCH ADJACENT ACOUST. PLASTER

4	ASI-060	13 APR 2017
3	ASI-056	17 MAR 2017
2	ASI-046	16 JAN 2017
1	ADDENDUM 3-2	15 APR 2016
-	ISSUED FOR CONSTRUCTION (BP3)	15 MAR 2016

Drawing Title:

**LEVEL 02 REFLECTED
CEILING PLAN AREA A**

Project No.: 04561.01 Checked by:

A0702.A