

THE SEAL(S) AND SIGNATURE(S) APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED, AND EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE ARCHITECTURAL OR ENGINEERING PROJECT.



Webster University  
Interdisciplinary Science  
Building

CANNONDESIGN

1100 Clark Avenue  
St. Louis, Missouri 63102  
T: 314.241.6250  
F: 314.241.2570

William Tao & Associates, Inc.  
MEP/FP Engineer  
7955 Manchester Road, Suite 125  
St. Louis, MO 63143  
314-884-7600

David Mason & Associates, Inc.  
Structural & Civil Engineer  
800 South Vandeventer Avenue  
St. Louis, MO 63110  
314.534.1053

Faith Group  
Technology  
3101 S. Hanley Rd., Suite 100  
St. Louis, MO 63143  
314.991.2228

Kuhmann Leavitt, Inc.  
Environmental Graphics & Signage  
7400 Pershing Ave.  
St. Louis, MO 63130  
314.725.6616

KWA Architects  
Architecture  
8721 Litzinger Road  
St. Louis, MO 63124  
314.962.2560

Spellman Brady & Company  
Interior Designer  
8251 Maryland Avenue, Suite 300  
St. Louis, MO 63105  
314.862.0070

SWT Design  
Landscape Architect  
7722 Big Bend Blvd  
St. Louis, MO 63119  
314.644.5700

Webb Engineering Services, Inc.  
Plumbing & Fire Protection  
1400 S. 3rd Street, Suite 201  
St. Louis, MO 63104  
314.588.0600

### GENERAL NOTES:

- DO NOT SCALE DRAWINGS. REFER TO ARCHITECTURAL PLANS AND ELEVATIONS FOR LOCATION AND ORIENTATION OF DEVICES. WHERE LOCATIONS ARE NOT INDICATED ON ARCHITECTURAL DRAWINGS, COORDINATE LOCATION AND ORIENTATION OF DEVICES IN FIELD WITH ARCHITECT PRIOR TO ROUGH-IN.
- CONTRACTOR SHALL VISIT PRIOR TO BID SUBMITTALS TO DETERMINE SITE CONDITIONS EFFECTING THE EXECUTION OF WORK. FAILURE TO BE ACQUAINTED WITH EXISTING CONDITIONS WILL NOT BE JUSTIFICATION FOR ADDITIONAL SERVICES.
- EXISTING DEVICES TO REMAIN ARE INDICATED WITH A THIN SOLID LINE WEIGHT (AND SUBSCRIPT "EX").
- CONTRACTOR SHALL REMOVE ALL ELECTRICAL DEVICES INCLUDING BUT NOT LIMITED TO LIGHTING, POWER, FIRE ALARM, AND AUXILIARY DEVICES FROM PARTITIONS AND CEILINGS INDICATED FOR DEMOLITION ON THE ARCHITECTURAL PLANS UNLESS NOTED OTHERWISE.
- FOR ANY DEVICES BEING REMOVED, REMOVE ASSOCIATED BOXES, CONDUIT, AND WIRE BACK TO NEAREST DEVICE REMAINING OR TO SOURCE UNLESS NOTED OTHERWISE.
- REMOVE ALL ABANDONED CONDUITS, JUNCTION BOXES, SUPPORTS, AND CABLES FROM ABOVE ACCESSIBLE CEILINGS INCLUDING, BUT NOT LIMITED TO, FIRE ALARM, TELECOMMUNICATIONS, CONTROL, AND POWER WIRING.
- CONTRACTOR TO MAINTAIN CONTINUITY OF CIRCUITS FEEDING DEVICES INDICATED TO REMAIN AND ANY CIRCUITS SERVICING DEVICES OUTSIDE THE PROJECT BOUNDARY.
- PROVIDE COVER PLATES WHERE MISSING ON EXISTING JUNCTION BOXES. CONTRACTOR TO VERIFY QUANTITY IN THE FIELD.
- PROVIDE FACE PLATES ON ALL J-BOXES ABANDONED IN FINISHED FLOORS, WALLS, OR CEILING. COORDINATE COLOR AND FINISH WITH ARCHITECT. CONTRACTOR TO VERIFY QUANTITY IN THE FIELD.

### KEYED NOTES

- L23** EXISTING FIXTURE TO REMAIN. INTERCEPT AND CONNECT FIXTURE TO EXISTING CIRCUIT SERVING NEAR BY PARKING LOT LIGHTS.
- L24** DISCONNECT AND REMOVE EXISTING SITE LIGHTING FIXTURE AND ASSOCIATED RACEWAY, BOXES, WIRE, AND CONCRETE BASE.
- L25** EXISTING FIXTURE TO REMAIN. MAINTAIN CONTINUITY OF CIRCUIT TO FIXTURE. MODIFY AND EXTEND EXISTING CIRCUIT AS REQUIRED.
- L26** EXISTING CIRCUITING SHOWN FOR REFERENCE. CONTRACTOR SHALL CONFIRM EXISTING CIRCUIT ROUTING AND LOCATION PRIOR TO DEMOLITION.
- L29** PROVIDE QUAZITE 22,500 LB. RATED, POLYMER CONCRETE 12"x12"Wx18"D HANDHOLE (PG1212HA00ELEC COVER WITH PG1212BA18BOX) OR APPROVED EQUAL.
- L45** DISCONNECT AND REMOVE EXISTING SITE LIGHTING FIXTURE, ASSOCIATED WIRE, AND CONCRETE BASE. IF EXISTING CIRCUIT IS REQUIRED TO MAINTAIN CONTINUITY TO ADJACENT LIGHT FIXTURES, PROVIDE HANDHOLE TO MAINTAIN CIRCUIT.



### 1 SITE PLAN - ELECTRICAL - DEMOLITION

1" = 20' 0"

Drawing Title:

ELECTRICAL SITE PLAN -  
DEMOLITION

Project No.: 04561.01 Checked by:

E0002