
J. CONNECT NON-EMERGENCY 277V LIGHTING ON THIS FLOOR TO PANEL 1NH1.
CONNECT SHADES TO NEAREST 120V PANEL.

- L01** PROVIDE CONDUIT SLEEVE(S) IN FOUNDATION WALL FOR WATER TIGHT SEAL OF ELECTRICAL SITE LIGHTING CONDUIT(S).
- L02** COORDINATE LOCATION OF PENDANT MOUNTED LIGHTS WITH OTHER TRADES, TO AVOID PIPING, DUCTWORK, AND OTHER EQUIPMENT.
- L03** THE LIGHTING CONTROLS IN THIS ROOM ARE CONNECTED TO THE BUILDING LIGHTING CONTROL SYSTEM.
- L04** PROVIDE PENDENT MOUNTED OCCUPANCY SENSORS MOUNTED AT SAME ELEVATION AS LIGHTS, AND WITH A CLEAR UNOBSTRUCTED VIEW OF THE AREA.
- L11** MOUNT STEP LIGHTS 2' AFF.
- L12** COORDINATE EXACT LOCATION OF ALL UNDERCABINET LIGHTS WITH CABINETS, COUNTER EQUIPMENT, AND ARCHITECT/ENGINEER. CONNECT TO STAND ALONE OCCUPANCY SENSOR OR BUILDING LIGHTING CONTROL SYSTEM SERVING ROOM.
- L13** PROVIDE SQUARE-D AUTOMATIC LOAD CONTROL RELAY (OR APPROVED EQUAL) TO CONTROL SWITCHED LIFE SAFETY LIGHTS IN THIS ROOM. CONFIGURE RELAY TO ENSURE LIGHTS ENERGIZE UPON LOSS OF NORMAL POWER. PROVIDE DIMMING RELAY WHERE A DIMMER CONTROLS THE LIGHTS.
- L27** CONNECT NEW LIGHTING IN EAB TO EXISTING CIRCUIT SERVING EAB LIGHTING.
- L28** MODIFY EXTEND EXISTING LIGHT FIXTURE TO PROVIDE A CONTINUOUS LINE OF LIGHT.
- L36** COORDINATE LOCATION OF ELEVATOR PIT LIGHTS AND SWITCHES WITH OTHER EQUIPMENT IN ELEVATOR PIT.

