

© Cannon Design 2015
All rights reserved. All other rights
are the property of the original
author or their respective
written authorization by The Cannon Corporation.
1/22/2016 2:44:03 PM

LIGHTING FIXTURE SCHEDULE 1 OF 3												
TYPE (I)	GENERAL DESCRIPTION, ACCESSORIES, AND APPLICATION	LIGHT SOURCE DATA			DRIVER/BALLAST			FIXTURE VOLTAGE	INPUT POWER	MANUFACTURER AND CATALOG NUMBER SERIES (V)	NOTES (VI)	
		TYPE (II)	QTY X WATTS/ LAMP	LED MODULE DELIVERED LUMENS	LED L70 RATED LIFE	CONTROL TYPE (III)	DIMMING ENABLED TO					
BA2	WALL MOUNTED, 4.75" WIDE X 5.5" DEEP X 2' LONG, 3000K LINEAR LED FIXTURE WITH DIRECT DISTRIBUTION, FLUSH OPAL LENS, AND REMOTE DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,000	50,000	0-10V DIM	100%	277	0 W 9 W	2,4,11	
BA3-8	WALL MOUNTED, 4.75" WIDE X 5.5" DEEP X 3'-8" LONG, 3000K LINEAR LED FIXTURE WITH DIRECT DISTRIBUTION, FLUSH OPAL LENS, AND REMOTE DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,875	50,000	0-10V DIM	100%	277	16 W	2,4,11	
BA13-6	WALL MOUNTED, 4.75" WIDE X 5.5" DEEP X 13'-6" LONG, 3000K LINEAR LED FIXTURE WITH DIRECT DISTRIBUTION, FLUSH OPAL LENS, AND REMOTE DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	6,750	50,000	0-10V DIM	100%	277	58 W	2,4,11	
BA20	WALL MOUNTED, 4.75" WIDE X 5.5" DEEP X 20' LONG, 3000K LINEAR LED FIXTURE WITH DIRECT DISTRIBUTION, FLUSH OPAL LENS, AND REMOTE DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	10,000	50,000	0-10V DIM	100%	277	86 W	2,4,11	
BB2	WALL MOUNTED, DECORATIVE LED SCIENCE WITH ACRYLIC SHADES AND INTEGRAL 0-10V DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,200	50,000	0-10V DIM	100%	277	20 W	1	
BC15	WALL MOUNTED, 4.75" WIDE X 5.5" DEEP X 15' LONG, 3000K LINEAR LED FIXTURE WITH INDIRECT DIRECT DISTRIBUTION, FLUSH OPAL LENS, AND REMOTE DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	15,000	50,000	0-10V DIM	100%	277	133 W	2,4	
CA	CEILING SURFACE MOUNTED, LOW PROFILE 1.5" WIDE X 3" TALL, 4" LONG LED LUMINAIRE WITH ACRYLIC LENS AND INTEGRAL 0-10V DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,600	50,000+	0-10V DIM	1%	277	18 W	1	
CB	CEILING SURFACE MOUNTED, 4" LONG, VAPORTIGHT ENCLOSED AND GASKETED, WET LOCATION RATED, 3,500K LED LUMINAIRE WITH INTEGRAL DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,728	60,000+	0-10V DIM	100%	277	61 W		
EA	1.5" DIAMETER, STAINLESS STEEL, 3,000K LED HANDRAIL WITH ASYMMETRIC DISTRIBUTION AND REMOTE CLASS II DIMMING DRIVERS.	LED	NA	FURNISHED WITH FIXTURE	205 LMFT	50,000	0-10V DIM	100%	277	78 W	1,8,12, 16	
EB	EPOXY POTTED, IP67, 3,000K LED TAPE LIGHT, MOUNTED WITHIN ALUMINUM CHANNEL, WITH 60 DEGREE OPTICS, 45 DEGREE MOUNTING CLIPS, AND REMOTE CLASS II DIMMING DRIVERS.	LED	NA	FURNISHED WITH FIXTURE	360 LMFT	50,000	0-10V DIM	100%	277	200 W	4,7,12	
EC	POWER PIPE MOUNTED, IP66, 3,000K LED SPOTLIGHT, WITH FLOOD DISTRIBUTION, SPOT FOCUS LENS, HONEYCOMB BAFFLE, FLUSH CAP, AND PIPE MOUNTED DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	600	50,000	0-10V DIM	100%	277	20 W	10	
ED	EPOXY POTTED, IP67, 3,000K LED TAPE LIGHT, MOUNTED WITHIN ALUMINUM CHANNEL, WITH 90 DEGREE OPTICS, 45 DEGREE MOUNTING CLIPS, AND REMOTE CLASS II DIMMING DRIVERS.	LED	NA	FURNISHED WITH FIXTURE	142 LMFT	50,000	0-10V DIM	100%	277	365 W	4,7,12	
EE	INGROUND, 2" LONG, IP68, WALK OVER RATED, 3,000K LED UPLIGHT, WITH ALUMINUM OPTICAL CHAMBER, PVC BLOCKOUT HOUSING, DIRECT VIEW OPTICS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE		75,000	0-10V DIM	100%	277	10 W	1	
EF36	36" TALL, 4" DIAMETER, 4,000K LED CAST ALUMINUM BOLLARD WITH TYPE III DISTRIBUTION, AND INTEGRAL DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,944	100,000+	0-10V DIM	100%	277	34 W	1,12	
EF42	42" TALL, 4" DIAMETER, 4,000K LED CAST ALUMINUM BOLLARD WITH TYPE III DISTRIBUTION, AND INTEGRAL DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,944	100,000+	0-10V DIM	100%	277	34 W	1,12	
EG3	CUSTOM ARM MOUNTED, 3,500K LED LUMINAIRE WITH TYPE III OPTICS, AND INTEGRAL DIMMING DRIVER MOUNTED ON 12" TALL, 5" DIAMETER, ROUND STRAIGHT ALUMINUM POLE WITH CONCRETE BASE.	LED	NA	FURNISHED WITH FIXTURE	4,800	50,000	0-10V DIM	100%	277	66 W	1,12	
EG5	SAME AS TYPE EG3 BUT WITH TYPE 5 OPTICS.	LED	NA	FURNISHED WITH FIXTURE	4,800	50,000	0-10V DIM	100%	277	66 W	1,12	
EG5R	SAME AS TYPE EG5 BUT WITH GFCI DUPLEX RECEPTACLE.	LED	NA	FURNISHED WITH FIXTURE	4,800	50,000	0-10V DIM	100%	277	66 W	1,12	
EH	RECESSED, 9" WIDE X 5" HIGH, IP66, 3,000K LED STEPLIGHT WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	396	50,000	0-10V DIM	100%	277	11 W	1	
EK	MULLION MOUNTED, 2.5" TALL, 3.5" WIDE, 4" LONG, 3000K LED SCIENCE WITH INTEGRAL DRIVER, UL LISTED FOR WET LOCATIONS.	LED	NA	FURNISHED WITH FIXTURE	2,400	50,000	0-10V DIM	100%	277	20 W		
EL	40" TALL, 7.5" DIAMETER, MARINE GRADE DIE-CAST ALUMINUM LED BOLLARD WITH 360 DEGREE DISTRIBUTION AND INTEGRAL 0-10V DIMMING DRIVER. EQUIPPED WITH GFCI AND KEYLESS DOOR.	LED	NA	FURNISHED WITH FIXTURE	1,600	50,000	0-10V DIM	100%	277	25 W	2,9	
PA4	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 4' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 40% UP / 60% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,000	60,000+	0-10V DIM	100%	277	52 W	1,5	
PA6	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 6' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 40% UP / 60% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	7,500	60,000+	0-10V DIM	100%	277	78 W	1,5	
PA8	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 8' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 40% UP / 60% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	10,000	60,000+	0-10V DIM	100%	277	104 W	1,5	
PA10	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 10' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 40% UP / 60% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	12,500	60,000+	0-10V DIM	100%	277	130 W	1,5	
PA12	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 12' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 40% UP / 60% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	15,000	60,000+	0-10V DIM	100%	277	156 W	1,5	
PB26-6	AIRCRAFT CABLE MOUNTED, 4" WIDE X 5" TALL X 26'-6" LONG, 3,000K LED DIRECT PENDANT, HIGH OUTPUT, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	16,900	100,000+	0-10V DIM	1%	277	249 W	2,8	
PC	CHAIN MOUNTED, 3,500K LED STRIPLIGHT, WITH DIFFUSING LENS AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,000	50,000	0-10V DIM	100%	277	38 W		
PD8	AIRCRAFT CABLE SUSPENDED, 4" WIDE X 5.5" TALL X 8' LONG, 3,000K LED LINEAR PENDANT, WITH ASYMMETRIC 60% UP / 40% DOWN DISTRIBUTION AND INTEGRAL DIMMING DRIVER. END MOUNTED ON ONE SIDE.	LED	NA	FURNISHED WITH FIXTURE	8,000	50,000	0-10V DIM	100%	277	71 W	1,8,11	
RA2	RECESSED 4" WIDE X 5" DEEP X 2' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,278	50,000+	0-10V DIM	100%	277	19 W		
RA3	RECESSED 4" WIDE X 5" DEEP X 3' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	1,920	50,000+	0-10V DIM	100%	277	28 W		
RA4	RECESSED 4" WIDE X 5" DEEP X 4' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,556	50,000+	0-10V DIM	100%	277	37 W		
RA6	RECESSED 4" WIDE X 5" DEEP X 6' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	3,834	50,000+	0-10V DIM	100%	277	56 W		
RA6-8C	RECESSED 4" WIDE X 5" DEEP X 6'-8" LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,260	50,000+	0-10V DIM	100%	277	63 W	11,15	
RA6C	RECESSED 4" WIDE X 5" DEEP X 6' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	3,834	50,000+	0-10V DIM	100%	277	56 W	11,15	
RA8	RECESSED 4" WIDE X 5" DEEP X 8' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,112	50,000+	0-10V DIM	100%	277	74 W		
RA9-4C	RECESSED 4" WIDE X 5" DEEP X 9'-4" LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	5,962	50,000+	0-10V DIM	100%	277	87 W	11,15	

LIGHTING FIXTURE SCHEDULE 2 OF 3												
TYPE (I)	GENERAL DESCRIPTION, ACCESSORIES, AND APPLICATION	LIGHT SOURCE DATA				DRIVER/BALLAST		FIXTURE VOLTAGE	INPUT POWER	MANUFACTURER AND CATALOG NUMBER SERIES (V)	NOTES (VI)	
		TYPE (II)	QTY X WATTS/ LAMP	LED MODULE DELIVERED LUMENS	LED L70 RATED LIFE	CONTROL TYPE (III)	DIMMING ENABLED TO					
RA10	RECESSED 4" WIDE X 5" DEEP X 10' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	6,390	50,000+	0-10V DIM	100%	277	94 W	FINELITE HP-4R-10-HO-3000K-277V-SC-GRID-DIM AXIS, PINNACLE, MARK	
RA12	RECESSED 4" WIDE X 5" DEEP X 12' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	7,668	50,000+	0-10V DIM	100%	277	112 W	FINELITE HP-4R-12-HO-3000K-277V-SC-GRID-DIM AXIS, PINNACLE, MARK	
RA12C	RECESSED 4" WIDE X 5" DEEP X 12' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	7,668	50,000+	0-10V DIM	100%	277	112 W	FINELITE HP-4R-12-HO-3000K-277V-SC-GRID-DIM-CORNER AXIS, PINNACLE, MARK	11,15
RA16	RECESSED 4" WIDE X 5" DEEP X 16' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	10,224	50,000+	0-10V DIM	100%	277	150 W	FINELITE HP-4R-16-HO-3000K-277V-SC-GRID-DIM AXIS, PINNACLE, MARK	
RA18	RECESSED 4" WIDE X 5" DEEP X 18' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	11,502	50,000+	0-10V DIM	100%	277	168 W	FINELITE HP-4R-18-HO-3000K-277V-SC-GRID-DIM AXIS, PINNACLE, MARK	
RA24	RECESSED 4" WIDE X 5" DEEP X 24' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	15,336	50,000+	0-10V DIM	100%	277	224 W	FINELITE HP-4R-24-HO-3000K-277V-SC-GRID-DIM AXIS, PINNACLE, MARK	
RA24C	RECESSED 4" WIDE X 5" DEEP X 24' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, GRID CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	15,336	50,000+	0-10V DIM	100%	277	224 W	FINELITE HP-4R-24-HO-3000K-277V-SC-GRID-DIM-CORNER AXIS, PINNACLE, MARK	11,15
RB4	RECESSED 4" WIDE X 5" DEEP X 4' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,556	50,000+	0-10V DIM	100%	277	37 W	FINELITE HP-4R-4-HO-3000K-277V-SC-SF-DIM AXIS, PINNACLE, MARK	3
RB6	RECESSED 4" WIDE X 5" DEEP X 6' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	3,834	50,000+	0-10V DIM	100%	277	56 W	FINELITE HP-4R-6-HO-3000K-277V-SC-SF-DIM AXIS, PINNACLE, MARK	3
RB7C	RECESSED 4" WIDE X 5" DEEP X 7' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	2,310	50,000+	0-10V DIM	100%	277	65 W	FINELITE HP-4R-7-HO-3000K-277V-SC-SF-DIM-CORNER	11,15
RB8	RECESSED 4" WIDE X 5" DEEP X 8' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,120	50,000+	0-10V DIM	100%	277	75 W	FINELITE HP-4R-8-HO-3000K-277V-SC-SF-DIM AXIS, PINNACLE, MARK	3
RB9C	RECESSED 4" WIDE X 5" DEEP X 9' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER. REFER TO PLANS FOR CORNER CONFIGURATION.	LED	NA	FURNISHED WITH FIXTURE	5,450	50,000+	0-10V DIM	100%	277	94 W	FINELITE HP-4R-9-HO-3000K-277V-SC-SF-DIM-CORNER	11,15
RB10	RECESSED 4" WIDE X 5" DEEP X 10' LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	6,390	50,000+	0-10V DIM	100%	277	94 W	FINELITE HP-4R-10-HO-3000K-277V-SC-SF-DIM AXIS, PINNACLE, MARK	3
RB17	RECESSED 4" WIDE X 5" DEEP X 17'-6" LONG, 3,000K LED DIRECT LUMINAIRE, HIGH OUTPUT, SPACKLE FLANGE FOR DRYWALL CEILING, FLUSH DIFFUSING LENS, AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	11,182	50,000+	0-10V DIM	100%	277	172 W	FINELITE HP-4R-17-6"-HO-3000K-277V-SC-SF-DIM AXIS, PINNACLE, MARK	3
RC4-7	RECESSED 6" APERTURE, 4'-7" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,000	60,000	0-10V DIM	100%	277	34 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-4'-7"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC5	RECESSED 6" APERTURE, 5' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,180	60,000	0-10V DIM	100%	277	38 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-5'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC5-6	RECESSED 6" APERTURE, 5'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,398	60,000	0-10V DIM	100%	277	41 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-5'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC6	RECESSED 6" APERTURE, 6' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,616	60,000	0-10V DIM	100%	277	45 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-6'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC7	RECESSED 6" APERTURE, 7' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	3,052	60,000	0-10V DIM	100%	277	53 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-7'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC8	RECESSED 6" APERTURE, 8' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	3,488	60,000	0-10V DIM	100%	277	60 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-8'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC9	RECESSED 6" APERTURE, 9' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	3,924	60,000	0-10V DIM	100%	277	68 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-9'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC10	RECESSED 6" APERTURE, 10' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,360	60,000	0-10V DIM	100%	277	75 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-10'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC10-6	RECESSED 6" APERTURE, 10'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,578	60,000	0-10V DIM	100%	277	79 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-10'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC12	RECESSED 6" APERTURE, 12' LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,232	60,000	0-10V DIM	100%	277	90 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-12'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC12-6	RECESSED 6" APERTURE, 12'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,450	60,000	0-10V DIM	100%	277	94 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-12'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC15-6	RECESSED 6" APERTURE, 15'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	6,758	60,000	0-10V DIM	100%	277	116 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-15'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC18-6	RECESSED 6" APERTURE, 18'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	8,066	60,000	0-10V DIM	100%	277	139 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-18'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC34-3	RECESSED 6" APERTURE, 34'-3" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	14,900	60,000	0-10V DIM	100%	277	257 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-34'-3"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC34-6	RECESSED 6" APERTURE, 34'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	15,000	60,000	0-10V DIM	100%	277	259 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-34'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC43-6	RECESSED 6" APERTURE, 43'-6" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	18,966	60,000	0-10V DIM	100%	277	326 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-43'-6"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC45-8	RECESSED 6" APERTURE, 43'-8" LONG, 3,000K LED WALL GRAZER, WITH MUD TRIM AND INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	20,000	60,000	0-10V DIM	100%	277	343 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-43'-8"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC66	RECESSED 6" APERTURE, 6'-3" LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	2,726	60,000	0-10V DIM	100%	277	47 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-6'-3"-N-REC/PR/GFW-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RC9-9	RECESSED 6" APERTURE, 9'-9" LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,251	60,000	0-10V DIM	100%	277	73 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-9'-9"-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG10	RECESSED 6" APERTURE, 10' LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,362	60,000	0-10V DIM	100%	277	75 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-10'-N-REC/PR/GFW-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG10-6	RECESSED 6" APERTURE, 10'-6" LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	4,580	60,000	0-10V DIM	100%	277	79 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-10'-6"-N-REC/PR/GFW-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG12	RECESSED 6" APERTURE, 12' LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	5,232	60,000	0-10V DIM	100%	277	90 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-12'-N-REC/PR/GFW-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG15	RECESSED 6" APERTURE, 15' LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	6,540	60,000	0-10V DIM	100%	277	105 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-15'-N-REC/PR/GMR-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG18-8	RECESSED 6" APERTURE, 18'-8" LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	8,142	60,000	0-10V DIM	100%	277	139 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-18'-8"-N-REC/PR/GFW-OP-WH PINNACLE, PRUDENTIAL	3,6,15
RCG20-6	RECESSED 6" APERTURE, 20'-6" LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	8,938	60,000	0-10V DIM	100%	277	154 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-20'-6"-N-REC/PR/GFW-OP-WH	3,6,15
RCG31	RECESSED 6" APERTURE, 31' LONG, 3,000K LED WALL GRAZER, GRID FLANGED, WITH INTEGRAL DIMMING DRIVER.	LED	NA	FURNISHED WITH FIXTURE	13,516	60,000	0-10V DIM	100%	277	233 W	GAMMALUX GPRG6B-ISOLED30-277-ZTV-31'-N-REC/PR/GFW-OP-WH	3,6,15