



1	DOMESTIC WATER PIPING IN THE CORRIDOR TO BE RUN AT THE BOTTOM OF THE STRUCTURAL CROSS MEMBERS. COORDINATE INSTALLATION AND ROUTING WITH OTHER TRADES ON THIS PROJECT.
2	DROP PIPING BELOW THE STRUCTURAL STEEL MEMBER. HOLD TIGHT TO BOTTOM OF STEEL.
3	THERMOSTATIC MIXING VALVE (TMV-2) SERVING THE EMERGENCY SHOWER TO BE LOCATED ABOVE THE ACCESSIBLE CEILING. REFER TO DRAWING P0403, DETAIL 4P0403 FOR PIPING DIAGRAM OF EMERGENCY SHOWER. VERIFY LOCATION AND PIPING CONFIGURATION PRIOR TO ROUGH-IN.
4	PROVIDE SHUT-OFF VALVES AT THE ENTRY TO EACH ROOM.
5	REFER TO DRAWING P0502, DETAIL 11P0502 FOR HOT WATER RETURN PIPING DIAGRAM.
6	WATER PIPING CONNECTION TO THERMOSTATIC MIXING VALVE (TMV-3) SERVING THE DECK MOUNTED EMERGENCY EYEWASH. REFER TO DRAWING P0403, DETAIL 4P0403 FOR PIPING DIAGRAM OF EMERGENCY EYEWASH. VERIFY LOCATION AND PIPING CONFIGURATION PRIOR TO ROUGH-IN.
7	LAB SINK WITH LAB FAUCET TYPE 'LF-1'.
8	WATER CONNECTION FOR UNDER COUNTER GLASS WASHER. COORDINATE LOCATION AND INSTALLATION WITH EQUIPMENT AND CASEWORK.
9	DOMESTIC WATER PIPING IN EACH ROOM TO BE RUN AS HIGH AS POSSIBLE TO AVOID CONFLICTS. COORDINATE INSTALLATION WITH OTHER TRADES ON THIS PROJECT PRIOR TO ROUGH-IN.
10	WATER CONNECTION FOR ICE MACHINE. COORDINATE LOCATION AND INSTALLATION WITH EQUIPMENT AND CASEWORK.
11	WATER CONNECTION FOR CLASS 1 BIOLOGICAL CABINET. COORDINATE LOCATION AND INSTALLATION WITH EQUIPMENT AND CASEWORK.
12	WATER CONNECTION FOR FLOOR MOUNTED AUTOCLAVE. COORDINATE LOCATION AND INSTALLATION WITH EQUIPMENT AND CASEWORK. PROVIDE WATER OUTLET BOX SIMILAR TO DW-1.
13	WATER CONNECTION FOR FUTURE FLOOR MOUNTED LAB EQUIPMENT. COORDINATE LOCATION AND INSTALLATION WITH EQUIPMENT AND CASEWORK. PROVIDE WATER OUTLET BOX SIMILAR TO DW-1.

