

Line No.	Line ID	Line Length (ft)	Line Size (in)	n-val Pipe	Invert Up (ft)	Invert Dn (ft)	Line Slope (%)	Gnd/Rim El Up (ft)	Gnd/Rim El Dn (ft)	HGL Up (ft)	HGL Dn (ft)	Cover Dn (ft)	Vel Ave (ft/s)	Defl Ang (Deg)	J-Loss Coeff	Minor Loss (ft)	Energy Loss (ft)	Known Q (cfs)	Flow Rate (cfs)	Capac Full (cfs)	
1	25 - 26	17.00	8	0.013	539.77	539.50	1.59	546.00	540.50	540.29	540.17	0.33	3.81	180.0	0.00	0.00	0.179	0.00	1.21	1.52	
2	26 - 27	13.00	6	0.013	539.85	539.10	5.77	545.18	546.00	540.90	540.29	6.40	6.16	110.3	1.00	0.59	0.605	1.21	1.21	1.35	
Project File: 25 26 27.stm												Number of lines: 2					Date: 05-13-2016				
NOTES: ** At critical depth																					