



November 17, 2016

Craig A. Miller Sr
Webster University
470 East Lockwood Ave
St. Louis, MO 63119-3194

Via Email

Re: Paric Corporation Project No. 15051
15051-Webster University Interdisciplinary Science Building
CP-047 - RFI#257 Lecture Hall 160 Floor Box Conduit Size

Dear Craig A. Miller Sr:

Paric Corporation proposes to complete the following additional work for the additive sum of Eight Hundred Thirty-Nine Dollars And Zero Cents \$839.00 .

This change will impact the scheduled completion date by 0 days.

- PCI-E-0046 (RFI#257 Lecture Hall 160 Floor Box Conduit Size), Total \$ 839.00

The owner contingency will be utilized for this change proposal. The originally specified 6 gang floor boxes will be turned over to the owner (less cover) if not utilized elsewhere on the project).

Proposed Change Proposal Total: \$839.00

If this change proposal meets with your approval, please sign and return this proposal for our records by November 23, 2016 at the latest. If accepted this scope will be incorporated into a change order.

Sincerely,

Paric Corporation

Jason Szachnieski
Project Manager

Accepted:

Date:

12/13/2016

Craig A. Miller Sr
Webster University

Declined:

Date:

Craig A. Miller Sr
Webster University

Paric Corporation

Page: 1 of 1
Date: 09-NOV-16
Time: 07:44 AM

PROJECT MANAGEMENT - CHANGE ITEM DETAIL REPORT 15051 - 15051-Webster University Interdisciplinary Science Building

Status: EXT EXT

CI Type	CI Number	Description	Estimated Amount	Quoted Amount	Final Amount	Due to Owner	Notes	Date Sent	Date Received	Date Closed	Budgeted Amount	Billing Amount	Owner CO
EXT	PCI-E-0046	RFI#257 Lecture Hall 160 Floor Box Conduit Size			839.00	09-NOV-16					839.00	839.00	
Vendor Name			Description										
	Guarantee Electrical Construction Co	15051	16000.001 S	Electrical Sub	800.00		RFI#257 Lecture Hall 160 Floor Box Conduit Size	Swap out the (2) 6 gang floor boxes in the Level 1 Auditorium to (2) 8 gang floor box per RFI#257 response and GECCO quote dated 10/19/16. Add \$800					
	PARIC	15051	23150.005 M	Contractor Default Insurance (1.25%)	10.00		RFI#257 Lecture Hall 160 Floor Box Conduit Size	Contractor Default Insurance					
	PARIC	15051	23300.001 F	Fee (2.5%)	20.00		RFI#257 Lecture Hall 160 Floor Box Conduit Size	Contractor Fee					
	PARIC	15051	23100.001 M	Risk Management (1.1%)	9.00		RFI#257 Lecture Hall 160 Floor Box Conduit Size	Risk Management					
Total For EXT			0.00	0.00	839.00						839.00	839.00	
Grand Total:			0.00	0.00	839.00						839.00	839.00	

END OF REPORT

Report Parameters

Job:	15051	Project Code:	
From Change Order:		Run Date:	09-NOV-16
To Change Order:		Run Time:	07:44 AM
Status Code:		Operator:	JAS39SZA
Report Type:	DETAIL	Posting Status:	Unposted CI
Print Notes:	Y	Report Code:	PM5000
Group By:	STATUS		



ELECTRICAL CONSTRUCTION

3415 Bent Avenue St. Louis, MO 63116 ph (314) 772-5400 fx (314) 772-2526 web gecoc.com

PROPOSED CHANGE ORDER

Client Address:

PARIC CORPORATION
Contact: Jason Szachnieski
77 W PORT PLAZA # 250
ST. LOUIS, MO 63146

CCN #

Date:

Project Name:

Project Number:

Page Number:

SWAP OUT OF 6 GANG FLOOR BOX

10/19/2016

WEBSTER GROVES ISB BUILDING

WEBSTER GROVES ISB BUILDING

1

Work Description

WEBSTER ISB BUILDING CHANGE FLOOR BOXES IN AUDITORIUM

Description of work

- 1) Provide (2) 8 gang floor boxes EFB8S-OG in Lieu of the specified 6 gang.
- 2) Pricing based on utilizing the original floor box cover.

Base bid shall increase by: \$ 800.00

We reserve the right to correct this quote for errors and omissions.

This quote covers direct costs only and we reserve the right to claim for impact and consequential costs.

This price is good for acceptance within 30 days from the date of receipt.

We request a time extension of 20 days.

We will supply and install all materials, labor, and equipment.

Itemized Breakdown

Description	Qty	Total Mat.	Total Hrs.
WM EBF8S-OG 8 GANG FLOOR BOX	2	596.26	0.00
DOUBLE HANDLING	1	0.00	1.00
Totals	3	596.26	1.00

Summary

General Materials	596.26
Material Total	596.26
FOREMAN	81.17
FREIGHT	50.00
Subtotal	727.43
Markup	72.74

ORIGINAL

PROPOSED CHANGE ORDER

Client Address:

PARIC CORPORATION
77 W PORT PLAZA # 250
ST. LOUIS, MO 63146

CCN #

Date:

Project Name:

Project Number:

Page Number:

SWAP OUT OF 6 GANG FLOOR BOX

10/19/2016

WEBSTER GROVES ISB BUILDING

WEBSTER GROVES ISB BUILDING

2

Summary (Cont'd)

Subtotal	800.17
Adjustment #1	-0.17
Final Amount	\$800.00

CONTRACTOR CERTIFICATION

Name: _____

Date: _____

Signature: _____

I hereby certify that this quotation is complete and accurate based on the information provided.

CLIENT ACCEPTANCE

CCN #: SWAP OUT OF 6 GANG FLOOR BOX

Final Amount: \$800.00

Name: _____

Date: _____

Signature: _____

Change Order #: _____

I hereby accept this quotation and authorize the contractor to complete the above described work.

ORIGINAL



PARIC CORPORATION
77 Westport Plaza Suite 250
St. Louis, MO 63146
TEL: 636-561-9500
FAX: 636-561-9501

REQUEST FOR INFORMATION **DATE:** August 25, 2016 **NO.:** RFI-257

To: Cannon Design

Attn: Kelvin Patel

From: Paric Corporation

Requested By: Joe Voypick

Project Name: 15051-Webster University Interdisciplinary Science Building Project No.: 15051

Subject: Lecture Hall 160 Conduit Size for EF6S OG Floor Box

Response Required By: September 01, 2016

Drawing / Spec Reference:

Information Requested:

Telecom Drawing T0101.B note # 18 calls for a 1 1/2" conduit from the floor box (EF6S - OG) to above accessible ceiling. The floor box specified only has a 1" and 1 1/4" knock outs. Can we run 1 1/4" in lieu of 1 1/2" please advise ?

Response:

Based on 9/29/16 correspondence with the Owner, AV consultant, contracting team, and design team, the contractor shall replace the specified 6 gang floor box with an 8 gang floor box (EFB8S-OG), 2 gangs power, 1 gang data, 4 gangs A/V (same side) and 1 gang spare. This floor box will accept up to a 2" conduit, provide the specified 1-1/2" conduit. The final electrical requirements will be reviewed when final AV design documents are made available to the MEP design team.

ARCHITECT'S RESPONSE:

This information is provided as an interpretation of the Contract Documents for implementation. It is not an authorization for change to the Contract Sum or Contract Time. If this information results in a claim for a change to the Contract, the Contractor shall notify the [Construction Manager][Architect] of a change through the change process.

Answered By: Bill Shaw

Date: 09/29/2016

