



March 02, 2017

Craig A. Miller Sr
Webster University
470 East Lockwood Ave
St. Louis, MO 63119-3194

Via Email

Re: Paric Corporation Project No. 15051
15051-Webster University Interdisciplinary Science Building
CP-072 - Door Hardware Changes

Dear Craig A. Miller Sr:

Paric Corporation proposes to complete the following additional work for the deducted sum of Negative Nine Thousand One Hundred Sixty-Four Dollars And Zero Cents (-\$9,164.00).

This change will impact the scheduled completion date by 0 days.

- PCI-E-0074 (Door Hardware Changes), Total \$ -9,164.00

The owner contingency shall be utilized for this change order.
Proposed Change Proposal Total: -\$9,164.00


If this change proposal meets with your approval, please sign and return this proposal for our records by March 02, 2017 at the latest. If accepted this scope will be incorporated into a change order.

Sincerely,

Paric Corporation


Jason Szachnieski
Project Manager

Accepted:


Date: 3/2/2017
Craig A. Miller Sr
Webster University

Declined:

Date: _____
Craig A. Miller Sr
Webster University

Paric Corporation

PROJECT MANAGEMENT - CHANGE ITEM DETAIL REPORT

15051 - 15051-Webster University Interdisciplinary Science Building

Page: 1 of 1

Date: 02-MAR-17

Time: 02:37 PM

Status: EXT EXT

CI Type	CI Number	Description	Estimated Amount	Quoted Amount	Final Amount	Due to Owner	Notes	Date Sent	Date Received	Date Closed	Budgeted Amount	Billing Amount	Owner CO
EXT	PCI-E-0074	Door Hardware Changes			-9,164.00	19-JAN-17					-9,164.00	-9,164.00	
Vendor Name		Description											
	Paric Corp - Self Perform	15051	06200.001 S	Finish Carpentry Sub	-7,277.00	Door Hardware Changes	Provide door hardware changes per Paric Self Perform COR#10 dated 1/11/17 - Deduct \$(7,277)						
	NGG Ltd., Incorporated	15051	08400.205 S	Interior Glass	-1,458.00	Door Hardware Changes	Delete door 140.1 and related hardware per NGG change order number 10047-012. Deduct \$(1,458)						
	PARIC	15051	23150.005 M	Contractor Default Insurance (1.25%)	-109.00	Door Hardware Changes	Contractor Default Insurance						
	PARIC	15051	23300.001 F	Fee (2.5%)	-224.00	Door Hardware Changes	Contractor Fee						
	PARIC	15051	23100.001 M	Risk Management (1.1%)	-96.00	Door Hardware Changes	Risk Management						
Total For EXT			0.00	0.00	-9,164.00						-9,164.00	-9,164.00	
Grand Total:			0.00	0.00	-9,164.00						-9,164.00	-9,164.00	

END OF REPORT

Report Parameters

Job:	15051	Project Code:	
From Change Order:		Run Date:	02-MAR-17
To Change Order:		Run Time:	02:37 PM
Status Code:		Operator:	JAS39SZA
Report Type:	DETAIL	Posting Status:	Unposted CI
Print Notes:	Y	Report Code:	PM5000
Group By:	STATUS		

Webster ISB
PARIC SELF PERFORM
COR 10 - Door Hardware Changes
1/11/2017

	UNITS	RATE	TOTAL	
RFI-378 - Changes in door hardware per Jim Ward.				
*Material upcharges from Negwer for HMD/WDD hardware only	1	\$ 1,725.00	\$1,725.00	= \$345/ea
*Upcharge in labor for Doors 144/401/406/434/434 (0.5 MH/EA)	2.5	\$ 62.00	\$155.00	
*Final electrical hookups and programming by others.				
Exterior Hardware Changes per 12/03				
*Material upcharges from Negwer for HMD/WDD hardware only	1	\$ 1,844.00	\$1,844.00	
*Upcharge in labor for Doors X188/X192.2/X178.2 (0.25 MH/EA)	0.75	\$ 62.00	\$46.50	
*Upcharge in labor for Door X160.3 (0.15 MH/EA)	0.15	\$ 62.00	\$9.30	
Hardware for Changed Door 140.1 to WDD ILO ALD				
*Material upchage from Negwer dated 12/11/16	1	\$ 953.00	\$953.00	
*Install Door 140.1 (1 MH)	1	\$ 62.00	\$62.00	
*Install Door Heading 18A (0.5 MH)	0.5	\$ 62.00	\$31.00	
			SUBTOTAL COR=	\$4,826
			Small Tools and Consumables 4%=	\$193
			10% OH&P=	\$502
			SUBTOTAL =	\$5,521
Credit for Removing Supply of Primus Cores per Webster Direction	1	\$ (12,798)	\$	(12,798)
			TOTAL COR =	\$ (7,277)



49 Airport Rd. | St. Louis, MO 63135 | 800-456-6540

Date: 03-02-2017

To: Paric
Attn: Matt Horton
Phone: 636 561-9841
E-mail: mrhorton@paric.com

Project: Webster ISB – RFI-378 Revised
Location: St. Louis, MO.
Architect: Cannon Design

Quoted By: Darryl Stith
Phone: (314) 595-4409
E-Mail: dstith@negwer.com

We propose to furnish the following materials, delivery included and tax excluded, for the above referenced projects. Based on RFI-378 Revision

114,116

Change lock to ND53 in lieu of ND70

N/C

144,401,406,432,434

Change lock to Alarm Lock DL2700 in lieu of ND53

\$ 1,725.00

364,412,414,441

Change lock to ND70 in lieu of ND53

N/C

- **ALTERNATE PRICE FOR COMPARABLE SCHLAGE CO100 LOCKSET WOULD BE \$1,100.00 add in lieu of ND53. CUT SHEET ATTACHED**

*** Written authorization to proceed is required to place materials on order.

General Qualifications-

*** Doors 291.1,291.2,276.1,284.1,284.2 and 174 are all Aluminum Storefront with hardware being supplied by door manufacturer.

=====

TOTAL FOR ABOVE MATERIALS AS LISTED

\$ 1,725.00 (tax not included)

All Pricing is based on Standard Lead Times approx. 6 weeks upon returned approved submittals. Please Contact Negwer Door Systems if material is time sensitive.

Conditions: Sales tax NOT included. Tax rate 9.113%. Payment terms, Net 30 days, pending credit approval. Quote is valid for 30 days. Material ONLY, no labor included.

Szachnieski, Jason

From: James Ward <wardji@webster.edu>
Sent: Wednesday, March 1, 2017 3:16 PM
To: Szachnieski, Jason
Subject: FW: Push Button Locks

FYI

From: Martin Scrogham [<mailto:martinscrogham53@webster.edu>]
Sent: Friday, February 24, 2017 4:09 PM
To: 'James Ward' <wardji@webster.edu>
Cc: johnbrennan98@webster.edu
Subject: RE: Push Button Locks

Hey Jim,

It's not Schlage, made by a company called Alarm Lock. Model # is Trilogy DL2700, we buy them from door services.

From: James Ward [<mailto:wardji@webster.edu>]
Sent: Friday, February 24, 2017 11:15 AM
To: Matt Scrogham <martinscrogham53@webster.edu>
Subject: Push Button Locks

Matt,

John said that you are purchasing and installing the Schlage Trilogy DL2700 push button lock on campus where needed. Where are you buying these locks? I'm requesting that these be purchased for the adjunct offices in the ISB.
Jim

Trilogy® T2: DL2700

#1 most popular standalone pushbutton cylindrical lock

Durable electronic digital locks available in indoor and outdoor models



- **Grade 1 Durability.** Dependable lockset with rugged clutch mechanism, plus **vandal-proof all metal keypad.**
- **Multi-level user codes:** Master, 10 managers, 90 users, 3 service codes
- **Up to 100 different user codes** (3-5 digits)
- **100% keypad programmable** with a fingertip
- **Individual, group or total user lockout codes**
- **Easy passage mode** by manager and/or master
- **Easy to install in about an hour,** retrofits cylindrical knobsets and digital locks using slightly modified ANSI 161 Series Prep
- **Standalone battery operated;** 5 AA batteries rated at 200,000 cycles
- **Non-handed** for easy installation and versatility
- **2-wire remote override**
- **Visual and audible entry indicators**
- **WP Models for weatherproof performance,** water-sealed for use inside and out, with operational temperature range of +151°F to -31°F (+66°C to -35°C)

(Note: all Trilogy models are available in WP weatherproof and non-WP standard models for interior doors.)



Ideal for schools, healthcare, pharmacies, offices, retail and airports.



ALARM LOCK

OPERATION: Clutch mechanism permits turning lever without retracting latch and reduces stress on lock bodies and spindle. Outside lever free turning in locked position. Entering access code, key bypass, or remote bypass will allow lever to retract latch. Inside lever always instant egress.

DOOR THICKNESS: 1 5/8" to 1 7/8". Other thicknesses. Please consult Alarm Lock.

BACKSET: 2 3/4" Standard. 2 3/8" backset also available.

KEYPAD: All metal, 12 button programmable for multi-level access functions including group or individual user codes, master and management codes, passage and emergency or service code, lockout and remote override capability and allowable entry time from 5 to 20 seconds. 4 Different keypad tones and keypad may be silenced.

STANDARD KEY OVERRIDE CYLINDERS: Solid brass 6 pin tumbler cylinder pinned 5, SC1 keyway, furnished in all locks. Additional tailpieces included: HW580 fits Schlage, Corbin/Russwin CL, Sargent 480 Series, ASSA65-611; Model HW620 fits Ilco and Lori cylinders.

INTERCHANGEABLE CORE MODELS: Accepts 6 & 7 Pin Cylinders from: Best, Arrow, KSP, Medeco Keymark & Kaba Peaks. Also available IC Core models for Yale, Medeco, Sargent, Corbin/Russwin CL and Schlage. Alarm Lock Tailpiece is supplied; IC Core is not included.

LATCHBOLT: UL Listed, fire rated, 3 hours, 1/2" throw, solid brass, deadlocking. Reversible. Adjustable front for flat or beveled doors.

STRIKE: 1 1/8" x 2 3/4" T strike & 1 1/4" x 4 7/8" ASA strike included. With screws for wood or metal jambs.

LATCH FRONT: 1 1/8" x 2 1/4" wrought brass or stainless steel.

HANDING: Non-handed.

FINISHES: US3 polished brass, US26D satin chrome, 10B Duronodic.

POWER: 5 AA alkaline batteries are now rated at 200,000 cycles, supplied. Audible low battery alert, visual and audible entry indicators, unique Flex Drive® motor.

DOOR PREP: Standard ANSI 161 Series Prep, modified by adding additional through-bolt holes.

COMPLIANCES: Grade I, heavy duty cylindrical lockset, UL listed and FCC certified. ADA compliant leversets.

Trilogy is available in many additional models, including those for outdoors, and/or Mortise, plus with Prox ID card reader, dual-sided keypads, wireless lock networks and more.

Some other Trilogy Options:

DL2700LD: With LocDown™ Indicator Light Bar & Keyfob


DL2800: Economical Audit Trail Security Lock provides keyless entry for up to 200 users

DL1200/1300: Models for Narrow Stile Glass Doors

DL/PDL5300: Dual-Sided PIN/Prox Lock with audit/trail

DL3000, DL3200: Advanced digital electronic door lock with audit trail

See Trilogy Network™ Locks for wireless network capabilities



DL 27 00 WP IC /26D -Y

Model & Series:
DL27 = Trilogy T2 Series

Trim:
00 = Lever
75 = Regal Trim Lever

Exterior / Interior Use:
WP = Weatherproof for exterior use
(Note: No "WP" indicates standard, interior use.)

Cylinder:
IC = Standard Interchangeable Core
Prep for Best, Falcon, Arrow, KSP
(Note: No "IC" indicates standard K.O. cylinder.)

Finish:
/3 = US3 Polished Brass
/26D = US26D Satin Chrome
/10B = Duronodic

Special Order IC Prep:
-Y = Yale
-M = Medeco
-R = Sargent
-C = Corbin/Russwin
-S = Schlage


UL CE




Lever set in US3
DL2700/3



With IC Core in 26D
DL2700IC/26D



Secure battery
compartment on
inside door



DL2775/26D



ALARM LOCK

Alarm Lock Systems, LLC (A Division of NAPCO Security Technologies, Inc.)

333 Bayview Ave, Amityville, New York 11701

1-800-ALA-LOCK • ++ 631.842.9400 • Fax 631-789-3383

www.alarmlock.com • salesinfo@alarmlock.com

Trilogy, Network and LocDown are trademarks of NAPCO Security Technologies. Other trademarks listed are those of their respective companies.

Preliminary specifications subject to change without prior notice. © 2016.3 ALA129

CP-72
E-6074

Webster ISB
PARIC SELF PERFORM
COR 10 - Door Hardware Changes
1/11/2017

RFI-378 - Changes in door hardware per Jim Ward.

- *Material upcharges from Negwer for HMD/WDD hardware only
- *Upcharge in labor for Doors 114/116 (.3 MH/EA)
- *Upcharge in labor for Doors 144/401/406/434/434 (0.5 MH/EA)
- *Final electrical hookups and programming by others.

Exterior Hardware Changes per 12/03

- *Material upcharges from Negwer for HMD/WDD hardware only
- *Upcharge in labor for Doors X188/X192.2/X178.2 (0.25 MH/EA)
- *Upcharge in labor for Door X160.3 (0.15 MH/EA)

Hardware for Changed Door 140.1 to WDD ILO ALD

- *Material upcharge from Negwer dated 12/11/16
- *Install Door 140.1 (1 MH)
- *Install Door Heading 18A (0.5 MH)

UNITS	RATE	TOTAL	
1	\$ 4,556.00	\$4,556.00	
0.6	\$ 62.00	\$37.20	Remove
2.5	\$ 62.00	\$155.00	
SUBTOTAL COR=		\$7,694	
Small Tools and Consumables 4%=		\$308	
10% OH&P=		\$800	
SUBTOTAL =		\$8,802	
Credit for Removing Supply of Primus Cores per Webster Direction	1	\$ (12,798.00)	\$ (12,798.00)
TOTAL COR =		\$ (3,196.00)	



PARIC CORPORATION
77 Westport Plaza Suite 250
St. Louis, MO 63146
TEL: 636-561-9500
FAX: 636-561-9501

REQUEST FOR INFORMATION **DATE:** December 12, 2016 **NO.:** RFI-378

To: Cannon Design

Attn: Kelvin Patel

From: Paric Corporation

Requested By: Devin Gates

Project Name: 15051-Webster University Interdisciplinary Science Building

Project No.: 15051

Subject: Door hardware requests from Webster University

Response Required By: December 19, 2016

Drawing / Spec Reference:

Information Requested:

Jim Ward from Webster University has the following questions/comments before we can release hardware for production;

1. Why is 291.2 an exit only door? 291.1 shows both.

2. 276.1 shows card access and a storefront walk, why is this different than 291?

3. 284.1 and 284.2 should have classroom locks on both doors.

4. Why are the prep rooms keyed different from the hallway? These should all match. OK

AT RESEARCH LAB, 291, 291.1 IS A CARD ACCESS DOOR TO CONTROL ACCESS AND 291.2 IS EXIT ONLY ALSO TO MAINTAIN ACCESS CONTROL. THIS IS ALSO TYPICAL OF 276.2, AND 283.2. WU ADVISE WHAT IS DESIRABLE

276.1 AND 291.1 ARE THE SAME: CARD ACCESS W/ STORAGE ROOM FUNCTION LOCK (NO ENTRY UNLESS CARD OR KEY)

284.1 AND 284.2 BOTH HAVE CLASSROOM LOCKS

Jim Ward proposes lock function changes per below;

174 Teaching Kitchen Change to Keypad OK - SEE ATTACHED/ BELOW SPEC

114 Mock Exam Room Change to ND53 OK

116 Mock Exam Room Change to ND 53 OK

144 Adj. Office Change to Keypad OK - SEE ATTACHED SCHLAGE AD-200 - HARDWARE CONSULTANT BELIEVES THIS IS WEBSTER'S PREFERENCE
Schlage Electrified Office Lock AD-200-CY-50-KP-RHO-TD-626 with a Primus 20-740 core.

401 Adj. Office Change to Keypad

406 Adj. Office Change to Keypad

432 Adj. Office Change to Keypad

434 Adj. Office Change to Keypad

364 Sm. Meeting Room Change to ND70 OK

412 Testing Change to ND70 OK

414 Testing Change to ND70 OK

441 Sm Meeting Room Change to ND70 OK

Suggestion: Please advise if these changes will be acceptable or advise as to what cannot be changed.

Response: SEE ABOVE

Answered By: LYNN GROSSMAN

Date: 12.15.16

SCHLAGE

AD-200

Standalone electronic lock



Overview

AD Series electronic locks from Schlage are designed to be modular and provide more options to choose from, more functionality in the lock and more compatibility with existing systems. Its patent-pending modular design allows the lock to be customized to fit the needs of an application now, and can change to meet future needs without removing it from the door.

Factory orderable options include choices of credential readers, chassis type, locking functions, power options, lever styles and finishes. It also offers a wide selection of features that can be configured in the field to customize your openings.


The AD-200 is a simple, economical solution if no access control system currently exists in facility, or for openings that don't require the control of a networked solution. The AD-200 is easily upgradable to a networked lock if requirements change in the future.

On all AD Series standalone locks, Schlage has built in many of the incremental features needed in a networked system such as request-to-exit and -enter sensors, interior cover tamper guard, as well as the door position switch. This way, if the customer chooses to network this opening in the future, all the components will be there to make the transition an easy one.

Features and benefits

- Security that's more intelligent and convenient than traditional mechanical locking devices
- Audit trail reports that allow you to track usage and events
- Update users and access rights at the lock using the keypad or handheld device
- The ability to upgrade to a networked solution without removing the lock from the door
- Available in cylindrical, mortise, mortise deadbolt and exit trim
- Compatible with major brands of master key systems and exit devices
- Now available with magnetic swipe reader
- AD Series with multi-technology readers are NFC compatible¹
- FIPS 201-1 compliant when applied with the FIPS multi-technology plus keypad reader module (FMK)
- ANSI/BHMA A156.25, ANSI/BHMA Grade 1, UL 294, UL 10C, FCC Part 15, ADA, RoHS

¹ Please refer to apt/Qmobile compatibility chart for a list of certified devices



AD-200 electronic lock specifications

Users	Up to 5000
Audits	Up to 5000
Credential verification time	≤ 1 second ¹
Visual/audible communications	Tri-colored LEDs and audible indicators (field configurable)
System interface	Handheld Device (HHD)
Power supply	4AA, 8AA, 12 VDC or 24 VDC
Voltage range	4 VDC to 26 VDC
Max current requirement	Up to 250 mA
Battery life	Up to 2 yrs with 4AA
Operating temperature - exterior	-31° to 151°F (-35° to 66°C)
Operating temperature - interior	32° to 120°F (0° to 49°C) (battery)
Operating humidity	0 - 100% non-condensing
Certifications	ANSI/BHMA A156.25, ANSI/BHMA Grade 1, UL 294, UL 10C, FCC Part 15, ADA, RoHS
Accessories	Handheld Device (HHD)

Functions

- Classroom/storeroom²
- Office^{2,3}
- Privacy³
- Apartment³

Standard status signals

- Lock/unlock status
- Mechanical key override
- Battery status

Schlage Utility Software on Handheld Device

The Schlage Utility Software (SUS) on the Handheld Device (HHD) provides an easy way to manage people, audits and locks for simple access control management.

Schlage Utility Software

- Initialize lock and accessories
- Field configure devices
 - Credential reader formats
 - Lock function
 - Unlock period
 - Failure mode
 - Audible alarm on/off
- Service and diagnostics
 - Battery status
 - Validate hardware and software revision
 - Troubleshooting status signals
- New device template simplifies configuration

HHD

- 3.5 in LCD display
- Touch screen/keypad backlit
- 32-bit processor
- OS: Windows Mobile 5.0
- Memory: 128 MB RAM/ 256 MB ROM
- Battery: rechargeable 3.7 v, 1,230 mAh, Li-ion
- Dimensions: 5.3" x 2.9" x 0.7" (13.5 cm x 7.3 cm x 1.8 cm)
- Weight: 0.42 lbs (190 g)
- 4 ft (1.2 m) drop to steel surface, 2 drops per 6 sides



The HHD connects with AD Series and CO Series locks and accessories via the USB interface

HHD is also compatible with CM, CL, VIP, WA and KC2 Series locks in a serial cable connection.

¹ Verification time is dependent on size of user base

² Classroom/storeroom and office function not available with mortise deadbolt option.

³ Not available on exit trim

Mechanical specifications

Chassis	Cylindrical	Mortise	Exit trim
Handing	Handed to order, field reversible		
ANSI standard (Meets or exceeds)	A156.25 A156.2 Series 4000 Grade 1	A156.25 A156.13 Series 1000 Grade 1	A156.25 A156.3
Door thickness	1 3/4" standard, 1 3/8" to 2 3/4" optional (available in 1/8" increments)		
Backset	Standard: 2 3/4" Optional: 2 3/8", 3 3/4", 5"	2 3/4" only	Defined by exit device
Latch bolt	Standard: 1/2" throw Optional: 3/4" throw	Standard: 3/4" throw Optional: 1" throw on mortise deadbolt	Provided by exit device
Levers	Pressure cast zinc, plated	Steel, plated	Steel, plated
Strike	Standard: 1 3/16" lip, ANSI, 1 1/4" x 4 7/8" Optional: Additional configurations available please see price book		Provided by exit device
Cylinder and keys	Schlage 6-pin Everest 29 S123 keyway cylinder with two patented keys standard Additional options available including Standard, SFIC, FSIC and competitor brands		

Multi-technology reader specification

Frequency	125 kHz proximity and 13.56 MHz smart card
Standards	ISO standard 15693 and ISO 14443
Maximum read range	Up to 1.25" on 125 kHz proximity, up to 0.75" on 13.56 MHz smart card
125 kHz compatibility	Schlage Proximity, XceedID™ Proximity, HID® Proximity, GE/CASI ProxLite®, AWID® Proximity, LenelProx®
13.56 MHz compatibility	Schlage MIFARE® Secure Sector, XceedID™ MIFARE® Secure Sector, aptiQ™ smart cards using MIFARE DESFire™ EV1 with PACSA; PIV and PIV-3.4
13.56 MHz compatibility (serial number only)	DESFire® CSN, HID iCLASS® CSN, Inside Contactless PicoTag® CSN, MIFARE®, MIFARE DESFire™ EV1, ST Microelectronics® CSN, Texas Instruments Tag-It® Serial Number, Phillips I-Code® CSN
125 kHz compatible XceedID credentials	125 kHz clamshell, ISO card, ISO card with magnetic stripe, keyfob, and PVC disk (7000 Series)
13.56 MHz compatible aptiQ™ credentials	aptiQ™ smart cards using MIFARE® in clamshell, ISO card, ISO card with magnetic stripe, Keyfob and PVC Patch (9000 Series); aptiQ™ smart cards using MIFARE DESFire™ EV1 in clamshell, ISO card, ISO card with magnetic stripe, keyfob, and PVC disk (8000 Series)
Certifications/standards	FCC, UL 294 Listed, ISO standard 15693, and ISO standard 14443
Style/layout	Option for 12 button, 3x4 matrix backlit keypad

¹ Request-to-exit switch optional for future network migration

² Narrow design and reversible rim exits not compatible

³ 75 bit output format default. Configurable to other output formats. Check with access control provider for specific support.

⁴ Smart card functionality dependent on access control software

⁵ Please refer to aptiQmobile compatibility chart for a list of certified devices

AD Series exit trim

Installed with a universal mounting plate, the AD Series exit trim is compatible with the following exit devices:

- Von Duprin 98/99 & 98/99XP¹
Rim, surface vertical rod, mortise.
Concealed vertical cable and concealed vertical rod on metal doors only.
- Von Duprin 22/22F¹
Rim, surface vertical rod
- Falcon 25¹ - Rim
- Sargent® 80² Series - Rim
- Precision™ 21 Rim
2100 converts to 21 with Precision's BP21 kit
- Corbin Russwin® 5000 Series - Rim
- Yale® 7000 - Rim
- Dorma® 9300 - Rim

Benefits of AD Series multi-technology readers:

- Reads both proximity (125 kHz) and smart (13.56 MHz) technologies with single device
- AD Series multi-technology readers are NFC compatible⁵
- Allows end user to migrate to more secure credentials over time and as budgets permit

Additional readers

Magnetic stripe

- Now available with choice of insertion or swipe style readers
- Triple track reader (1, 2 or 3), field configurable
- ABA, ISO76XX Standard
- Option for 12 button, 3x4 matrix backlit keypad

Keypad

- Backlit keypad
- 12 button, 3x4 matrix

Available AD Series reader modules



Multi-technology

- Proximity
- Smart card



KEYPAD
FIPS 201-1 compliant option available (FMK)



Multi-technology

- Proximity
- Smart card



Magnetic stripe (insertion)

- KEYPAD



Magnetic stripe (insertion)



Magnetic stripe (swipe)

- KEYPAD



Magnetic stripe (swipe)



Keypad

Ordering information

Available through one of our GSA schedule 84 approved distributors; BAA options available

AD-200-CY-70-MG-SPA-626-PD-S123-RH-4B-13-049-10-025-1 3/4

Series	Class	Chassis	Function	Reader	Lever style	Finish	Lever cylinder	Keying type	Handing	Battery	Backset and latch	Strike	Door thickness
1	2	3	4	5	6	7	8	9	10	11	12	13	14

Selections correspond with the numbers above

Standards options are indicated in bold. See price book for specific configuration options.

3	Chassis
CY	Cylindrical
MS	Mortise
MD	Mortise deadbolt
993R	Exit trim – Rim/CVC/CVR
993S	Exit trim – SVR
993M	Exit trim – mortise
993DT	Non-functioning dummy trim for exit
4	Function
70	Classroom/storeroom
50	Office
40	Privacy
60	Apartment
5	Reader
KP	Keypad
MG	Magnetic stripe (insertion)
MGK	Magnetic stripe + keypad (insertion)
MS	Magnetic stripe (swipe)
MSK	Magnetic stripe + keypad (swipe)
MT	Multi-technology (125kHz and 13.56 MHz)
MTK	Multi-technology + keypad (125kHz and 13.56 MHz)
FMK	FIPS 201-1 compliant multi-technology + keypad (125 kHz and 13.56 MHz)
DT	Dummy trim

6	Lever
SPA	Sparta
RHO	Rhodes
ATH	Athens
TLR	Tubular
Available with knurled surface	
7	Finish
626	Satin chrome
605	Bright brass
606	Satin brass
612	Satin bronze
619	Satin nickel
625	Bright chrome
643e	Aged bronze
626AM	Satin chrome antimicrobial
8	Lever cylinder type
PD	Schlage 6-pin full cylinder
See price book for other SFIC, FSIC and Less Cotes options available. Compatible with Schlage, Sargent, Corbin, Medeco and Yale.	
9	Keyway type
S123	Everest 29
See price book for other available keyway options including master keying	
10	Handing
RH	Right handed
LH	Left handed
Field reversible	
11	Battery

4B	4AA
8B	8AA
12	Backset and latch or armor front
Cylindrical	
13-049	2 3/4" backset, deadlatch, square corner, 1 1/8" x 2 1/4"
Mortise	
09-663	Armor front, 1 1/4" wide, square corner
See price book for mortise deadbolt and other backset and latch options or armor front options	
13	Strike
Cylindrical	
10-025	1 3/16" lip, ANSI, no box, 1 1/4" x 4 7/8"
Mortise	
10-072	1 3/16" lip, 1 1/4" x 4 7/8" square corner, box
See price book for other available strikes	
14	Door thickness
1 3/4"	
Other thicknesses available between 1 3/8" and 2 3/4"	
See price book for detail	

Lever styles

Standard cylinders shown, SFIC and FSIC also available.



Sparta

Rhodes

Athens

Tubular

Finishes

Warm tone finishesCool tone finishes



605 Bright brass

606 Satin brass

612 Satin bronze

643e Aged bronze

619 Satin nickel

625 Bright chrome

626 Satin chrome

626AM Satin chrome with antimicrobial

Allegion, the Allegion logo, Schlage, the Schlage logo, XceedID, Von Duprin, Falcon and aptiQ are trademarks of Allegion plc, its subsidiaries and/or affiliates in the United States and other countries. All other trademarks are the property of their respective owners.

About Allegion

Allegion (NYSE: ALLE) creates peace of mind by pioneering safety and security. As a \$2 billion provider of security solutions for homes and businesses, Allegion employs more than 7,800 people and sells products in more than 120 countries across the world. Allegion comprises 23 global brands, including strategic brands CISA®, Interflex®, LCN®, Schlage® and Von Duprin®. For more, visit www.allegion.com.

aptiQ ■ LCN ■ SCHLAGE ■ STEELCRAFT ■ VON DUPRIN



© 2014 Allegion
004442, Rev. 02/14
www.allegion.com/us



ARCHITECT'S RESPONSE:

This information is provided as an interpretation of the Contract Documents for implementation. It is not an authorization for change to the Contract Sum or Contract Time. If this information results in a claim for a change to the Contract, the Contractor shall notify the [Construction Manager][Architect] of a change through the change process.

Answered By: _____

Date: _____



49 Airport Rd. | St. Louis, MO 63135 | 800-456-6540

Date: 01-05-2017

To: Paric
Attn: Matt Horton
Phone: 636 561-9841
E-mail: mrhorton@paric.com

Project: Webster ISB – RFI-378
Location: St. Louis, MO.
Architect: Cannon Design

Quoted By: Darryl Stith
Phone: (314) 595-4409
E-Mail: dstith@negwer.com

Revised

We propose to furnish the following materials, delivery included and tax excluded, for the above referenced projects. Based on RFI-378.

<u>114,116</u>	
Change lock to ND53 in lieu of ND70	N/C
<u>144,401,406,432,434</u>	
Change lock to AD-200-CY-50-KP-RHO 626 in lieu of ND53	\$ 4,556.00
<u>364,412,414,441</u> <i>DL2700</i>	
Change lock to ND70 in lieu of ND53	N/C

*** Written authorization to proceed is required to place materials on order.

General Qualifications-

*** Final cores to be provided by others.

*** Doors 291.1, 291.2, 276.1, 284.1, 284.2 and 174 are all Aluminum Storefront with hardware being supplied by door manufacturer.

*** Change will need to be approved before ordering materials. If approved after material order is placed there will be additional costs.

=====

TOTAL FOR ABOVE MATERIALS AS LISTED

\$ 4,556.00 (tax not included)

All Pricing is based on Standard Lead Times approx. 6 weeks upon returned approved submittals. Please Contact Negwer Door Systems if material is time sensitive.

Conditions: Sales tax NOT included. Tax rate 9.113%. Payment terms, Net 30 days, pending credit approval. Quote is valid for 30 days. Material ONLY, no labor included.



49 Airport Rd. | St. Louis, MO 63135 | 800-456-6540

Date: 12-08-2016

To: Paric
Attn: Matt Horton
Phone: 636 561-9841
E-mail: mrhorton@paric.com

Project: Webster ISB – Returned Exterior Hardware
Location: St. Louis, MO.
Architect: Cannon Design

Quoted By: Darryl Stith
Phone: (314) 595-4409
E-Mail: dstith@negwer.com

We propose to furnish the following materials, delivery included and tax excluded, for the above referenced projects. Based on 2016.12.03 update. Exterior door hardware review.

Heading 2

Change continuous hinge finish to black anodized in lieu of 628.
Change Threshold to 566A in lieu of 657A at doors X188, X192.2, X178.2

Heading 3

Change continuous hinge finish to black anodized in lieu of 628.

Heading 4

Change continuous hinge finish to black anodized in lieu of powder coated.
Change Threshold to 566A in lieu of 233A/236A.
Add additional 188S-CL 36" to head.

Heading 11

Add DEL function to closers 177,179,277,279. (377, 379, 477, 479 closers have DEL feature accepted in COR2)

Heading 24

Change astragal to 8194AA in lieu of 328AA

*** Written authorization to proceed is required to place materials on order.

General Qualifications-

*** ZERO Manufacturing will need to know the "Powder Coat Code" in order to match for the weather strip items.

*** Changes in Headings 6A.1, 13A.1, 13B, 14,14A.1, 18.1, 19B and 31 are not included. Aluminum door supplier provided items.

=====

TOTAL FOR ABOVE MATERIALS AS LISTED

\$ 1,844.00 (tax not included)

All Pricing is based on Standard Lead Times approx. 6 weeks upon returned approved submittals. Please Contact Negwer Door Systems if material is time sensitive.

Conditions: Sales tax NOT included. Tax rate 9.113%. Payment terms, Net 30 days, pending credit approval. Quote is valid for 30 days. Material ONLY, no labor included.

SUBMITTAL IDENTIFICATION SHEET

To be completed by Contractor/CM

WEBSTER UNIVERSITY ISB

PROJECT NAME

8274 BIG BEND BLVD

ADDRESS

NUMBER

WEBSTER UNIVERSITY

OWNER

CANNON DESIGN

ARCHITECT / ENGINEER

Joe Voypick

SUBMITTED BY

087100.03-001

CONTRACTOR / CM SUBMITTAL NO.

CANNON DESIGN SUBMITTAL NO.

087100.03

DRAWING / DETAIL REFERENCE

SPECIFICATION SECTION / PARAGRAPH

Negwer Door Systems

MANUFACTURER / SUPPLIER

ITEM / PRODUCT ID

REQUIRED DATE

PRIORITY

CRITICAL

ITEM BEING SUBMITTED (check only one)

- ☐ Shop Drawings ☐ Certification / Qualifications ☐ Coordination Drawing
☐ Samples (____ copies) ☐ Record Documents ☒ Calculations
☐ LEED Submittal ☐ Product Data ☐ O&M Manuals
☐ Other _____

ITEM BEING SUBMITTED FOR (check only one)

- ☒ Action ☐ Information Only ☐ Record

REMARKS OR DEVIATIONS

CONTRACTOR / CM CERTIFICATION
(SUBMITTALS NOT CERTIFIED WILL BE RETURNED WITHOUT REVIEW)



Joe Voypick

REVIEWED BY

9/12/16

DATE

To be completed by Reviewer

08 7100.03-001

CANNON DESIGN SUBMITTAL NUMBER

9/13/16

RECEIVED DATE

- ☐ A. No Exceptions Taken
 No further review of submittal is required.
☒ B. Make Corrections Noted
 Incorporate corrections in work;
 resubmission is not required.
☐ C. Revise and Resubmit
 Revise as noted, and resubmit for review.
☐ D. Rejected
 Submittal is not in compliance with Contract Documents;
 provide new submittal.
☐ E. For Record / Information Only
 Submittal was reviewed for Record / Information
 purposes only.
☐ F. Not Required for Review
 Submittal is not required by Contract Documents
 and has not been reviewed.

Review is for conformance with the design concept of this project and for general compliance with contract documents. Contractor is responsible for quantities, dimensions and compliance with contract documents and for information that pertains to fabrication processes, construction techniques and coordination of this work with all trades which will be affected thereby. This review is null and void if submittal deviates from contract documents and does not indicate or note deviations.

A/E COMMENTS

☒ See attached sheet(s) for additional comments

Note : partial review -- groups not reviewed are highlighted.

See letter from Allegion (hardware consultant) as well as enclosed marks.

Handing of doors not reviewed. CM to review.

Closers - we have noted what side of door closer should be located on. Verify that indicated closer is correct.

Astragals: Please advise on use of mortised astragals where noted. We prefer these to the surface mounted for most doors.

Delete kickplates where indicated.

Owner will need to review this spec.

Changes following Owner meeting are in teal color. for aluminum doors: changes indicated on these drawings. Per subsequent discussion with Webster, Doors 177, 179, 277 and 279 should have automatic openers. We are working on those with Aaron Owen at Allegion

2016 10.07 update: Automatic openers to be on 180, 182, 277, and 279. Hardware groups 10.1 and 11.1 added to include openers. New groups 10.1 and 11.1 follow this page

2016.12.03 update: Exterior door hardware review comments in green color markups

Lynn Grossman

REVIEWED BY

Digitally signed by Lynn Grossman
 DN: C=US, E=lgrossman@cannondesign.com,
 O=CannonDesign, CN=Lynn Grossman
 Date: 2016.12.07 13:05:21-0500

12/03/16

DATE

10.07.16: HARDWARE GROUPS ADDED**HARDWARE GROUP NO. 10.1**

FOR USE ON MARK/DOOR #(S):

180 182

EACH TO HAVE:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HW HINGE	5BB1HW 4.5 X 4.5	652	IVE
1	EA	PRIVACY	L9056T 06A L583-363	626	SCH
1	EA	DOOR BOLT W/INDICATOR	B-571	626	SCH
1	EA	ELECTRIC STRIKE	6211	630	VON
1	EA	PRIMUS CORE	20-740	626	SCH
1	EA	AUTO OPERATOR	4642	689	LCN
4	EA	KICK PLATE	8400 10" X 2" LDW B-GS	630	IVE
1	EA	WALL STOP	WS401/402CCV	626	IVE
1	EA	GASKETING	188S-CL	S-CL	ZER
1	EA	COAT HOOK	CH-23	626	MOCT
1	EA	ACTUATOR PACKAGE	8310-3822TW		LCN

NOTE: ACTIVATING THE ACTUATOR ENERGIZES THE ELECTRIC STRIKE AND STARTS THE AUTO OPERATOR. FOR PRIVACY, THE DOOR BOLT W/INDICATOR MUST BE PROJECTED. TO EXIT, THE DOOR BOLT MUST BE RETRACTED AND THE INSIDE ACTUATOR ACTIVATED TO START THE AUTOMATIC OPERATOR.

HARDWARE GROUP NO. 11.1

FOR USE ON MARK/DOOR #(S):

277 279

EACH TO HAVE:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HW HINGE	5BB1HW 4.5 X 4.5	652	IVE
1	EA	PUSH PLATE	8200 6" X 16"	630	IVE
1	EA	PULL PLATE	8303 10" 6" X 16"	630	IVE
1	EA	ATTO OPERATOR	4642	689	LCN
1	EA	WALL STOP	WS401/402CCV	626	IVE
3	EA	SILENCER	SR64	GRY	IVE
1	EA	ACTUATOR PACKAGE	8310-3822TW		LCN



Allegion, PLC
6810 Hillside Ct.
Indianapolis, IN 46250 USA
Office 877.238.2022 Fax 317.715.4055
allegion.com

Submittal Review

Specification Section: 087100 Door Hardware

Date: 09/21/2016

Project: Webster Interdisciplinary Science Building
St. Louis, MO

Firm: Cannon Design
Attn: Lynn Grossman
1100 Clark Avenue
St. Louis, MO 63102
(314) 241-6250

Lynn,

I have reviewed this submittal for the door hardware per specification section 087100 only. This review is for specification compliance based on the specifications submitted to you for the above referenced project. I did not review for doors and frames and nor did I respond to any questions or comments regarding doors and frames. The Contractor remains responsible for the accuracy and completeness of submittal including, but not limited to, dimensions, quantities, fabrication, and construction techniques. General Conditions of contract documents apply.

You will need to review the door and frame submittal for compliance based on your plans, door schedule, and door/frame elevations. If any changes were made through addenda or RFI please update my comments appropriately.

Submittal Action:

Door Hardware Submittal dated 09/07/16 -

Reviewed / Reviewed As Noted

Submittal Notes/Comments:

Door Hardware Submittal (dated 09/07/16) –

Note: The general comments are listed to save time for repetitious items, comments, and/or concerns. The specific comments listed for individual headings are subject to the general comments listed below.

1. General:
 - a. I did not review submittal for handing.
 - b. Provide items to receive custom powder coating as specified for all applicable sets. The color should match the storefront.
 - c. Provide 5" hinge for doors greater than 36" for all applicable sets.
 - d. Provide CON-192 wire harness as specified for all applicable sets.
 - e. See comments per set.

Please remind the contractor to coordinate the hardware being supplied by the Aluminum Door supplier with the hardware from this package. The hardware for aluminum doors is specified in Section 087100. This submittal references aluminum hardware as "by others". All the hardware is required to be of the same manufacturer and model and meet the requirements of Section 087100.

- ✓ Single Source Responsibility: Obtain each type of hardware (ie. latch and locksets, hinges, exit devices, closers, etc.) from a single manufacturer. [Reference Section 087100, Article 1.4.D.]

The door hardware specification includes some project controls to assist in a smooth project. Please remind the general contractor of the following specification items in Section 087100:

- ✓ Article 1.3.C. Riser and Wiring Diagram – Please advise hardware supplier to provide riser and (point-to-point) Wiring Diagrams per approved finish hardware schedule.
- ✓ Articles 1.4.E. and 2.6. Keying – Please advise the hardware supplier to schedule and complete the keying conference prior to ordering hardware to avoid issues with keying or lock functions.
- ✓ Articles 1.6. and 1.7. Coordination – Please advise general contractor to schedule pre-installation, installation coordination, and electrified hardware coordination conferences prior to installation of any finish hardware.

Also, put the following items on the check-list at project completion time:

- ✓ Field Quality Control
- ✓ Adjustment, Cleaning and Protection, and Demonstration

As a reminder the following services are available to you for this project:

- ✓ Review submitted keying schedule and/or assist with keying meeting, questions, or concerns.
- ✓ Provide product training to installers.
- ✓ Provide product training to owner.

Please review and contact us at the above telephone number or via email at chris.mueller@allegion.com with any questions. Thank you for your time and allowing me to follow up on this project.

Sincerely,

A handwritten signature in cursive script that reads "Chris Mueller".

<Chris Mueller>



PARIC
EXPERIENCE. EXCELLENCE.

77 Westport Plaza
Suite 250
St. Louis, MO 63146

TRANSMITTAL

No. 15051-0220

Paric Corporation

PROJECT: 15051-Webster University Interdisciplinary Science Building

DATE: 09/12/2016

TO: Cannon Design
1100 Clark Ave
St Louis MO 63102

RE: Hardware Schedule

ATTN: Kelvin Patel

JOB: 15051

WE ARE SENDING:	SUBMITTED FOR:	ACTION TAKEN:
☐ Shop Drawings	☒ Approval	☐ Approved as Submitted
☐ Letter	☐ Your Use	☐ Approved as Noted
☐ Prints	☐ As Requested	☐ Returned After Loan
☐ Change Order	☐ Review and Comment	☐ Resubmit
☐ Plans		☐ Submit
☐ Samples	SENT VIA:	☐ Returned
☐ Specifications	☐ Attached	☐ Returned for Corrections
☒ Other: Schedule	☐ Separate Cover Via:	☐ Due Date:

Item	Package Code	Rev. Copies	Date	Description	Status
Submittal	08100.03-001	1	09/12/2016	Hardware Schedule	Submitted

NOTES:

CC:

Signed: _____
Devin Gates



The Knowledgeable Door Specialist

49 Airport Road

St. Louis, MO 63135

Phone: (314) 522-0579

Fax: (314) 522-6659

Spec Section
087100.03

Schedule of Hardware

By : Darryl Stith

Project: WEBSTER ISB

8274 Big Bend

Webster Groves, MO 63119-

Architect: Cannon Design

1100 Clark Avenue

St. Louis, MO 63102-

Contractor: Paric Corporation

77 Westport Plaza Dr

St. Louis, MO 63146-

(636) 561-9500 (636) 561-9501

9/7/2016

PROJECT NOTES:

- 1) HARDWARE IS SUPPLIED WITH FINISH AS NOTED UNDER FINISH COLUMNS. IF CUSTOM POWDER COAT FINISH IS WANTED A SAMPLE WILL NEED TO BE PROVIDED TO HARDWARE MANUFACTURER.
- 2) KEYED CORES ONLY SUPPLIED AT ALUMINUM DOORS. CONTRACTOR TO COORDINATE CORES REQUIRED WITH ALUMINUM DOOR SUPPLIER.
- 3) VON DUPRIN 9447 DEVICE NOT AVAILABLE FOR WOOD DOORS C170.

We have changed door C170 to Hollow Metal to allow use of this exit device.

REVIEWED:

The review of shop drawings, product data, or samples is for general conformance only and shall not relieve the subcontractor/supplier for any deviation from the requirements of the contract documents nor the responsibility for errors or omissions including sizes, dimensions, quantities or locations.

Reviewed Date: 09/21/2016
Chris Mueller
Allegion

General Notes:

- 1) Provide items to receive custom powder coating as specified for all applicable sets. The color should match the storefront.
- 2) Provide 5" hinge for doors greater than 36" for all applicable sets.
- 3) Provide CON-192 wire harness as specified for all applicable sets.
- 4) See comments per set.

Manufacturer's List

Mfr.	Hardware Used
SC	Cylinder, Housing, Mortise Lock, Cylindrical Lock, Electrified Multi-Point Lock
GJ	Overhead Stop
VD	Wire Harness, Extension Rod Kit, Electric Power Transfer, Fire Rated Mortise Exit, Mortise Exit Device, Fire Rated Conc Vert Rod, Touch Bar, Power Supply
SH	Position Switch
LC	Surface Closer, Electromagnetic Holder, Concealed Closer
AT	Pocket Door Lock
IV	Push Plate, Continuous Hinge, Pivot, Dust Proof Strike, Hinge, Wall Stop, Flush Bolt, Coat Hook, Coordinator, Mounting Bracket, Silencer, Pull Plate, Kick Plate
ZE	Anchor, Door Bottom, Gasketing, Threshold, Sweep, Rain Drip, Ramp, Astragal
OT	Brio SR108-57GN-1ss-106RB/94-94P/94PA-180DS, 690 Edge Pull
DK	Coat hook

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
X160.3	X160.3	18	4		RHR
X172.2	X172.2	12	2		RHRA/LHR
X178.2	X178.2	13	2		RHRA/LHR
X188	X188	14	2		RHRA/LHR
X192.2	X192.2	15	2		RHRA/LHR
XC130	XC130				
XC153	XC153				
XS176.1	XS176.1	16	3		RHR
XC270A.1	XC270A.1				
XC270A.2	XC270A.2				
X294.2	X294.2	17	4		RHR
XC250	XC250				
XC230	XC230				
S076	S076	1	1		RHR
100A	100A	128	21		
100B	100B	52	8a		LH
101	101	131	22		RH
104	104	132	22		LH
105	105	133	22		LH
106	106	134	22		RH
107	107	135	22		RH
108	108	136	22		LH
109	109	137	22		LH
110A	110A	50	8a		LH
110B	110B	53	8a		RH
110B.2	110B.2	34	6b		LHR
111	111	138	22		RH
112	112	51	8a		LH
113	113	139	22		LH
114	114	96	18		LH
115	115	140	22		RH
116	116	97	18		LH
117	117	141	22		LH
131	131	109	18.1		
133A	133A	86	14a		RHR
133B	133B	72	13.1		LHR
133B.2	133B.2	48	8a		LHR
133B.3	133B.3	49	8a		RHR

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
135.1	135.1	87	14a.1		
135.2	135.2	98	18		RH
137	137	74	13a.1		
137A	137A	27	6a		RHR
140.1	140.1	117	18a.1		
140.2	140.2	116	18a		RHR
144	144	203	22		RH
150	150	126	20b		RHRA/LHR
151	151	46	8.1		RH
154	154	118	19		LH
156.1	156.1	119	19		RH
156.2	156.2	122	19a		RH
160.1	160.1	211	24		RHR/LHR
160.2	160.2	212	25		RHR/LHR
160A	160A	120	19		LHR
160B	160B	208	22A		RH
160D	160D	54	9		LH
172.1	172.1	69	12		RHA/LH
172A	172A	93	17		RH
174	174	110	18.1		
175	175	47	8.1		RH
176	176	38	6b.1		RHR
177	177	61	11		RH
178.1	178.1	70	12a		RHRA/LHR
179	179	62	11		LH
180	180	58	10		RH
182	182	59	10		LH
183A	183A	73	13a		LHR
183B.1	183B.1	90	15		RHA/LH
183B.2	183B.2	91	16		RHRA/LHR
183C	183C	92	17		LH
184	184	25	6		LH
185	185	43	8.1		LH
186	186	40	8		LH
187	187	23	6		RH
192.1	192.1	39	7		RHR
195	195	24	6		LH
196	196	44	8.1		RHR
C153	C153	125	20a		

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
C170	C170	127	20c		RHR/LHR
S140	S140				
S176.2	S176.2	3	1		LHR
S194	S194	19	5		RH
200A	200A	129	21		Pocket
200B	200B	4	1		LH
202	202	217	27		LHR
203	203	121	19		LH
205	205	142	22		RH
206	206	143	22		LH
207	207	144	22		LH
208	208	145	22		RH
209	209	146	22		RH
210A	210A	56	9		LH
210B	210B	7	1A		RH
210B.2	210B.2	35	6b		LHR
211	211	147	22		LH
212	212	148	22		LH
214	214	149	22		RH
215	215	210	23		LH
231	231	76	13b		
233	233	123	19b		
235	235	75	13a.1		
272A	272A	5	1.1		LHR
272B	272B	41	8		LH
274	274	77	13c		LH
275	275	60	10		RH
276.1	276.1	79	14		RHR
276.2	276.2	213	26		LHR
277	277	63	11		RH
279	279	64	11		LH
282.1	282.1	28	6a.1		
282.2	282.2	111	18.2		LH
282.3	282.3	99	18		RHR
283.1	283.1	80	14		
283.2	283.2	214	26		
284.1	284.1	221	31		
284.2	284.2	222	31		
289A.1	289A.1	112	18.2		RHR
289A.2	289A.2	113	18.2		LHR

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
289B.1	289B.1	114	18.2		LHR
289B.2	289B.2	100	18		RHR
291.1	291.1	81	14		
291.2	291.2	215	26		
292.1	292.1	29	6a.1	change to group 14A to include card reader	
292.2	292.2	26	6.1		LHR
C210	C210	218	28		LH
C230A	C230A	219	29		
C250A	C250A	220	30		
C270	C270	124	20		RHRA/LHR
S240	S240				
S294	S294	20	5		RH
S294A	S294A				
300A	300A	130	21		Pocket
300B	300B	8	1A		LH
304	304	150	22		LH
305.1	305.1	151	22		RH
305.2	305.2	207	22		LH
306	306	152	22		RH
310A	310A	9	1A		RH
310A.2	310A.2	36	6b		LHR
310B	310B	55	9		RH
311	311	153	22		RH
312	312	57	9		RH
313	313	154	22		LH
314	314	155	22		LH
315	315	156	22		RH
316	316	157	22		RH
317	317	158	22		LH
318	318	159	22		LH
319	319	160	22		RH
320	320	161	22		RH
321	321	162	22		LH
322	322	163	22		LH
323	323	164	22		RH
325	325	165	22		RH
327	327	166	22		LH
329	329	167	22		RH
331	331	168	22		LH
332.1	332.1	209	23		LH

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
332.2	332.2	88	14a.2		LH
333	333	169	22		RH
335	335	170	22		LH
337	337	171	22		RH
342	342	172	22		LH
344	344	173	22		RH
346	346	174	22		LH
348	348	175	22		RH
352	352	94	18		LH
353	353	89	14a.2		RH
360	360	176	22		RH
362	362	177	22		LH
364	364	178	22		RH
372B	372B	71	13		RHR
372C	372C	42	8		LH
372D	372D	179	22		RH
374A	374A	82	14		RHR
374B	374B	115	18.2		LHR
375	375	45	8.1		RH
376	376	237	33		
377	377	65	11		RH
378.1	378.1	223	31		
378.2	378.2	224	31		
379	379	66	11		LH
383.1	383.1	83	14		
383.2	383.2	225	31		
386.1	386.1	30	6a.1		
386.2	386.2	101	18		LH
386.3	386.3	102	18		RH
388.1	388.1	84	14		
388.2	388.2	226	31		
389.1	389.1	31	6a.1		
389.2	389.2	103	18		RH
389.3	389.3	104	18		LH
391.1	391.1	227	31		
391.2	391.2	228	31		
S340.1	S340.1				
S340.2	S340.2	236	32		RH
S394	S394	21	5		RH
400A	400A	95	18		LH

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
400B	400B	10	1A		LH
401	401	180	22		LH
402	402	181	22		RH
403	403	182	22		RH
404	404	183	22		LH
405	405	184	22		LH
406	406	185	22		RH
407.1	407.1	186	22		RH
407.2	407.2	187	22		LH
410	410	11	1A		RHR
410.2	410.2	37	6b		LHR
411	411	188	22		RH
412	412	189	22		RH
413	413	190	22		RH
414	414	191	22		RH
415	415	192	22		LH
416	416	193	22		LH
417	417	194	22		RH
419	419	195	22		RH
432	432	196	22		RH
433	433	197	22		RH
434	434	198	22		LH
435	435	199	22		LH
437	437	200	22		RH
439	439	201	22		LH
441	441	202	22		RH
452	452	204	22		LH
454	454	205	22		LH
456	456	206	22		RH
472.1	472.1	78	14		RHR
472.2	472.2	229	31		LHR
475	475	6	1.1		RHR
477	477	67	11		RH
478.1	478.1	32	6a.1		LHR
478.2	478.2	105	18		LH
478.3	478.3	106	18		RH
479	479	68	11		LH
480.1	480.1	230	31		
480.2	480.2	231	31		
483.1	483.1	85	14		

DOOR INDEX

Project ID: JOB001775

WEBSTER ISB

<u>Door Number</u>	<u>Arch Mark</u>	<u>Item Number</u>	<u>Heading #</u>	<u>Keying</u>	<u>Hand</u>
483.2	483.2	216	26		
488.1	488.1	232	31		
488.2	488.2	233	31		
489.1	489.1	33	6a.1		
489.2	489.2	107	18		RH
489.3	489.3	108	18		LH
491.1	491.1	234	31		
491.2	491.2	235	31		
S440	S440				
S494	S494	22	5		LH
S494A	S494A	2	1		RHR

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 1

			closer side		
	1 SGL	Door:S076	STAIR 3-0 from MECH. ROOM	RHR	45
		3' 0" x 7' 0" x 1 3/4" HMD/HMF (45)			
	1 SGL	Door:S494A	ROOF ACCESS from STAIR 2-4	RHR	
		3' 0" x 7' 2" x 1 3/4" HMD/HMF			
	1 SGL	Door:S176.2	MECH. ROOM from STAIR 3-1	LHR	90
		3' 0" x 7' 2" x 1 3/4" HMD/HMF (90)			
	1 SGL	Door:200B	WORK/COPY to DATA	LH	45
		3' 0" x 7' 2" x 1 3/4" WDD/HMF (45)			
12 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
4 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
4 EA	Cylinder	20-740	626	(CY-1) Schlage	
4 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
3  EA	Kick Plate	8400 B-CS 10" x 34" no kickplate door 200B	US32D	(KP-2) Ives	
4 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
4 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc	
4 EA	Sweep	339AA 36"		(SW-2) Zero International Inc	

Heading #: 1.1

			closer side		
	1 SGL	Door:272A	CORRIDOR from CHEM. STOCK	LHR	45
		3' 6" x 7' 2" x 1 3/4" HMD WDD HMF (45)			
	1 SGL	Door:475	CORRIDOR from LAB WASTE CHEM	RHR	90
		3' 6" x 7' 2" x 1 3/4" WDD/HMF (90)			
6 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
2 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
2 EA	Cylinder	20-740	626	(CY-1) Schlage	
2 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
2 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives	
2 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
2 EA	Gasketing	188S-CI 48" 96"		(GA-1) Zero International Inc	
2 EA	Sweep	339AA 42"		(SW-1) Zero International Inc	

Heading #: 1A

			closer side		
	1 SGL	Door:210B	CORRIDOR to ELEC.	RH	45
	1 SGL	Door:300B	WORK COPY to DATA	LH	45
	1 SGL	Door:310A	CORRIDOR to ELEC.	RH	45
	1 SGL	Door:400B	WORK COPY to DATA	LH	45
	1 SGL	Door:410	COMMONS from ELEC.	RHR	45
		3' 0" x 7' 2" x 1 3/4" WDD/HMF (45)			
15 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
5 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
5 EA	Cylinder	20-740	626	(CY-1) Schlage	
5 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
5 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
5 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc	
5 EA	Sweep	339AA 36"		(SW-2) Zero International Inc	

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 2

Exterior

1 PR	Door:X172.2	EXTERIOR from EL	RHRA/LHR
1 PR	Door:X178.2	EXTERIOR from MECH. ROOM	RHRA/LHR
1 PR	Door:X188	EXTERIOR from FIRE PUMP	RHRA/LHR
1 PR	Door:X192.2	EXTERIOR from MAIN ELECTRICAL	RHRA/LHR
2-3' 0" x 7' 10" x 1 3/4" HMD/HMF			

8 EA	Continuous Hinge	112HD 95"	black anodized finish 626	(HC-1) Ives
4 Set	Flush Bolt	FB51P-24	630	(BO-1) Ives
4 EA	Dust Proof Strike	DP2	626	(BO-2) Ives
4 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
4 EA	Cylinder	20-740	626	(CY-1) Schlage
4 EA	Coordinator	COR52 FL20	628	(CO-2) Ives
8 EA	Mounting Bracket	MB1	689	(CO-3) Ives
8 EA	Surface Closer	4040XP MC SRI SCUSH	AL	(CL-4) LCN Closers
8 EA	Kick Plate	8400 B-CS 10" x 35"	US32D	(KP-4) Ives
4 EA	Threshold	657A 72" V3 -7"	USE 566A AT DOORS X188, X192.2 AND X178.2	
4 EA	Rain Drip	142A 76"	finish drip,gasketing and exposed fasteners to match door paint (match reynobond "pewter")	
4 EA	Gasketing	25A 72"		
4 EA	Gasketing	144A 36"		
4 EA	Gasketing	188S-CI 72" 96"		
8 EA	Sweep	339AA 36"	exposed exterior items to be finished to match door	
8 EA	Astragal	328AA 2/96"		
24 EA	Anchor	226		

RAIN DRIP AND WEATHERSTRIP ARE FIGURED AS CLEAR ALUMINUM FINISH.

Heading #: 3

Exterior

1 SGL	Door:XS176.1	EXTERIOR from STAIR 3-1	RHR
3' 6" x 7' 10" x 1 3/4" HMD/HMF			

1 EA	Continuous Hinge	112HD 95"	black anodized finish 626	(HC-1) Ives
1 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC SRI SCUSH	AL	(CL-4) LCN Closers
1 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives
1 EA	Threshold	657A 42" V3 -7"	(TH-10) Zero International Inc	
1 EA	Gasketing	188S-CI 48" 96"	(GA-1) Zero International Inc	
1 EA	Gasketing	25A 42" 0	(GA-3) Zero International Inc	
1 EA	Gasketing	144A 42"	(GA-4) Zero International Inc	
1 EA	Rain Drip	142A 46"	(GA-13) Zero International Inc	
1 EA	Sweep	339AA 42"	(SW-1) Zero International Inc	

RAIN DRIP AND WEATHERSTRIP ARE FIGURED AS CLEAR ALUMINUM FINISH.

09-26-2016: REVIEW NOT COMPLETE THIS HEADING
12.03.2016: REVIEW COMPLETE

09-26-2016: REVIEW NOT COMPLETE THIS HEADING
12.03.2016: REVIEW COMPLETE

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 4

Exterior

1 SGL Door:X294.2 EXTERIOR from STAIR 2-2 RHR
3' 0" x 7' 10" x 1 3/4" HMD/HMF

1 SGL Door:X160.3 EXTERIOR from LECTURE HALL 160 RHR
3' 0" x 9' 0" x 1 3/4" HMD/HMF

Door not listed in specification

2 EA	Continuous Hinge	112HD 120"			(HC-2) Ives
2 EA	Mortise Exit Device	LD 9975EO			(ED-9) Von Duprin
2 EA	Surface Closer	4040XP MC SRI SCUSH			(CL-4) LCN Closers
2 EA	Ramp	288A 36"			(TH-7) Zero International Inc
2 EA	threshold	566A 36"			(TH-8) Zero International Inc
2 EA	Ramp	236A 36"			(GA-9) Zero International Inc
2 EA	Gasketing	144A 36"	install on door X294.2 only.	finish drip,gasketing and exposed	(GA-14) Zero International Inc
2 EA	Gasketing	25A 36"	provide loose for door X160.3	fasteners to match door paint (match reynobond "pewter")	(GA-15) Zero International Inc
2 EA	Rain Drip	11A 40"			(GA-19) Zero International Inc
2 EA	Gasketing	188S-CI 36" 108"	door X160.3: apply additional 188S-CI 36" to head.		(DB-2) Zero International Inc
2 EA	Door Bottom	3551 36"			(OT-4) Zero International Inc
8 EA	Anchor	226		exposed exterior items to be finished to match door	

CONT. HINGE, CLOSER AND WEATHERSTRIP ARE FIGURED AS CLEAR ALUMINUM FINISH

Heading #: 5

closer side

1 SGL	Door:S194	CORRIDOR to STAIR 2-1	RH	90	
1 SGL	Door:S294	CORRIDOR to STAIR 2-2	RH	90	
1 SGL	Door:S394	COMMONS to STAIR 2-3	RH	90	
1 SGL	Door:S494	CORRIDOR to STAIR 2-4	LH	90	
	3' 0" x 7' 2" x 1 3/4" WDD/HMF (90)				
12 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652		(HI-1) Ives
4 EA	Fire Rated Mortise Exit	9975L-BE-F 06 996L-BE SNB	US26D		(ED-1) Von Duprin
4 EA	Surface Closer	4040XP MC Rw/PA	AL		(CL-5) LCN Closers
4 EA	Wall Stop	WS401CCV	626		(ST-1) Ives
4 EA	Gasketing	188S-CI 36 96			(GA-7) Zero International Inc
4 EA	Sweep	339AA 36"			(SW-2) Zero International Inc

DOOR SWEEP IS FIGURED AS CLEAR ALUMINUM FINISH.

Heading #: 6

closer side

1 SGL	Door:187	CORRIDOR to CYLINDER ROOM	RH		
1 SGL	Door:195	CORRIDOR to MDF/IT WOORK ROOM	LH		
	3' 0" x 7' 2" x 1 3/4" HMD/HMF				
1 SGL	Door:184	CORRIDOR to BLDG. STOR	LH		
	3' 0" x 7' 2" x 1 3/4" WDD/HMF				
9 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652		(HI-1) Ives
3 EA	Cylindrical Lock	ND80 T D RHO	626		(LO-1) Schlage
3 EA	Cylinder	20-740	626		(CY-1) Schlage
3 EA	Overhead Stop	104S	US32D		(OH-1) Glynn-Johnson
3 EA	Surface Closer	4040XP MC Rw/PA	AL		(CL-5) LCN Closers
3 EA	Kick Plate	8400 B-CS 10" x 34"	US32D		(KP-2) Ives
9 EA	Silencer	SR64-GRY			(SI-1) Ives

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 6.1

closer side

1 SGL Door:292.2

PHYSICS LAB from PHYS
RESEARCH LAB

LHR

3' 6" x 7' 2" x 1 3/4" WDD/HMF

3 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
1 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Overhead Stop	105S	US32D	(OH-2) Glynn-Johnson
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
1 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives
3 EA	Silencer	SR64-GRY		(SI-1) Ives

Heading #: 6a

closer side

1 SGL Door:137A

MODELS/ASSESSMENT from
PREACTION SYSTEM

RHR

3' 6" x 7' 2" x 1 3/4" HMD/HMF

3 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
1 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Overhead Stop	105S	US32D	(OH-2) Glynn-Johnson
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
3 EA	Silencer	SR64-GRY		(SI-1) Ives

Heading #: 6a.1

AL - Cores only

1 SGL Door:282.1

~~1 SGL Door:292.1~~

change to group 14A to
include card reader

1 SGL Door:386.1

1 SGL Door:389.1

1 SGL Door:478.1

1 SGL Door:489.1

LHR

3' 6" x 7' 2" x 1 3/4" ALD/ALF

6 EA	Cylinder	20-740	626	(CY-1) Schlage
------	----------	--------	-----	----------------

Heading #: 6b

1 SGL Door:110B.2

ELEC. from CLOSET

LHR 90

1 SGL Door:210B.2

ELEC. from CLOSET

LHR 90

1 SGL Door:310A.2

ELEC. from CLOSET

LHR 90

1 SGL Door:410.2

ELEC. from CLOSET

LHR 90

2' 0" x 8' 0" x 1 3/4" HMD/HMF (90)

4 hinges per opening

16

12 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
4 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
4 EA	Cylinder	20-740	626	(CY-1) Schlage
4 EA	Overhead Stop	102S	US32D	(OH-3) Glynn-Johnson
4 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
4 EA	Kick Plate	8400 B-CS 10" x 22"	US32D	(KP-3) Ives
4 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc

Heading #: 6b.1

closer side

1 SGL Door:176

CORRIDOR from ELEV CONTROL

RHR 90

3' 0" x 7' 2" x 1 3/4" WDD/HMF (90)

3 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
1 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Overhead Stop	104S	US32D	(OH-1) Glynn-Johnson
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
1 EA	Kick Plate	8400 B-CS 10" x 34"	US32D	(KP-2) Ives
1 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 7

				closer side	
	1 SGL	Door: 192.1	CORRIDOR from	MAIN ELECTRICAL	RHR 45
3' 0" x 7' 2" x 1 3/4" HMD/HMF (45)					
3 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
1 EA	Fire Rated Mortise Exit	9975L-NL-F 17 996L-NL	US26D	(ED-2) Von Duprin	
1 EA	Cylinder	20-740	626	(CY-1) Schlage	
1 EA	Housing	26-064	626	(CY-2) Schlage	
1 EA	Surface Closer	4040XP MC SCUSH	AL	(CL-6) LCN Closers	
1 EA	Kick Plate	8400 B-CS 10" x 34"	US32D	(KP-2) Ives	
1 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc	

Heading #: 8

				closer side	
	1 SGL	Door: 186	CORRIDOR to	CUST. STOR.	LH
	1 SGL	Door: 272B	CORRIDOR to	LAB. STOR.	LH
3' 6" x 7' 2" x 1 3/4" HMD/HMF					
	1 SGL	Door: 372C	COMMONS to	LAB STOR.	LH
3' 6" x 7' 2" x 1 3/4" WDD/HMF					
9 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
3 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
3 EA	Cylinder	20-740	626	(CY-1) Schlage	
3 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
3 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives	
3 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
9 EA	Silencer	SR64-GRY		(SI-1) Ives	

Heading #: 8.1

	1 SGL	Door: 185	CORRIDOR to	SPILL CLOSET	LH
	1 SGL	Door: 196	CORRIDOR from	WATER ENTRY	RHR
	1 SGL	Door: 375	CORRIDOR to	JC	RH
3' 0" x 7' 2" x 1 3/4" HMD/HMF					
	1 SGL	Door: 151	CORRIDOR to	EAB STORAGE	RH
	1 SGL	Door: 175	CORRIDOR to	JC	RH
3' 0" x 7' 2" x 1 3/4" WDD/HMF					
15 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
5 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
5 EA	Cylinder	20-740	626	(CY-1) Schlage	
5 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
5 EA	Kick Plate	8400 B-CS 10" x 34"	US32D	(KP-2) Ives	
5 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
15 EA	Silencer	SR64-GRY		(SI-1) Ives	

Heading #: 8a

				closer side	
	1 SGL	Door: 133B.2	SIM LAB from	CLOSET	LHR
	1 SGL	Door: 133B.3	SIM LAB from	CLOSET	RHR
3' 0" x 7' 2" x 1 3/4" HMD/HMF					
	1 SGL	Door: 110A	CORRIDOR to	STORAGE	LH
	1 SGL	Door: 112	CORRIDOR to	STORAGE	LH
3' 0" x 7' 2" x 1 3/4" WDD/HMF					
	1 SGL	Door: 100B	WORK COPY to	DATA	LH
	1 SGL	Door: 110B	CORRIDOR to	ELEC.	RH
3' 0" x 7' 2" x 1 3/4" WDD/HMF (45)					
18 EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives	
6 EA	Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage	
6 EA	Cylinder	20-740	626	(CY-1) Schlage	
6 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers	
6 EA	Wall Stop	WS401CCV	626	(ST-1) Ives	
18 EA	Silencer	SR64-GRY		(SI-1) Ives	

Provide seals for rated openings

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 9

1 SGL Door: 160D	LECTURE HALL 160 to AV EQUIP	LH	closer side
3' 0" x 7' 10" x 1 3/4" WDD/HMF			
1 SGL Door: 310B	CORRIDOR to STORAGE	RH	
3' 0" x 7' 2" x 1 3/4" HMD/HMF			
1 SGL Door: 210A	CORRIDOR to STORAGE	LH	
1 SGL Door: 312	CORRIDOR to STORAGE	RH	
3' 0" x 7' 2" x 1 3/4" WDD/HMF			

Provide 4 hinges for Door 160D

13

12 EA Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
4 EA Cylindrical Lock	ND80 T D RHO	626	(LO-1) Schlage
4 EA Cylinder	20-740	626	(CY-1) Schlage
4 EA Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
4 EA Wall Stop	WS401CCV	626	(ST-1) Ives
12 EA Silencer	SR64-GRY		(SI-1) Ives

revision 2016.10.07: doors 180 and 182 in this group to be changed to low energy automatic openers - see new hardware group 10.1 at front of submittal

Heading #: 10

1 SGL Door: 180	CORRIDOR to TOILET	RH	closer side
1 SGL Door: 182	CORRIDOR to TOILET	LH	
1 SGL Door: 275	CORRIDOR to LACT.	RH	
3' 0" x 7' 2" x 1 3/4" WDD/HMF			

LCN 4010/4110 DEL MC AS REQ'D

9 EA Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
3 EA Mortise Lock	L9056 R T L583-363 06A L283-722	626	(LO-2) Schlage
3 EA Cylinder	20-740	626	(CY-1) Schlage
3 EA Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
3 EA Kick Plate	8400 B-CS 10" x 34"	US32D	(KP-2) Ives
3 EA Wall Stop	WS401CCV	626	(ST-1) Ives
3 EA Gasketing	188S-CI 36 96		(GA-7) Zero International Inc
3 EA Coat Hook	572	626	(OT-1) Ives MOCKETT

Set closer at size 1 for owner requirements

CHANGE TO MATCH HOOK AT HEADING #22

Heading #: 11

1 SGL Door: 177	CORRIDOR to WOMENS	RH	closer side
1 SGL Door: 179	CORRIDOR to MENS	LH	
1 SGL Door: 277	CORRIDOR to WOMENS	RH	
1 SGL Door: 279	CORRIDOR to MENS	LH	
1 SGL Door: 377	CORRIDOR to WOMENS	RH	
1 SGL Door: 379	CORRIDOR to MENS	LH	
1 SGL Door: 477	CORRIDOR to WOMENS	RH	
1 SGL Door: 479	CORRIDOR to MENS	LH	
3' 0" x 7' 2" x 1 3/4" WDD/HMF			

hold these doors. Webster want to change these to low energy automatic doors.

revision 2016.10.07: doors 277 and 279 in this group to be changed to low energy automatic openers - see new hardware group 11.1 at front of submittal

24 EA Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
8 EA Push Plate	8200-6x16	630	(PP-1) Ives
8 EA Pull Plate	8303-0-6x16	630	(PP-2) Ives
8 EA Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
8 EA Wall Stop	WS401CCV	626	(ST-1) Ives
24 EA Silencer	SR64-GRY		(SI-1) Ives

Set closer at size 1 for owner requirements.

LCN 4010/4110 DEL MC AS REQ'D

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 12

			closer side	
1	PR	Door: 172.1	CORRIDOR to	LOADING DOCK
		2-3' 0" x 7' 2" x 1 3/4" HMD/HMF		RHA/LH
6	EA	Hinge	5BB1 4-1/2" x 4-1/2"	652 (HI-1) Ives
1	Set	Flush Bolt	FB51P-24	630 (BO-1) Ives
1	EA	Dust Proof Strike	DP2	626 (BO-2) Ives
1	EA	Cylindrical Lock	ND80 T D RHO	626 (LO-1) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Coordinator	COR52 FL20	628 (CO-2) Ives
2	EA	Mounting Bracket	MB2	689 (CO-4) Ives
2	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D (KP-4) Ives
2	EA	Wall Stop	WS401CCV	626 (ST-1) Ives
2	EA	Sweep	339AA 36"	(SW-2) Zero International Inc
2	EA	Astragal	328AA 2/86"	(AS-3) Zero International Inc

ASTRAGAL AND SWEEP ARE FIGURED AS CLEAR ALUMINUM FINISH.

Heading #: 12a

			closer side	
1	PR	Door: 178.1	CORRIDOR from	MECH. ROOM
		2-3' 0" x 7' 2" x 1 3/4" HMD/HMF		RHRA/LHR
6	EA	Hinge	5BB1 4-1/2" x 4-1/2"	652 (HI-1) Ives
1	Set	Flush Bolt	FB51P-24	630 (BO-1) Ives
1	EA	Dust Proof Strike	DP2	626 (BO-2) Ives
1	EA	Cylindrical Lock	ND80 T D RHO	626 (LO-1) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Coordinator	COR52 FL20	628 (CO-2) Ives
2	EA	Mounting Bracket	MB1	689 (CO-3) Ives
2	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D (KP-4) Ives
2	EA	Wall Stop	WS401CCV	626 (ST-1) Ives
1	EA	Threshold	657A 72" V3 -7"	(TH-5) Zero International Inc
2	EA	Door Bottom	3551 36"	(DB-2) Zero International Inc
2	EA	Sweep	339AA 36"	(SW-2) Zero International Inc
2	EA	Astragal	328AA 2/86"	(AS-3) Zero International Inc

PROVIDE GASKETING THIS DOOR

ASTRAGAL AND SWEEP ARE FIGURED AS CLEAR ALUMINUM FINISH.

Heading #: 13

			closer side	
1	SGL	Door: 372B	COMMONS from	LAB WASTE-BIO
		3' 6" x 7' 2" x 1 3/4" WDD/HMF		RHR
3	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626 (LO-3) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
1	EA	Kick Plate	8400 B-CS 10" x 40"	US32D (KP-1) Ives
1	EA	Wall Stop	WS401CCV	626 (ST-1) Ives
3	EA	Silencer	SR64-GRY	(SI-1) Ives
1	EA	Electric Power Transfer	EPT10 CON	SP28 (EA-1) Von Duprin
1	EA	Wire Harness	CON-192P	(EA-2) Von Duprin
1	EA	Position Switch	679-05HM	(EA-3) Schlage Electronic Security

CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY. CON-192 MAY NEED TO BE SPLICED IN FIELD FOR THIS OPENING.

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 13.1

closer side

1 SGL Door:133B		CORRIDOR from	SIM LAB	LHR
3' 6" x 7' 2" x 1 3/4" WDD/HMF				
3 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1 EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626	(LO-3) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC R/W/PA LCN 4010/4110 DEL MC AS REQ'D	AL	(CL-5) LCN Closers
1 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives
1 EA	Wall Stop	WS401CCV	626	(ST-1) Ives
3 EA	Silencer	SR64-GRY		(SI-1) Ives
1 EA	Electric Power Transfer	EPT10 CON	SP28	(EA-1) Von Duprin
1 EA	Position Switch	679-05HM		(EA-3) Schlage Electronic Security
1 EA	Wire Harness	CON-44P		(EA-4) Von Duprin
CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY.				

Heading #: 13a

closer side

1 SGL Door:183A		CORRIDOR from	BIO VESTIBULE	LHR
3' 6" x 7' 2" x 1 3/4" WDD/HMF				
3 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1 EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626	(LO-3) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC R/W/PA	AL	(CL-5) LCN Closers
1 EA	Wall Stop	WS401CCV	626	(ST-1) Ives
3 EA	Silencer	SR64-GRY		(SI-1) Ives
1 EA	Electric Power Transfer	EPT10 CON	SP28	(EA-1) Von Duprin
1 EA	Wire Harness	CON-192P		(EA-2) Von Duprin
1 EA	Position Switch	679-05HM		(EA-3) Schlage Electronic Security
CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY. CON-192 MAY NEED TO BE SPLICED IN FIELD FOR THIS OPENING.				

Heading #: 13a.1

AL - cores only

1 SGL Door:137				
3' 0" x 7' 2" x 1 3/4" ALD/ALF				
1 SGL Door:235				
3' 6" x 7' 2" x 1 3/4" ALD/ALF				
note: closer: LCN 4010/4110 DEL MC AS REQ'D				
2 EA	Cylinder	20-740	626	(CY-1) Schlage

Heading #: 13b

AL - cores only

1 SGL Door:231				
3' 0" x 7' 2" x 1 3/4" ALD/ALF				
1 EA	Cylinder	20-740	626	(CY-1) Schlage
note: closer: LCN 4010/4110 DEL MC AS REQ'D				

Project ID: JOB001775 - WEBSTER ISB

closer side

		1 SGL	Door:274	CORRIDOR to	MICROSCOPY ROOM	LH
	3' 6" x 7' 2" x 1 3/4"	HMD/HMF				
		WDD	CHANGE			
3 EA	Hinge	5BB1HW	4-1/2" x 4-1/2"		652	(HI-2) Ives
1 EA	Cylindrical Lock	ND80EU T D RHO	N123-062	CON	626	(LO-3) Schlage
1 EA	Cylinder	20-740			626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC	Rw/PA		AL	(CL-5) LCN Closers
1 EA	Wall Stop	WS401CCV			626	(ST-1) Ives
1 EA	Threshold	566A	48"			(TH-2) Zero International Inc
1 EA	Gasketing	475AA	42" 86"			(GA-16) Zero International Inc
1 EA	Door Bottom	3551	48"			(DB-1) Zero International Inc
1 EA	Electric Power Transfer	EPT10	CON		SP28	(EA-1) Von Duprin
1 EA	Position Switch	679-05HM				(EA-3) Schlage Electronic Security
1 EA	Wire Harness	CON-44P				(EA-4) Von Duprin
4 EA	Anchor	226				(OT-2) Zero International Inc

CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY.

AL -Cores only

	1	SGL	Door:472.1	CORRIDOR from CHEM LAB	RHR
				GENERAL	
			3' 0" x 7' 2" x 1 3/4" ALD/ALF		
	1	SGL	Door:276.1	CORRIDOR from SCIN CLASSROOM	RHR
	1	SGL	Door:283.1		
	1	SGL	Door:291.1		
Add door 292.1	1	SGL	Door:374A	CORRIDOR from BIO FAC.	RHR
				RESEARCH	
	1	SGL	Door:383.1		
	1	SGL	Door:388.1		
	1	SGL	Door:483.1		
			3' 6" x 7' 2" x 1 3/4" ALD/ALF		
				note: closer: LCN 4010/4110 DEL MC AS REQ'D	
8 EA		Cylinder	20-740		626

closer side

1 SGL Door: 133A		CORRIDOR from CONTROL ROOM		RHR
3' 0" x 7' 2" x 1 3/4" WDD/HMF				
3 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1 EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626	(LO-3) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Overhead Stop	104S	US32D	(OH-1) Glynn-Johnson
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
3 EA	Silencer	SR64-GRY		(SI-1) Ives
1 EA	Electric Power Transfer	EPT10 CON	SP28	(EA-1) Von Duprin
1 EA	Wire Harness	CON-192P		(EA-2) Von Duprin
1 EA	Position Switch	679-05HM		(EA-3) Schlage Electronic Security

CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY. CON-192 MAY NEED TO BE SPLICED IN FIELD FOR THIS OPENING.

AL -cores only

1 SGL Door: 135.1
3' 6" x 7' 2" x 1 3/4" ALD/ALF

1 EA Cylinder 20-740 626 (CY-1) Schlage
note: closer: LCN 4010/4110 DEL MC AS REQ'D

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 14a.2

			closer side	
1	SGL	Door:332.2	CORRIDOR to OFF. ADJ	LH
1	SGL	Door:353	CORRIDOR to QUAN. LAB/ INTERVIEW LAB	RH
3' 0" x 7' 2 1/4" x 1 3/4" WDD/ALF				
6	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
2	EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626 (LO-3) Schlage
2	EA	Cylinder	20-740	626 (CY-1) Schlage
2	EA	Overhead Stop	104S	US32D (OH-1) Glynn-Johnson
2	EA	Surface Closer	4040XP MC Rw/PA LCN 4010/4110 DEL MC AS REQ'D	AL (CL-5) LCN Closers
6	EA	Silencer	SR64-GRY	(SI-1) Ives
2	EA	Electric Power Transfer	EPT10 CON	SP28 (EA-1) Von Duprin
2	EA	Position Switch	679-05HM	(EA-3) Schlage Electronic Security
2	EA	Wire Harness	CON-38P	(EA-5) Von Duprin
CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY.				

Heading #: 15

			closer side	
1	PR	Door:183B.1	CORRIDOR to CADAVER LAB WORKROOM	RHA/LH
2-3' 0" x 7' 2" x 1 3/4" HMD/HMF				
6	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Dust Proof Strike	DP2	626 (BO-2) Ives
1	Set	Flush Bolt	FB31P	630 (BO-3) Ives
1	EA	Cylindrical Lock	ND80EU T D RHO N123-062 CON	626 (LO-3) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Coordinator	COR52 FL20	628 (CO-2) Ives
2	EA	Mounting Bracket	MB2	689 (CO-4) Ives
2	EA	Overhead Stop	104S	US32D (OH-1) Glynn-Johnson
2	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D (KP-4) Ives
1	EA	Gasketing	188S-CI 72" 96"	(GA-17) Zero International Inc
1	EA	Astragal	328AA 2/86" ADVISE IF MORTISED ASTRAGAL CAN BE USED THIS DOOR	(AS-3) Zero International Inc
2	EA	Electric Power Transfer	EPT10 CON	SP28 (EA-1) Von Duprin
2	EA	Position Switch	679-05HM	(EA-3) Schlage Electronic Security
2	EA	Wire Harness	CON-38P	(EA-5) Von Duprin
CARD READER TO RELEASE ELECTRIC LOCK ALLOWING ENTRY.				

Heading #: 16

			closer side	
1	PR	Door:183B.2	CADAVER LAB WORKROOM from CADAVER LAB	RHRA/LHR
2-3' 0" x 7' 2" x 1 3/4" HMD/HMF				
6	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Dust Proof Strike	DP2	626 (BO-2) Ives
1	Set	Flush Bolt	FB31P	630 (BO-3) Ives
1	EA	Cylindrical Lock	ND70 T D RHO	626 (LO-4) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Coordinator	COR52 FL20	628 (CO-2) Ives
2	EA	Mounting Bracket	MB1	689 (CO-3) Ives
2	EA	Overhead Stop	104S	US32D (OH-1) Glynn-Johnson
2	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D (KP-4) Ives
2	EA	Silencer	SR64-GRY	(SI-1) Ives

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 17

			closer side	
	1 SGL	Door:183C	CADAVER LAB to	BIO VESTIBULE LH
		3' 6" x 7' 2" x 1 3/4" HMD/HMF		
	1 SGL	Door:172A	LOADING DOCK to	RECYCLING RH 45
		3' 6" x 7' 2" x 1 3/4" HMD/HMF (45)		
6 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
2 EA	Cylindrical Lock	ND70 T D RHO	626	(LO-4) Schlage
2 EA	Cylinder	20-740	626	(CY-1) Schlage
2 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
2 EA	Kick Plate	8400 B-CS 10" x 40"	US32D	(KP-1) Ives
2 EA	Wall Stop	WS401CCV	626	(ST-1) Ives

Heading #: 18

	1 SGL	Door:352	CORRIDOR to CONF ROOM	LH
	1 SGL	Door:400A	CORRIDOR to WORK COPY	LH
		3' 0" x 7' 2 1/4" x 1 3/4" WDD/ALF		
	1 SGL	Door:114	CORRIDOR to MOCK EXAM	LH
	1 SGL	Door:116	CORRIDOR to MOCK EXAM	LH
		3' 0" x 7' 2" x 1 3/4" WDD/ALF		
	1 SGL	Door:135.2	SIM LAB to DRY SKILLS LAB	RH
	1 SGL	Door:282.3	PHYSICS LAB PREP from PHYSICS LAB	RHR
	1 SGL	Door:289B.2	MICROBIO/ PLANT RESEARCH LAB from TISSUE CULTURE B	RHR
	1 SGL	Door:386.2	BIO LAB PREP ROOM B to MOLECULAR BIO LAB	LH
	1 SGL	Door:386.3	BIO LAB PREP ROOM B to ORGANIS. BIO LAB	RH
	1 SGL	Door:389.2	BIO LAB PREP ROOM A to ANATOMY/ PHYSIO LAB	RH
	1 SGL	Door:389.3	BIO LAB PREP ROOM A to CELL BIO/BIOCHEM LAB	LH
	1 SGL	Door:478.2	CHEM LAB PREP to CHEM LAB ORGANIC	LH
	1 SGL	Door:478.3	CHEM LAB PREP to CHEM LAB GENERAL	RH
	1 SGL	Door:489.2	CHEM INSTR LAB to CHEM LAB PHYSICAL	RH
	1 SGL	Door:489.3	CHEM INSTR LAB to CHEM LAB RESEARCH	LH
		3' 0" x 7' 2" x 1 3/4" WDD/HMF		
45 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
15 EA	Cylindrical Lock	ND70 T D RHO	626	(LO-4) Schlage
15 EA	Cylinder	20-740	626	(CY-1) Schlage
15 EA	Overhead Stop	104S	US32D	(OH-1) Glynn-Johnson
45 EA	Silencer	SR64-GRY		(SI-1) Ives

Heading #: 18.1

AL - Cores only

	1 SGL	Door:131		
	1 SGL	Door:174		
		3' 6" x 7' 2" x 1 3/4" ALD/ALF		
2 EA	Cylinder	20-740	626	(CY-1) Schlage

note: closer: LCN 4010/4110 DEL MC AS REQ'D

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 18.2

1	SGL	Door: 282.2	PHYSICS LAB PREP to PHYSICS LAB LH	
1	SGL	Door: 289A.1	CELL BIO/PHYS RESEARCH LAB RHR	
			from MICROBIO PREP	
1	SGL	Door: 289A.2	MICROBIO/ PLANT RESEARCH LAB LHR	
			from MICROBIO PREP	
1	SGL	Door: 289B.1	CELL BIO/PHYS RESEARCH LAB LHR	
			from TISSUE CULTURE B	
1	SGL	Door: 374B	BIO FAC. RESEARCH from TISSUE LHR	
			CULTURE A	
		3' 6" x 7' 2" x 1 3/4" WDD/HMF		
15	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
5	EA	Cylindrical Lock	ND70 T D RHO	626 (LO-4) Schlage
5	EA	Cylinder	20-740	626 (CY-1) Schlage
5	EA	Overhead Stop	105S	US32D (OH-2) Glynn-Johnson
15	EA	Silencer	SR64-GRY	(SI-1) Ives

Heading #: 18a

1	SGL	Door: 140.2	CORRIDOR from CONF ROOM	RHR
		3' 1/4" x 8' 10 1/4" x 1 3/4" WDD/ALF		
4	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Cylindrical Lock	ND70 T D RHO	626 (LO-4) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Overhead Stop	904S	US32D (OH-4) Glynn-Johnson
1	EA	Concealed Closer	2033 STD	AL (CL-7) LCN Closers
3	EA	Silencer	SR64-GRY	(SI-1) Ives

Heading #: 18a.1

AL - cores only

1	SGL	Door: 140.1	DOOR 140.1 TO MATCH DOOR 140.2	
		3' 0" x 8' 10 1/4" x 1 3/4" ALD/ALF		
1	EA	Cylinder	20-740	626 (CY-1) Schlage

Heading #: 19

1	SGL	Door: 154	COMMONS to CONF. ROOM	LH
1	SGL	Door: 156.1	LOBBY to SM MTG/ GREEN ROOM	RH
		3' 0" x 7' 0" x 1 3/4" WDD/ALF		
1	SGL	Door: 160A	CORRIDOR from LECTURE HALL 160	LHR (45)
		3' 0" x 7' 10" x 1 3/4" WDD/HMF (45)		
1	SGL	Door: 203	RECEPTION to CONF. ROOM	LH
		3' 0" x 7' 2 1/4" x 1 3/4" WDD/ALF		
12	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
4	EA	Cylindrical Lock	ND70 T D RHO	626 (LO-4) Schlage
4	EA	Cylinder	20-740	626 (CY-1) Schlage
4	EA	Wall Stop	WS401CCV	626 (ST-1) Ives
12	EA	Silencer	SR64-GRY	(SI-1) Ives

Heading #: 19a

1	SGL	Door: 156.2	CORRIDOR to SM MTG/ GREEN ROOM	RH
		3' 0" x 7' 2" x 1 3/4" WDD/HMF		
3	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Cylindrical Lock	ND53 T D RHO	626 (LO-5) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Wall Stop	WS401CCV	626 (ST-1) Ives
3	EA	Silencer	SR64-GRY	(SI-1) Ives

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 19b

AL - cores only

1 SGL Door: 233
3' 0" x 7' 2" x 1 3/4" ALD/ALF

1 EA Cylinder 20-740 **note: closer: LCN 4010/4110 DEL MC AS REQ'D** 626 (CY-1) Schlage

Heading #: 20

closer side

1 PR Door: C270
2-3' 0" x 8' 0" x 1 3/4" WDD/HMF (90) **EAB CONNECTOR** from CORRIDOR RHRA/LHR 90

8	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
2	EA	Fire Rated Conc Vert Rod	QEL RX 9947WDC-L-NL-F 06 996L-NL CON	US26D	(ED-4) Von Duprin
2	EA	Cylinder	20-740	626	(CY-1) Schlage
2	EA	Housing	26-064	626	(CY-2) Schlage
2	EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
2	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
1	EA	Gasketing	188S-CI 72" 96"		(GA-17) Zero International Inc
2	EA	Astragal	328AA 2/86"		(AS-3) Zero International Inc
2	EA	Silencer	SR64-GRY		(SI-1) Ives
2	EA	Electric Power Transfer	EPT10 CON	SP28	(EA-1) Von Duprin
2	EA	Position Switch	679-05HM		(EA-3) Schlage Electronic Security
2	EA	Wire Harness	CON-38P		(EA-5) Von Duprin
1	EA	Power Supply	PS904 900-4RL		(PS-1) Von Duprin

BOTH DEVICES ARE NL TRIM. DT TRIM NOT RECOMMENDED FOR FIRE DEVICES.

Heading #: 20a

AL cores only

1 PR Door: C153
2-3' 0" x 8' 10" x 1 3/4" ALD/ALF

1 EA Cylinder 20-740 626 (CY-1) Schlage

Heading #: 20b

closer side

1 PR Door: 150
2-3' 0" x 7' 2" x 1 3/4" WDD/HMF **EAB CONNECTOR** from CORRIDOR RHRA/LHR

6	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1	EA	Electrified Multi-Point Lock	LM9291EL 06A	626	(LO-6) Schlage
1	EA	Electrified Multi-Point Lock	LM9295EL T 06A	626	(LO-7) Schlage
2	EA	Cylinder	20-740	626	(CY-1) Schlage
2	EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
2	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
2	EA	Silencer	SR64-GRY		(SI-1) Ives
2	EA	Electric Power Transfer	EPT10 CON	SP28	(EA-1) Von Duprin
2	EA	Wire Harness	CON-192P		(EA-2) Von Duprin
2	EA	Position Switch	679-05HM		(EA-3) Schlage Electronic Security
1	EA	Power Supply	PS904 900-4RL		(PS-1) Von Duprin

CON-192P WILL NEED TO BE SPLICED IN FIELD FOR THIS OPENING.

HARDWARE FINISH TO MATCH HARDWARE
FINISH IN EAB. VERIFY FINISH

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

CHANGE DOOR TO HMD
PER DOOR SCHEDULE
MARKS

Heading #: 20c

	1	PR	Door: C170	CORRIDOR to EAB CONNECTOR	RHR/LHR	45
			2-3' 6" x 8' 9" x 1 3/4" WDD/HMF (45)			
			HMD			
8	EA	Pivot	91105F	US32D	(PV-1) Ives	
2	EA	Fire Rated Conc Vert Rod	9447L-BE-F 06 940L-BE	US26D	(ED-5) Von Duprin	
2	EA	Surface Closer	4003T STD TBWMS	AL	(CL-3) LCN Closers	
2	EA	Electromagnetic Holder	SEM7840	AL	(ST-2) LCN Closers	
1	EA	Gasketing	188S-CI 84" 108"		(GA-18) Zero International Inc	
2	EA	Astragal	328AA 2/108"		(AS-4) Zero International Inc	

94 Series INPACT Device for HMD only.
Recommend 9947WDC-L-BE-F 06

4'-7" PER DOOR
SCHEDULE MARKS

Heading #: 21

	1	SGL	Door: 100A	WORK COPY to CORRIDOR		
			4' 8" x 7' 4" x 1 3/4" WDD/			
	1	SGL	Door: 200A	WORK/COPY	Pocket	
	1	SGL	Door: 300A	WORK COPY	Pocket	
			5' 2" x 7' 4" x 1 3/4" WDD/			
3	EA	Brio SR18057GN-1ss-10 6RB/94-94P/94PA-180DS	Brio SR18057GN-1SS-106RB		(SL-1) Other	
3	EA	Pocket Door Lock	SD-2001SDL-3-S2002T-S2002		(LO-8) Accurate Lock and Hardware	
3	EA	690 Edge Pull	690 Edge Pull	US32D	(LO-9) Other	
3	EA	Housing	26-064	626	(CY-2) Schlage	
3	EA	Cylinder	20-079	626	(CY-3) Schlage	

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 22

1	SGL	Door:101	CORRIDOR to OFFICE STAFF	RH
1	SGL	Door:104	CORRIDOR to OFF. NA.	LH
1	SGL	Door:105	CORRIDOR to OFF. NA.	LH
1	SGL	Door:106	CORRIDOR to OFF. NA.	RH
1	SGL	Door:107	CORRIDOR to OFF. NA.	RH
1	SGL	Door:108	CORRIDOR to OFF. NA.	LH
1	SGL	Door:109	CORRIDOR to OFF. NA.	LH
1	SGL	Door:111	CORRIDOR to OFF. NU	RH
1	SGL	Door:113	CORRIDOR to OFF. NU	LH
1	SGL	Door:115	CORRIDOR to OFF. NU	RH
1	SGL	Door:117	CORRIDOR to OFF. FUT	LH
1	SGL	Door:205	CORRIDOR to OFF. GLOBAL	RH
1	SGL	Door:206	CORRIDOR to OFF. DEAN'S ASSIST.	LH
1	SGL	Door:207	CORRIDOR to OFF. STRATEGIC	LH
1	SGL	Door:208	CORRIDOR to OFF. ASSESSMENT	RH
1	SGL	Door:209	CORRIDOR to OFF. ASSOC. DEAN	RH
1	SGL	Door:211	CORRIDOR to OFF. ASSOC. DEAN	LH
1	SGL	Door:212	CORRIDOR to OFF. COMMUNICATIONS	LH
1	SGL	Door:214	CORRIDOR to OFF. COMMUNICATIONS	RH
1	SGL	Door:304	CORRIDOR to HR WS OFF.	LH
1	SGL	Door:305.1	CORRIDOR to OFF. STAFF	RH
1	SGL	Door:306	CORRIDOR to OFF. SCI	RH
1	SGL	Door:311	CORRIDOR to OFF. SCI	RH
1	SGL	Door:313	CORRIDOR to OFF. SCI	LH
1	SGL	Door:314	CORRIDOR to OFF. SCI	LH
1	SGL	Door:315	CORRIDOR to OFF. SCI	RH
1	SGL	Door:316	CORRIDOR to OFF. ASP	RH
1	SGL	Door:317	CORRIDOR to OFF. SCI	LH
1	SGL	Door:318	CORRIDOR to OFF. ASP	LH
1	SGL	Door:319	CORRIDOR to OFF. SCI	RH
1	SGL	Door:320	CORRIDOR to OFF. ASP	RH
1	SGL	Door:321	CORRIDOR to OFF. SCI	LH
1	SGL	Door:322	CORRIDOR to OFF. ASP	LH
1	SGL	Door:323	CORRIDOR to OFF. SCI	RH
1	SGL	Door:325	CORRIDOR to INTERVIEW/ CONF.	RH
1	SGL	Door:327	CORRIDOR to OFF. ASP	LH
1	SGL	Door:329	CORRIDOR to OFF. ASP	RH
1	SGL	Door:331	CORRIDOR to OFF. ASP	LH
1	SGL	Door:333	CORRIDOR to OFF. ASP	RH
1	SGL	Door:335	CORRIDOR to OFF. ASP	LH
1	SGL	Door:337	CORRIDOR to OFF. ASP	RH
1	SGL	Door:342	COMMONS to OFF. ASP	LH
1	SGL	Door:344	COMMONS to OFF. ASP	RH
1	SGL	Door:346	COMMONS to OFF. ASP	LH
1	SGL	Door:348	COMMONS to OFF. ASP	RH
1	SGL	Door:360	CORRIDOR to OFF. ASP	RH
1	SGL	Door:362	CORRIDOR to OFF. HR DIR	LH
1	SGL	Door:364	COMMONS to SM. MTG.	RH
1	SGL	Door:372D	COMMONS to OFF. LAB MGR.	RH
1	SGL	Door:401	CORRIDOR to OFF. ADJ	LH
1	SGL	Door:402	CORRIDOR to OFF. WORK STUDY	RH
1	SGL	Door:403	CORRIDOR to OFF. FLX	RH
1	SGL	Door:404	CORRIDOR to OFF. FLX	LH
1	SGL	Door:405	CORRIDOR to OFF. FLX	LH
1	SGL	Door:406	CORRIDOR to OFF. ADJ	RH

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 22

1	SGL	Door:407.1	CORRIDOR to OFF. STAFF	RH
1	SGL	Door:407.2	CORRIDOR to OFF. STAFF	LH
1	SGL	Door:411	COMMONS to OFF. FLX	RH
1	SGL	Door:412	CORRIDOR to TESTING	RH
1	SGL	Door:413	CORRIDOR to OFF. IL	RH
1	SGL	Door:414	CORRIDOR to TESTING	RH
1	SGL	Door:415	CORRIDOR to OFF. IL	LH
1	SGL	Door:416	CORRIDOR to OFF. IL WS	LH
1	SGL	Door:417	CORRIDOR to OFF. IL	RH
1	SGL	Door:419	CORRIDOR to TRANSLATION	RH
1	SGL	Door:432	CORRIDOR to OFF. ADJ	RH
1	SGL	Door:433	CORRIDOR to OFF. IL	RH
1	SGL	Door:434	CORRIDOR to OFF. ADJ	LH
1	SGL	Door:435	CORRIDOR to OFF. IL	LH
1	SGL	Door:437	CORRIDOR to OFF. IL	RH
1	SGL	Door:439	CORRIDOR to OFF. ESL	LH
1	SGL	Door:441	CORRIDOR to SM. MTG.	RH

3' 0" x 7' 2 1/4" x 1 3/4" WDD/ALF

1	SGL	Door:144	CORRIDOR to OFF. NU/NA	RH
1	SGL	Door:452	CORRIDOR to OFF. TA	LH
1	SGL	Door:454	CORRIDOR to OFF. INTL	LH
1	SGL	Door:456	CORRIDOR from OFF SAFETY OFFICER	RH

3' 0" x 8' 10 1/4" x 1 3/4" WDD/ALF

1	SGL	Door:305.2	CORRIDOR to OFF. STAFF	LH
---	-----	------------	------------------------	----

3' 1/8" x 7' 2 1/4" x 1 3/4" WDD/ALF

Provide 4 hinges

NOTE DOOR TYPE FT1:
7'-2" HIGH OPERABLE
PANEL W/ FIXED
TRANSOM ABOVE

232	231	EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
	77	EA	Cylindrical Lock	ND53 T D RHO	626	(LO-5) Schlage
	77	EA	Cylinder	20-740	626	(CY-1) Schlage
	77	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
	231	EA	Silencer	SR64-GRY		(SI-1) Ives
	77	EA	Coat Hook	572	626	(OT-1) Ives
	77	EA	Coat hook	CH23	626	(OT-3) Doug Mockett

Heading #: 22A

1	SGL	Door:160B	CORRIDOR to CONTROL ROOM	RH
---	-----	-----------	--------------------------	----

3' 0" x 7' 2" x 1 3/4" WDD/HMF (45)

3	EA	Hinge	5BB1 4-1/2" x 4-1/2"	652	(HI-1) Ives
1	EA	Cylindrical Lock	ND53 T D RHO	626	(LO-5) Schlage
1	EA	Cylinder	20-740	626	(CY-1) Schlage
1	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
1	EA	Threshold	657A 36" V3 -7"		(TH-9) Zero International Inc
1	EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc
1	EA	Door Bottom	3551 36"		(DB-2) Zero International Inc
1	EA	Coat Hook	572	626	(OT-1) Ives
1	EA	Coat hook	CH23	626	(OT-3) Doug Mockett

Provide closer for rated opening.

Provide #225 anchors as specified

USE 5" MAX WIDTH TO
MATCH FRAME WIDTH

45

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 23

1	SGL	Door:332.1	CORRIDOR to OFF. ADJ	LH
		3' 0" x 7' 2 1/4" x 1 3/4" WDD/ALF		
3'-0"	1	SGL	Door:215	CORRIDOR to DEAN'S OFFICE
		3' 7/8" x 7' 2 1/4" x 1 3/4" WDD/ALF		LH
6	EA	Hinge	5BB1 4-1/2" x 4-1/2"	652 (HI-1) Ives
2	EA	Cylindrical Lock	ND53 T D RHO	626 (LO-5) Schlage
2	EA	Cylinder	20-740	626 (CY-1) Schlage
2	EA	Overhead Stop	104S	US32D (OH-1) Glynn-Johnson
6	EA	Silencer	SR64-GRY	(SI-1) Ives

advise if
exposed metal
channel at
edge

Heading #: 24

1	PR	Door:160.1	LOBBY from closer side LECT. ENTRY	RHR/LHR	45
		2-3' 0" x 8' 10" x 1 3/4" WDD/HMF (45)			
8	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
2	EA	Fire Rated Conc Vert Rod	9947WDC-L-F LBR 996L(Std)	US26D	(ED-6) Von Duprin
2	EA	Extension Rod Kit	ER-ADJ10-33A/99	US26D	(ED-7) Von Duprin
2	EA	Cylinder	20-740	626	(CY-1) Schlage
2	EA	Cylinder	20-079	626	(CY-3) Schlage
2	EA	Surface Closer	4040XP MC Rw/PA LCN 4010/4110 DEL MC AS REQ'D AL	AL	(CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D	(KP-4) Ives
2	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
1	EA	Gasketing	188S-CI 84" 108"		(GA-18) Zero International Inc
2	EA	Astragal	328AA 2/108" 8194AA		(AS-4) Zero International Inc

Heading #: 25

1	PR	Door:160.2	closer side LECT. ENTRY from LECTURE HALL	RHR/LHR	
		2-3' 0" x 8' 10" x 1 3/4" WDD/HMF	160		
8	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
2	EA	Touch Bar	330	US26D	(ED-8) Von Duprin
2	EA	Surface Closer	4040XP MC Rw/PA LCN 4010/4110 DEL MC AS REQ'D AL	AL	(CL-5) LCN Closers
2	EA	Kick Plate	8400 B-CS 10" x 35"	US32D	(KP-4) Ives
2	EA	Wall Stop	WS401CCV	626	(ST-1) Ives
1	EA	Gasketing	188S-CI 84" 108"		(GA-18) Zero International Inc
1	EA	Astragal	328AA 2/108" Provide 36AA meeting stile as specified		(AS-4) Zero International Inc

Heading #: 26

AL - by others

1	SGL	Door:276.2	CORRIDOR from SCIN CLASSROOM	LHR
1	SGL	Door:283.2		
1	SGL	Door:291.2		
1	SGL	Door:483.2		
		3' 6" x 7' 2" x 1 3/4" ALD/ALF		

Heading #: 27

1	SGL	Door:202	COMMONS from closer side RECEPTION	LHR
		3' 0" x 9' 4" x 1 3/4" WDD/ALF	NOTE: 8'-6" HIGH DOOR W/ 10" HIGH FLUSH TRANSOM PANEL ABOVE	
4	EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652 (HI-2) Ives
1	EA	Cylindrical Lock	ND70 T D RHO	626 (LO-4) Schlage
1	EA	Cylinder	20-740	626 (CY-1) Schlage
1	EA	Overhead Stop	104S	US32D (OH-1) Glynn-Johnson
1	EA	Surface Closer	4040XP MC Rw/PA	AL (CL-5) LCN Closers
3	EA	Silencer	SR64-GRY	(SI-1) Ives

COORDINATE MOUNTING ON
FLUSH TRANSOM PANEL
ABOVE DOOR.

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 28

1 SGL Door: C210 CORRIDOR to closer side CORRIDOR C210 LH
3' 0" x 7' 2" x 1 3/4" WDD/ALF

3 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1 EA	Cylindrical Lock	ND70 T D RHO	626	(LO-4) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
1 EA	Wall Stop	WS401CCV	626	(ST-1) Ives
3 EA	Silencer	SR64-GRY		(SI-1) Ives

Heading #: 29

AL - Cores only

1 SGL Door: C230A
3' 2" x 7' 2" x 1 3/4" ALD/ALF

1 EA	Cylinder	20-740	626	(CY-1) Schlage
------	----------	--------	-----	----------------

Heading #: 30

AL - Cores only

1 PR Door: C250A
2-3' 0" x 7' 10 1/2" x 1 3/4" ALD/ALF

1 EA	Cylinder	20-740	626	(CY-1) Schlage
------	----------	--------	-----	----------------

Heading #: 31

AL - cores only

1 SGL Door: 284.1
1 SGL Door: 284.2
1 SGL Door: 378.1
1 SGL Door: 378.2
1 SGL Door: 383.2
1 SGL Door: 388.2
1 SGL Door: 391.1
1 SGL Door: 391.2
1 SGL Door: 472.2

1 SGL Door: 480.1
1 SGL Door: 480.2
1 SGL Door: 488.1
1 SGL Door: 488.2
1 SGL Door: 491.1
1 SGL Door: 491.2

CORRIDOR from CHEM LAB
GENERAL LHR

3' 6" x 7' 2" x 1 3/4" ALD/ALF

note: closer: LCN 4010/4110 DEL MC AS REQ'D

15 EA	Cylinder	20-740	626	(CY-1) Schlage
-------	----------	--------	-----	----------------

Heading #: 32

1 SGL Door: S340.2 CORRIDOR to closer side STAIR 1-3 RH 90
3' 0" x 7' 2" x 1 3/4" WDD/HMF (90)

3 EA	Hinge	5BB1HW 4-1/2" x 4-1/2"	652	(HI-2) Ives
1 EA	Cylindrical Lock	ND70 T D RHO	626	(LO-4) Schlage
1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Surface Closer	4040XP MC Rw/PA	AL	(CL-5) LCN Closers
1 EA	Kick Plate	8400-B CS 40" x 34"	US32D	(KP-2) Ives
1 EA	Wall Stop	WS401CCV	626	(ST-1) Ives
1 EA	Gasketing	188S-CI 36 96		(GA-7) Zero International Inc
1 EA	Sweep	339AA 36"	match SW 7004 Snowbound	(SW-2) Zero International Inc

SWEEP IS FIGURED AS ~~CLEAR ALUMINUM FINISH.~~

Hardware Schedule

Project ID: JOB001775 - WEBSTER ISB

Heading #: 33

AL - cores only

1 SGL Door:376
3' 4" x 7' 0" x 3" Other/

1 EA	Cylinder	20-740	626	(CY-1) Schlage
1 EA	Housing	26-064	626	(CY-2) Schlage
1 EA	Cylinder	20-079	626	(CY-3) Schlage



49 Airport Rd.
St. Louis, MO 63135
314-522-0579

Date: 12/11/16

To: Paric
Attn: Matt Horton
Phone: 636 561-9841

Project: Webster ISB – Changes per partial return Hardware
Location: St Louis Mo
Quoted By: Darryl Stith (Direct Line 314 595-4409)

We propose to furnish the following materials, delivery included and tax not included, for the above referenced project.

140.1
Add hardware group 18a

Written authorization to proceed is required to place materials on order.

Total Price For Above Items:

ADD \$ 953.00

Conditions: Sales tax NOT included. Tax rate 9.113%. Payment terms, Net 30 days, pending credit approval. Quote is valid for 30 days. Material ONLY, no labor included.



49 Airport Rd. | St. Louis, MO 63135 | 800-456-6540

Date: 01-05-2017

To: Paric
Attn: Matt Horton
Phone: 636 561-9841
E-mail: mrhorton@paric.com

Project: Webster ISB – Primus cores
Location: St. Louis, MO.
Architect: Cannon Design

Quoted By: Darryl Stith
Phone: (314) 595-4409
E-Mail: dstith@negwer.com

We propose to delete the following materials for the above referenced project.

Primus cores

Delete 217ea. 20-740 Primus Cores

< \$12,798.00 >

*** Written authorization to proceed is required to place materials on order.

General Qualifications-

=====

TOTAL FOR ABOVE MATERIALS AS LISTED

< \$ 12,798.00 > (tax not included)

Conditions: Sales tax NOT included. Tax rate 9.113%. Payment terms, Net 30 days, pending credit approval. Quote is valid for 30 days. Material ONLY, no labor included.

NGG LTD., INC1850 CRAIGSHIRE RD.
ST. LOUIS, MISSOURI, 63146**NGG****CHANGE ORDER REQUEST**NGG PROJECT NUMBER: PROJECT NAME:

OWNER:

DATE OF CHANGE ORDER: CHANGE ORDER NUMBER:

SUBCONTRACT FOR:

Glass & Glazing

TO: Paric - Attn: Jason Szachnieski

CHANGE ORDER AMOUNT: ADD: DEDUCT: CHANGE ORDER TOTAL: ADD:

ORIGINAL CONTRACT SUM WAS.....
NET BY PREVIOUS CHANGE ORDERS.....
CONTRACT SUM PRIOR TO THIS CHANGE ORDER.....
CURRENT CHANGE ORDER AMOUNT.....
NEW CONTRACT AMOUNT INCLUDING THIS CHANGE ORDER WILL BE.....
THE SCHEDULE WILL BE CHANGED BY 0 DAYS.....

\$	-
\$	-
\$	(1,458.00)
\$	(1,458.00)
	-

ORIGIN: _____

DESCRIPTION:

DELETE DOOR 140.1 AND RELATED HARDWARE

CHANGE ORDER DETAILS (ADDS)

DESCRIPTION	Material/Labor	Allow Markup	TOTAL
		\$ -	\$ -
	\$ -	\$ -	\$ -
	\$ -	\$ -	\$ -
	\$ -	\$ -	\$ -
TOTAL	\$ -	\$ -	\$ -

CHANGE ORDER DETAILS (DEDUCTS)

DESCRIPTION	Material/Labor	Allow Markup	TOTAL
See attached breakdown for specifics	\$ 1,458.00	\$ -	\$ 1,458.00
	\$ -	\$ -	\$ -
TOTAL	\$ 1,458.00	\$ -	\$ 1,458.00

Paric

NGG Ltd., Inc.

BY: _____

BY: _____

Daniel Ward - Project Manager

TITLE: _____

DATE: _____

DATE: 3/2/17

PROJECT	WEBSTER UNIVERSITY							
SUBJECT	DELETE ALUMINUM DOOR #140.1 - WAS CHANGED TO A WOOD DOOR							
DESCRIPTION	QTY	UNIT		RATE / UNIT PRICE		SUBTOTAL	OH/M	TOTAL
ENGINEERING								
STRUCTURAL CALCULATIONS / RESOLUTION		HRS	@	\$100.00	=	\$0.00		\$0.00
DRAFTING (DETAILS & ELEVATIONS)		HRS	@	\$75.00	=	\$0.00		\$0.00
PRECONSTRUCTION SERVICES MANAGER		HOURS	@	\$100.00		\$0.00		\$0.00
MATERIAL								
			@		=	\$0.00	\$0.00	\$0.00
Aluminum Door 140.1	1	each	@	\$487.56	=	\$487.56	\$73.13	\$560.69
Hardware for Door 140.1	1	Lot	@	\$501.73	=	\$501.73	\$75.26	\$576.99
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
Sales Tax Exempt			@			\$0.00	\$0.00	\$0.00
			@		=	\$0.00	\$0.00	\$0.00
			@			\$0.00	\$0.00	\$0.00
			@			\$0.00	\$0.00	\$0.00
Ironworkers					=			
Labor to Install Door 140.1	4	HRS	@	\$80.00	=	\$320.00		\$320.00
		HRS	@		=	\$0.00		\$0.00
		HRS	@		=	\$0.00		\$0.00
		HRS	@		=	\$0.00		\$0.00
			@					
EQUIPMENT								
BOOM / SCISSOR RENTAL (DAY)		LUMP	@		=	\$0.00	\$0.00	\$0.00
DELIVERY / PICKUP		LUMP	@	\$300.00	=	\$0.00	\$0.00	\$0.00
TAX (EQUIPMENT ONLY)		LUMP	@		=	\$0.00	\$0.00	\$0.00
GRAND TOTAL						\$1,309.29	\$148.39	\$1,457.68