



PARIC CORPORATION
77 Westport Plaza Suite 250
St. Louis, MO 63146
TEL: 636-561-9500
FAX: 636-561-9501

REQUEST FOR INFORMATION DATE: April 11, 2016 NO.: RFI-028

To: Cannon Design

Attn: Kelvin Patel

From: Paric Corporation

Requested By: Devin Gates

Project Name: Webster University Interdisciplinary Science Building Project No.: 15051

Subject: BP 3 - pre-bid clarifications

Response Required By: April 18, 2016

Drawing / Spec Reference:

Information Requested:

REQUEST:

1. The kitchen island in Teaching Kitchen 174 does not have any section for detail cuts, please provide more detail.
2. Please confirm that the 1st and 2nd levels do NOT have wood jambs at the corridors, it appears these only occur on Levels 3 and 4.
3. Section cut 1/A0802 is called out on elevation 1/A0606, however drawing A0802 does not exist, please advise the correct section cut.
4. Time-Out Board is shown on 11/A0611 – what is a Time-Out Board? Who furnishes and installs it?
5. Section 114000 Food Service Equipment is confusing – equipment is listed on Pages 6-9, to the right of the Item some of the equipment is listed as N.I.C.; on the next line there are statements that the equipment is furnished and installed by the GC, Plumber or HVAC. Please revise and re-issue as a part of Bid Package No. 3

Suggestion: Please advise

Response:

.


ARCHITECT'S RESPONSE:

This information is provided as an interpretation of the Contract Documents for implementation. It is not an authorization for change to the Contract Sum or Contract Time. If this information results in a claim for a change to the Contract, the Contractor shall notify the [Construction Manager][Architect] of a change through the change process.

Answered By: _____

Date: **APRIL 14, 2016**

1. KITCHEN ISLAND HAS 1-1/2" THK. QUARTZ COUNTERTOP WITH WATERFALL EDGE. SEE SKETCH BELOW FOR FRONT OF THE ISLAND AND ELEVATION 2/A0607 FOR CASEWORK ON THE OTHER SIDE.



2. WOOD JAMBS AT THE CORRIDORS ARE A TYPICAL CONDITION AT LEVELS 01, 02, 03 & 04. REFER KEYED NOTE 2 ON INTERIOR DRAWINGS ID0101 - ID0104. ALSO REFER INTERIOR DRAWINGS FOR FINISHES.

3. SHEET A0802 WILL BE ISSUED IN UPCOMING ADDENDUM.

4. TIME-OUT BOARD IS A TYPE OF MARKER BOARD. IT IS 'OFOI' ITEM PER EQUIPMENT SCHEDULE ON SHEET A1101 - EQUIPMENT NUMBER 06.10.14. PROVIDE BACKING FOR INSTALLATION OF TIME-OUT BOARD.

5. N.I.C. REFERS ONLY TO KITCHEN EQUIPMENT CONTRACTOR. AS SPECIFIED THEY ARE FURNISHED AND INSTALLED BY GC, PLUMBER OR HVAC.