



PARIC CORPORATION
77 Westport Plaza Suite 250
St. Louis, MO 63146
TEL: 636-561-9500
FAX: 636-561-9501

REQUEST FOR INFORMATION **DATE:** May 19, 2016 **NO.:** RFI-100

To: Cannon Design

Attn: Kelvin Patel

From: Paric Corporation

Requested By: Joe Voypick

Project Name: Webster University Interdisciplinary Science Building Project No.: 15051

Subject: Emergency shower in room 272A

Response Required By: May 26, 2016

Drawing / Spec Reference:

Information Requested:

Plumbing plans call for an ES-1 Emergency eyewash/shower unit in Room 272A Chem Stock Room. The placement of this unit overlaps and is behind one of the shelves. There is 1'-11 5/16" of space from the edge of the wall to the side of the shelving, as dimensioned from the architectural model. The eyewash unit has a width of over 27" from flange to flange. Placing the emergency unit as close to the edge of the wall as possible will result in nearly all of (if not all of) the emergency shower pull lever to be blocked by the shelving. (See attached product data and sketch). Please verify it is acceptable to install the unit as shown on the architectural/plumbing plans.

Response: The basis of design for the emergency shower is Guardian model GBF2150, which is 21 inches wide. A partial cut sheet received with the RFI is for a Bradley unit, 27- 5/8 inches wide. The architect selected the locations of the emergency showers. This RFI should be directed to the architect for clarification.

ARCHITECT'S RESPONSE:

This information is provided as an interpretation of the Contract Documents for implementation. It is not an authorization for change to the Contract Sum or Contract Time. If this information results in a claim for a change to the Contract, the Contractor shall notify the [Construction Manager][Architect] of a change through the change process.


Cc: Kathy Bathe, Paric Corporation


Answered By: Mike Whitworth - WES

Date: May 20, 2016



S19345JXB, S19345JFB, S19345JXBT, S19345JFBT
Barrier-Free Recessed Drench Shower and Halo Eye/Face Wash





CHEM S
ROO

272