



PARIC CORPORATION
77 Westport Plaza Suite 250
St. Louis, MO 63146
TEL: 636-561-9500
FAX: 636-561-9501

REQUEST FOR INFORMATION **DATE:** February 13, 2017 **NO.:** RFI-445

To: Cannon Design

Attn: Kelvin Patel

From: Paric Corporation

Requested By: Joe Voypick

Project Name: 15051-Webster University Interdisciplinary Science Building Project No.: 15051

Subject: Mullion Mate Color

Response Required By: February 20, 2017

Drawing / Spec Reference:

Information Requested:

Specification 092900-2.6.C calls out for extruded aluminum trim and reveals to be used as called out of the drawings. Details 9/A0810 and 5/A0811 call out for "092900 Mullion Closure: Basis of Design: Gordon Mullion Mate- Extend to bottom of surface above". The standard finish, which was carried in the budget, is clear anodized. This is because no color was called out in specs or drawings. Please confirm that this is the finish that is wanted for these products.

Response:

Attached are the standard, stocked colors for Gordon trim.

For the Mullion Mate and for the other extruded trims on the project, we would like one of the four available whites – please provide samples of all white colors from Gordon for selection.

Design intent is to select the one that most closely matches Sherwin Williams SW 7004 Snowbound.

ARCHITECT'S RESPONSE:

This information is provided as an interpretation of the Contract Documents for implementation. It is not an authorization for change to the Contract Sum or Contract Time. If this information results in a claim for a change to the Contract, the Contractor shall notify the [Construction Manager][Architect] of a change through the change process.


Answered By: Kelvin Patel

Date: 02/16/2017


POWDER COAT COLOR CHART

GORDON
INCORPORATED


STANDARD FINISHES


REGAL WHITE


PDR-20100
GLOSS 5 +/-5
LIGHT REFLECTANCE 75


CLEANROOM WHITE


PDR-20101
GLOSS 45 +/-5
LIGHT REFLECTANCE 83


PARCHMENT WHITE

PDR-20108
GLOSS 20 +/-5
LIGHT REFLECTANCE 70


SECURITY WHITE


PDR-20127
GLOSS 50 +/-5
LIGHT REFLECTANCE 78


BARONET BEIGE

PDR-20900
GLOSS 5 +/-5
LIGHT REFLECTANCE 48


DARK BRONZE

PDR-20205
GLOSS 15 +/- 5
LIGHT REFLECTANCE 9



GRAPHITE BLACK

PDR-20400
GLOSS 20 +/-5
LIGHT REFLECTANCE 8



BLACK JACK

PDR-20407
GLOSS 40 +/-5
LIGHT REFLECTANCE 5


PREMIUM FINISHES


DRIFTWOOD GRAY


PDR-20700
GLOSS 5 +/-5
LIGHT REFLECTANCE 36


ANODIZED ALUMINUM

PDR-20803
GLOSS 10 +/-5
LIGHT REFLECTANCE 36


ASTI II

PDR-20811
GLOSS 10 +/-5
LIGHT REFLECTANCE 27


COPPERPLATE

PDR-21408
GLOSS 15 +/- 5
LIGHT REFLECTANCE 15

Gordon stocks all finishes featured. Gordon has virtually unlimited custom color matching capabilities. Antimicrobial finishes are also available.

Finish samples shown on this card are digital replications of the actual paint finishes and may vary slightly in color. Color samples, supplied on an aluminum panel, provide an actual representation of color, gloss, texture, and hue and are available upon request.

Gloss levels are expressed from measurement on a 60° gloss meter.

5023 HAZEL JONES ROAD, BOSSIER CITY, LA 71111

POWDER COAT

TECHNICAL INFORMATION



Our durable powder coat finishes are offered in acrylics, polyesters, hybrids, and epoxies. Gordon powder coat finishes are environmentally friendly, solvent-free, and nonflammable. No volatile organic compounds (VOCs) are emitted into the atmosphere during or after application.

TECHNICAL DATA

GLOSS	5 - 85+	ASTM D523	MANDREL BEND	1/8"	ASTM D522
COLOR RANGE	Wide		ADHESION	5b	ASTM D3359
TEXTURE	Limited		MACHINE ABILITY	Pass	Drill 1/4" hole
IMPACT RESISTANCE	160 / 160	ASTM D2794	QUV-B 313	200 hours	ASTM D4587
SMOOTHNESS	8 - 10	Ford Scale	SALT SPRAY RESISTANCE	1000 hours	ASTM B117
PENCIL HARDNESS	2H	ASTM D3363	HUMIDITY RESISTANCE	1500 hours	ASTM 2247
TABER ABRASION	80	ASTM D4060			

All testing utilized a .063" aluminum substrate and a film thickness of 1.9 - 2.0 mils.

ENVIRONMENTAL POLICY

Our in-house finishing facility uses only water-soluble materials in our pre-treatment process. All overflow from this process is approved for introduction into our city water treatment plant without adverse impact to the environment. Gordon powder coat finishes are EPA compliant and contribute to the U.S. Green Building initiative.

Gordon's environmental commitment is affirmed within our core *Values, Beliefs, and Principles*. Waste reduction and recycling are key elements of our business culture and are embraced by all Gordon team members.



5023 HAZEL JONES ROAD, BOSSIER CITY, LA 71111
 800.747.8954
 800.877.8746 FAX
 SALES@GORDON-INC.COM
 GORDON-INC.COM
 AN EMPLOYEE OWNED COMPANY

