Product Information

DOW CORNING

Silicone Sealants

Dow Corning® 795 Silicone Building Sealant

Neutral, one-part silicone sealant

FEATURES

- Suitable for most new construction and remedial sealing applications
- Versatile – high performance structural glazing and weather sealing from a single product
- Available in 13 standard colors; custom colors also available

BENEFITS

- Excellent weatherability – virtually unaffected by sunlight, rain, snow, ozone and temperature extremes of - 40°F (-40°C) to 300°F (149°C)
- Excellent unprimed adhesion to a wide variety of construction materials and building components, including anodized, alodined, most coated and many Kynar® [1]-painted aluminums[2]
- Ease of application – ready to use as supplied
- Ease of use – all-temperature gunnability, easy tooling and low-odor cure byproduct
- Meets global standards (Americas, Asia and Europe)

COMPOSITION

- One-part, neutral-cure, RTV silicone sealant

APPLICATIONS

- Structural and nonstructural glazing
- Structural attachment of many panel systems
- Panel stiffener applications
- Weather sealing of most common construction materials including glass, aluminum, steel, painted metal, EIFS, granite and other stone, concrete, brick and plastics

TYPICAL PROPERTIES

Specification Writers: These values are not intended for use in preparing specifications. Please contact your local Dow Corning sales office or your Global Dow Corning Connection before writing specifications on this product.

Method	Test	Unit	Result
As Supplied			
ASTM C 679	Tack-Free Time, 50% RH	hours	3
	Curing Time at 25°C (77°F) and 50% RH	days	7-14
	Full Adhension	days	14-21
ASTM C 639	Flow, Sag or Slump	Inches (mm)	0.1 (2.54)
	Working Time	minutes	20-30
	VOC Content[1]	g/L	28
As Cured-After 21 days at 25 C (77 F) and 50% RH			
ASTM D 2240	Durometer Hardness, Shore A	points	35
ASTM C 794	Peel Strength	lb/in (kg/cm)	32 (5.7)
ASTM C 1135	Tension Adhension Strength		
	At 25% extension	psi (MPa)	45 (0.310)
	At 50% extension	psi (MPa)	60 (0.414)
ASTM C 719	Joint Movement Capability	percent	±50
ASTM C 1248	Staining (granite, marble, lime-Stone, brick and concrete)		None
As Cured-After 21 days at 25 C (77 F) and 50% RH followed by 10,000 hours in a QUV weatherometer, ASTM G 53			
ASTM C 1135	Tensile Adhesion Strength		
	At 25% extension	psi (MPa)	35 (0.241)
	At 50% extension	psi (MPa)	50 (0.345)

Based on South Coast Air Quality Management District of California. Maximum VOC is listed both inclusive and exclusive of water and exempt compounds. For a VOC data sheet for a specific sealant color, please send your request to product.inquiry@dowcorning.com.

DESCRIPTION

Dow Corning® 795 Silicone Building Sealant is a one-part, neutral-cure, architectural-grade sealant that easily extrudes in any weather and cures quickly at room temperature.

This cold-applied, non-sagging silicone material cures to a medium-modulus silicone rubber upon exposure to atmospheric moisture. The cured sealant is durable and flexible enough to accommodate ±50 percent movement of original joint dimension

[1]Kynar is a trademark of Atofina Chemicals Inc.
[2]Contact your local Dow Corning Sales Application Engineer for specifics.

when installed in a properly designed weather seal joint. In a properly designed structurally glazed joint, the sealant is strong enough to support glass and other panel materials under high wind load.

APPROVALS/ SPECIFICATIONS

Dow Corning 795 Silicone Building Sealant meets the requirements of:

- Federal Specification TT-S 001 543A (COM-NBS) Class A for silicone building sealants
- Federal Specification TT-S-00230C (COM-NBS) Class A for one- component building sealants
- ASTM Specification C 920 Type S, Grade NS, Class 50, Use NT, G, A and O
- ASTM Specification C 1184 for structural silicone sealants
- Canadian Specification CAN2-19.13- M82



COLORS

Dow Corning 795 Silicone Building Sealant is available in 13 colors: white, limestone, champagne, natural stone, gray, black, bronze, sandstone, adobe tan, dusty rose, rustic brick, blue spruce, and charcoal. Custom colors may be ordered to match virtually any substrate.

HOW TO USE

Please consult the Dow Corning Americas Technical Manual, Form No. 62-1112, for detailed information on state-of-the- art application methods and joint design. Please contact your local Dow Corning Sales Application Engineer for specific advice.

Preparation

Clean all joints, removing all foreign matter and contaminants such as grease, oil, dust, water, frost, surface dirt, old sealants or glazing compounds and protective coatings.

Application Method

Install backing material or joint filler, setting blocks, spacer shims and tapes. Mask areas adjacent to joints to ensure neat sealant lines. Primer is generally not required on non-porous surfaces, but may be necessary for optimal sealing of certain porous surfaces. A test placement is always recommended. Apply *Dow Corning* 795 Silicone Building Sealant in a continuous operation using positive pressure. (The sealant can be applied using many types of air-operated guns and most types of bulk dispensing equipment.) Before a skin forms (typically within 15 minutes), tool the sealant with light pressure to spread the sealant against the backing material and joint surfaces. Remove masking tape as soon as the bead is tooled.

HANDLING PRECAUTIONS

PRODUCT SAFETY INFORMATION REQUIRED FOR SAFE USE IS NOT INCLUDED IN THIS DOCUMENT. BEFORE HANDLING, READ PRODUCT AND MATERIAL SAFETY DATA SHEETS AND CONTAINER LABELS FOR SAFE USE, PHYSICAL AND HEALTH HAZARD INFORMATION. THE MATERIAL SAFETY DATA SHEET IS AVAILABLE ON THE DOW CORNING WEBSITE AT DOWCORNING.COM, OR FROM YOUR DOW CORNING SALES APPLICATION ENGINEER, OR DISTRIBUTOR, OR BY CALLING DOW CORNING CUSTOMER SERVICE.

USABLE LIFE AND STORAGE

When stored at or below 27°C (80°F), *Dow Corning* 795 Silicone Building Sealant has a shelf life of 12 months from the date of manufacture. Refer to product packaging for “Use By Date.”

PACKAGING INFORMATION

Dow Corning 795 Silicone Building Sealant is supplied in 10.3-fl oz (305-mL) disposable plastic cartridges that fit ordinary caulking guns, 20-fl oz (590- mL) sausages and 2- and 4.5-gal (7.5- and 1 7-L) bulk containers.

LIMITATIONS

Dow Corning 795 Silicone Building Sealant should not be used:

- In structural applications without prior review and approval by your local Dow Corning Sales Application Engineer
- In below-grade applications
- When surface temperatures exceed 50°C (122°F) during installation
- On surfaces that are continuously immersed in water
- On building materials that bleed oils, plasticizers or solvents that may affect adhesion
- On frost-laden or wet surfaces
- In totally confined joints (the sealant requires atmospheric moisture for cure)
- If the sealant is intended to be painted (paints do not typically adhere to most silicone sealants)
- To surfaces in direct contact with food or other food-grade applications

This product is neither tested nor represented as suitable for medical or pharmaceutical uses.

Dow Corning is a registered trademark of Dow Corning Corporation.
We help you invent the future is a trademark of Dow Corning Corporation.
XIAMETER is a registered trademark of Dow Corning Corporation.
© 2009 Dow Corning Corporation. All rights reserved.

2009, September 3
Ref. No. 61-885N-01

HEALTH AND ENVIRONMENTAL INFORMATION

To support Customers in their product safety needs, Dow Corning has an extensive Product Stewardship organization and a team of Product Safety and Regulatory Compliance (PS&RC) specialists available in each area.

For further information, please see our website, dowcorning.com or consult your local Dow Corning representative.

LIMITED WARRANTY INFORMATION – PLEASE READ CAREFULLY

The information contained herein is offered in good faith and is believed to be accurate. However, because conditions and methods of use of our products are beyond our control, this information should not be used in substitution for customer's tests to ensure that our products are safe, effective, and fully satisfactory for the intended end use. Suggestions of use shall not be taken as inducements to infringe any patent.

Dow Corning's sole warranty is that our products will meet the sales specifications in effect at the time of shipment.

Your exclusive remedy for breach of such warranty is limited to refund of purchase price or replacement of any product shown to be other than as warranted.

DOW CORNING SPECIFICALLY DISCLAIMS ANY OTHER EXPRESS OR IMPLIED WARRANTY OF FITNESS FOR A PARTICULAR PURPOSE OR MERCHANTABILITY.

DOW CORNING DISCLAIMS LIABILITY FOR ANY INCIDENTAL OR CONSEQUENTIAL DAMAGES.

We help you invent the future. ™

dowcorning.com

Dow Corning is a registered trademark of Dow Corning Corporation.
We help you invent the future is a trademark of Dow Corning Corporation.
XIAMETER is a registered trademark of Dow Corning Corporation.
© 2009 Dow Corning Corporation. All rights reserved.

2009, September 3
Ref. No. 61-885N-01

CANNONDESIGN

SUBMITTAL IDENTIFICATION SHEET

To be completed by Contractor/CM

WEBSTER UNIVERSITY ISB
PROJECT NAME

8274 BIG BEND BLVD
ADDRESS

NUMBER

WEBSTER UNIVERSITY
OWNER

CANNON DESIGN
ARCHITECT / ENGINEER

DEVIN D GATES
SUBMITTED BY

076200-007 REV 2
CONTRACTOR / CM SUBMITTAL NO.

CANNON DESIGN SUBMITTAL NO.

DRAWING / DETAIL REFERENCE

076200
SPECIFICATION SECTION / PARAGRAPH

MANUFACTURER / SUPPLIER

ITEM / PRODUCT ID

REQUIRED DATE

PRIORITY

CRITICAL

ITEM BEING SUBMITTED (check only one)

- ○ Shop Drawings
- ○ Samples (_____ copies)
- ○ LEED Submittal
- ○ Certification / Qualifications
- ○ Record Documents
- ◉ Product Data
- ○ Coordination Drawing
- ○ Calculations
- ○ Schedules
- ○ O&M Manuals
- ○ Other _____

ITEM BEING SUBMITTED FOR (check only one)

◉ Action ○ Information Only ○ Record

REMARKS OR DEVIATIONS

CONTRACTOR / CM CERTIFICATION
(SUBMITTALS NOT CERTIFIED WILL BE RETURNED WITHOUT REVIEW)

PARIC

PARIC CORPORATION
SUBMITTAL STAMP

THIS SHOP DRAWING HAS BEEN REVIEWED BY PARIC CORPORATION

Subcontractor remains responsible for dimensions, quantities, coordination with other trades and compliance with contract documents.

By:
Devin D. Gates

DEVIN D GATES
REVIEWED BY

12/27/16
DATE

To be completed by Reviewer

07 6200-007 REV003
CANNON DESIGN SUBMITTAL NUMBER

12/28/16
RECEIVED DATE

- ◉ A. No Exceptions Taken
  No further review of submittal is required.
- ○ B. Make Corrections Noted
  Incorporate corrections in work; resubmission is not required.
- ○ C. Revise and Resubmit
  Revise as noted, and resubmit for review.
- ○ D. Rejected
  Submittal is not in compliance with Contract Documents; provide new submittal.
- ○ E. For Record / Information Only
  Submittal was reviewed for Record / Information purposes only.
- ○ F. Not Required for Review
  Submittal is not required by Contract Documents and has not been reviewed.

Review is for conformance with the design concept of this project and for general compliance with contract documents. Contractor is responsible for quantities, dimensions and compliance with contract documents and for information that pertains to fabrication processes, construction techniques and coordination of this work with all trades which will be affected thereby. This review is null and void if submittal deviates from contract documents and does not indicate or note deviations.

A/E COMMENTS ○ See attached sheet(s) for additional comments

Kathy Williams
REVIEWED BY

01-03-17
DATE

SINCE 1946
VOGEL
SHEET METAL and HEATING, INC.

1642 MANUFACTURERS DRIVE
FENTON, MO 63026
PHONE: (314) 351-2533
FAX: (314) 351-3253

LETTER OF TRANSMITTAL

	Date: December 27, 2016 Job No. A31750
TO: Paric Corporation	Attention: Devin Gates
77 Westport Plaza Dr. Ste.250	Re: Webster Interdisciplinary Science Building
St.Louis, Mo 63146	

WE ARE SENDING YOU:

☒Attached ☐Under separate cover via_____ the following:

☒Shop drawings ☐Prints ☐Plans ☐Samples ☐Specifications

☐Copy of letter ☐Change order ☐other:

COPIES	DATE	NO.	DESCRIPTION
1	12/27/16	1	072600 - 26Ga Stainless steel flashing, roof plan showing application, Dow Corning 795 sealant

THESE ARE TRANSMITTED as checked below:

☒For approval
☐For your use
☐As Requested
☐For review and comment
☐Approved as submitted
☐Approved as noted
☐Returned for corrections
☐For Bids Due on _____
☒Resubmit
☐Submit
☐Return
☐Prints Returned after loan to us
☐Copies for approval
☐Copies for distribution
☐Corrected prints

REMARKS: _____

Copy To:

Signature:Rick Sowa, Architectural Specialist

If enclosures are not as noted, kindly notify us at once.