




ND Series

Continuous improvements make the ND Series a simpler, smarter, stronger lock.

The ND Series has long been one of Schlage's best selling mechanical locks for good reason - it's tough, durable, Grade 1 rated and fits a wide variety of applications. Now we've made our trusted ND Series lock even better by making it easier to install. We've added these enhancements because we know that a lock installed correctly the first time will last longer and perform better. And the longer the lock lasts, the lower the cost of ownership over the life of the lock. We've also beefed up our warranty to provide 10 years of coverage. The result: greater peace of mind that every door is safe and secured with a lock built to last.

So not only do you get our toughest Grade 1 cylindrical lock, that is ideal for use in schools, hospitals, offices, retail spaces, colleges, universities and other applications. You also get the promise of continuous improvements and innovations and our greatest warranty backing your project.



Pictured here: Sparta lever shown in 626 satin chrome

We don't compromise on security

The safety and security of your clients' buildings is something we take very seriously. That's why every Schlage lock and deadbolt undergoes intensive testing to determine its ANSI grade level:

- Cycle tests
- Resistance tests
- Door impact tests
- Warped door tests
- Bolt strength tests

We pay attention to these details so you can focus on creating a functional and aesthetically pleasing environment for your clients. In fact, every one of our ND Series locks meets ANSI Grade 1 standards for safety.

Schlage • ND Series • 7

Interdisciplinary Science Building
Webster University

ND Series

The Schlage ND Series is the toughest cylindrical lock we make. That means you get premium durability and performance in a lock that's also easy to service and maintain. And because we test our locks beyond the standards required by ANSI, you know that you're getting a product you can count on to withstand the use and abuse that come with heavy duty commercial applications.

Pictured here: Athens lever shown
in 626 Satin Chrome




8 • Schlage • ND Series

Interdisciplinary Science Building
Webster University

Built to perform without fail

- Tested to three times the ANSI Grade 1 requirement
- Exceeds ANSI A156.2, Series 4000 Grade 1 locked lever torque requirements
- 10-year limited warranty



ND Series with Vandlgard

The ND Series Vandlgard is ideal for areas subject to abuse or anywhere vandalism is likely to be present, such as schools, universities, offices and commercial/public buildings. Vandlgard prevents damage to internal lock components caused by excessive force from hitting or standing on the lever to gain access. Vandlgard functions maintain total key system and architectural design compatibility with Schlage's regular ND Series cylindrical locks.




Locked lever freely rotates up and down while remaining securely locked. The Vandlgard function also increases resistance to over-rotation of the lever.

Schlage • ND Series • 9

Interdisciplinary Science Building
Webster University

Lever designs

Athens (ATH)



Material: Pressure cast zinc lever; wrought brass rose




Sparta (SPA)



Material: Pressure cast zinc lever; wrought brass rose



Rhodes (RHO)



Material: Pressure cast zinc lever; wrought brass rose




Tubular (TLR)



Material: Pressure cast zinc lever; wrought brass rose



Omega (OME)




Material: Pressure cast zinc lever; wrought brass rose




Tactile warning

Milled



Order as follows:
8AT for Athens
8RO for Rhodes
8SP for Sparta

Knurled



Order as follows:
8TR for Tubular


Only available on outside lever, unless otherwise specified

All designs shown in 626 satin chrome

- = Standard cylinder.
- = FSIC - Full size interchangeable core option.
- = SFIC - Small format interchangeable core option.
- = Complies with ADA accessibility guidelines.

- = Antimicrobial coating available on 626 finish only.
- = Meets California code for 1/2" or less return to the door.
- = Extended factory lead time.


Lever finishes

								
	605 Bright brass	606 Satin brass	612 Satin bronze	613 Oil rubbed bronze	619 Satin nickel	625 Bright chromium plated	626 Satin chromium plated	643e Aged bronze
ND Series locks								
Athens	•	•	•	•	•	•	•	•
Omega	•	•	•	•	•	•	•	•
Rhodes	•	•	•	•	•	•	•	•
Sparta	•	•	•	•	•	•	•	•
Tubular	•	•	•	•	•	•	•	•

e = an equivalent finish to the BHMA standard.

Door handing

All ND levers are reversible. Hand information is necessary to ensure proper cylinder orientation in keyed functions, and finish of latchbolt and strike for locks that are to be installed on reverse bevel doors. Follow the diagram to correctly determine the hand of the door.



ADA-compliant products



In compliance with the American National Standards Institute (ANSI A117.1) and the Americans with Disabilities Act (ADA), Schlage Lock Company offers a wide selection of locks designed for the needs of the physically challenged. This act is designed to provide protection for people with disabilities.

The intent of ADA is that owners of certain types of buildings must remove barriers and provide people with disabilities with access equal to, or similar to, that available to the general public.


Product information and specifications contained in this catalog are subject to change without notice. Please consult the factory.

Schlage • ND Series • 11

Interdisciplinary Science Building
Webster University


Lock functions

ANSI A156.2 Series 4000 Grade 1




Non-keyed locks

Schlage ANSI
ND10S **F75**
Passage latch
• Both levers always unlocked.



Available with RX feature

Schlage ANSI
ND12D **F89**
Exit lock
• Outside lever always fixed.
• Inside lever always unlocked.



Available with RX feature


Schlage ANSI
ND12DEL -
Electrically locked (fail safe)
• Outside lever continuously locked electrically.
• Unlocked by switch or power failure.
• Auxiliary latch deadlocks latchbolt when door is closed.
• Inside lever always free for immediate exit.



Schlage ANSI
ND12DEU -
Electrically unlocked (fail secure)
• Outside lever continuously locked until unlocked by electric current.
• Auxiliary latch deadlocks latchbolt when door is closed.
• Inside lever is always free for immediate exit.



Schlage ANSI
ND25D -
Exit lock
• Blank plate outside.
• Inside lever always unlocked.



 Standard cylinder.	 FSIC - full size interchangeable core option.
 Safe school locks.	 SFIC - small format interchangeable core option.

†Caution:

Double cylinder locks are a life safety hazard in times of emergency and their use is not recommended. Installation should be in accordance with existing codes only.

Keyed locks

Schlage ANSI ND40S F76 Bath/bedroom privacy lock • Push-button locking. • Can be opened from outside with a small screwdriver. • Turn inside lever or close door to release button. Outside Inside 	Schlage ANSI ND44S - Hospital privacy lock • Push-button locking. • Unlocked from outside by turning emergency turn-button. • Turn inside lever or close door to release button. Outside Inside 	Schlage ANSI ND170 - Single dummy trim • Dummy trim for one side of door. • Used for door pull or as matching inactive trim. Outside/Inside 	Schlage ANSI ND50PD F82 Entrance/office lock • Push-button locking. • Push-button locks outside lever until it is unlocked with key or by turning inside lever. Outside Inside 
Schlage ANSI ND53PD F109 Entrance lock • Turn/push-button locking: Pushing and turning the button locks the outside lever, requiring use of a key until the button is manually unlocked. • Push-button locking: Pushing button locks outside lever until unlocked by key or by turning the inside lever. Outside Inside 	Schlage ANSI ND60PD F88 Vestibule lock • Latch retracted by key from outside when outside lever is locked by key in inside lever. • Inside lever always unlocked for immediate egress. Outside Inside 	Schlage ANSI ND66PD F91 Store lock† • Key in either lever locks or unlocks both levers. Outside Inside 	Schlage ANSI ND70PD F84 Classroom lock • Outside lever locked and unlocked by key. • Inside lever always unlocked. Outside Inside 

Schlage • ND Series • 13

Lock functions


ANSI A156.2 Series 4000 Grade 1

Keyed locks (continued)

Schlage ANSI
ND73PD F90

Corridor lock


- Locked or unlocked by key from outside.
- Push-button locking from inside.
- Turn inside lever or close door to release button.
- When outside lever is locked by key it can only be unlocked by key.
- Inside lever is always unlocked.



Schlage ANSI
ND75PD -

Classroom security lock


- Key in either lever locks or unlocks outside lever.
- Inside lever is always unlocked.



Schlage ANSI
ND80PD F86

Storeroom lock

- Outside lever is fixed.
- Entrance by key only.
- Inside lever always unlocked.




Available with RX feature



Schlage ANSI
ND80PDEL -

Electrically locked (fail safe)


- Outside lever continuously locked electrically.
- Unlocked by key outside or by switch or power failure.
- Auxiliary latch deadlocks latchbolt when door is closed.
- Inside lever always free for immediate exit.



Schlage ANSI
ND80PDEU -

Electrically unlocked (fail secure)

- Outside lever continuously locked until unlocked by key or electric current.
- Auxiliary latch deadlocks latchbolt when door is closed.
- Inside lever always free for immediate exit.




14 • Schlage • ND Series

Schlage ANSI
ND82PD F87

Institution lock†


- Both levers are fixed.
- Entrance by key in either lever.



Schlage ANSI
ND85PD -

Faculty restroom lock


- Outside lever is fixed.
- Entrance by key only.
- Push-button in inside lever activates visual occupancy indicator, allowing only emergency master key to operate.
- Turn inside lever or close door to release visual occupancy indicator.
- Rotation of inside spinner-button provides lock-out feature by keeping indicator thrown.



Schlage ANSI
ND91PD F82

Entrance/office lock

- Push-button locking.
- Push-button disengages outside lever until locked with key or by turning inside lever.
- Vandlgard is designed to disengage outside spindle from latch when locked.



Interdisciplinary Science Building
Webster University

Cylinders and key systems

Protect new key systems with Everest 29

Schlage can help you design a system that can grow and change along with your needs, allowing you the flexibility to upgrade your security without the need to replace all your cylinders.


What it operates	What it is
• Everest 29 Primus® XP cylinders • Everest 29 restricted cylinders • Everest 29 open cylinders	UL 437 version • UL 437 versions provide drill and pick resistance and withstand physical attack • High security cylinders have a second set of pins for added security • Patented key control sold with various levels of geographic exclusivity • Keys operate high security, as well as restricted security or standard security cylinders • Available only in conventional
• Everest 29 Primus XP cylinders • Everest 29 restricted cylinders • Everest 29 open cylinders	Controlled access • Patented key control sold with various levels of geographic exclusivity • High security cylinders have a second set of pins for added security and pick resistance • Keys operate high security, as well as restricted security or standard security cylinders • Available only in conventional and FSIC
• Everest 29 restricted cylinders	• Key distribution is restricted duplication must be authorized • End user's ID numbers are stamped on all keys, enabling Schlage to identify the source of any unauthorized keys • Patent-protected keys are drop-shipped from the factory directly to an end-user specified location to guarantee exclusivity • Available in conventional, SFIC and FSIC
• Everest 29 open cylinders	• Patented key blanks can be stored by commercial locksmiths and security dealers • Keys can be duplicated without any paperwork or signature verification • Sold only through commercial outlets • Available in conventional and FSIC

Upgrade existing classic key systems with Primus XP

Schlage offers key system solutions that are ideal for upgrading an existing key system to control key management. Our patent-protected cylinders help prevent unauthorized duplication and can be integrated into virtually any existing system.

What it is	What it operates
UL 437 version • UL 437 versions provide drill and pick resistance and withstand physical attack • High security cylinders have a second set of pins for added security • Patented key control sold with various levels of geographic exclusivity • Keys operate high security, as well as restricted security or standard security cylinders • Available only in conventional	• Primus XP cylinders • Classic cylinders
Controlled access • Patented key control sold with various levels of geographic exclusivity • High security cylinders have a second set of pins for added security and pick resistance • Keys operate high security, as well as restricted security or standard security cylinders • Available only in conventional	• Primus XP cylinders • Classic cylinders
• Keys can be duplicated at most retail and commercial points of sale with no restrictions • Recommended only for residential applications or existing commercial systems that cannot rekey • Can be upgraded to Primus XP without rekeying the entire facility • Available in conventional and FSIC	• Classic cylinders

Compatible key systems



Schlage key systems	Key-in-lever cylinder	Full size interchangeable core	Small format interchangeable core
Primus XP	X	X	
Everest 29	X	X	X
Classic	X	X	
Other key systems (6 Pin FSIC)			
Sargent	X	X	X
Corbin Russwin		X	X
Yale		X	X

Cylinder options (how to order)

Cylinder	Order suffix	Description
	LD SAR	Sargent Key-in-lever
	JD SAR	Sargent Full size interchangeable core 6-pin cylinder
	JD C06	Corbin Russwin Full size interchangeable core 6-pin cylinder
	JD YA6	Yale Full size interchangeable core 6-pin cylinder

Schlage • ND Series • 17

Interdisciplinary Science Building
Webster University

Standard cylinders

Standard cylinders are available in Classic keyways or in patented Everest 29 keyways. Specify keyway to differentiate between Everest 29 and Classic.

Example: C or CP (Classic) vs. S123 (Everest 29).



Standard cylinders - options

- 6-pin conventional (standard)
- Primus XP high security
- Primus XP UL437 Listed high security
- Hotel cylinder
- Temporary construction plug, plastic for functions

Available in 606 and 626 finish only.
Everest 29 S123 keyway standard.

Full size interchangeable core 8

Schlage FSIC full size interchangeable core (IC) locksets allow immediate rekeying at the door simply by using a special control key to replace the core.



Available in all lever designs, full size interchangeable cores can be integrated into any 5 or 6-pin Schlage key.

Full size interchangeable cores - options

- Conventional core
- Primus XP high security core
- FSIC driver

Available in 606 and 626 finish only.
Everest 29 S123 keyway standard.

Primus XP access control and high security cylinders

Classic Primus XP cylinders are recommended for upgrading existing Classic key systems. Due to its extended patent life, the newly designed Everest 29 Primus XP is recommended for new key systems and for upgrading existing Everest 29 key systems. Specify keyway to differentiate between Everest 29 and Classic.

Example: C or CP (Classic) vs. S123 (Everest 29).


Latches

ND Series latches are adjustable for flat or beveled edge doors. Latches and strikes are furnished in brass, bronze, or chrome finishes to be compatible with lock trim. When ordering, specify quantity, part number, and finish. All ND Series latches have 1/2" throw and 1" housings except 2 3/8" backset latches, which includes sleeve G506-815 to fill a 1" edge bore. Standard latches are shown in bold type.


Latches - options

Backset	Description	Deadlatch 1/2" (13 mm) throw	Springlatch 1/2" (13 mm) throw
2 3/8" (60 mm)	1 1/8" (29 mm) x 2 1/4" (57 mm) square corner	3	—
	1 1/8" (29 mm) x 2 1/4" (57 mm) square corner	3	—
2 3/4" (70 mm)	1 1/8" (29 mm) x 2 1/4" (57 mm), standard square corner	3	3
	1 1/8" (29 mm) x 2 1/4" (57 mm) throw, anti-friction door latch, square corner	3	—
3 3/4" (95 mm)	1 1/8" (29 mm) x 2 1/4" (57 mm), square corner	3	3
5"	Backset extension link	3	—



Deadlatch



Springlatch




3/4" Throw anti-friction deadlatch for pairs of fire doors



G506-815

Long backsets

ND Series locks with 5" backsets are normally furnished with 1 1/8" faceplates and 1" housings. Links installed in metal doors require one A501-567 sleeve and 43-005 (order separately) to join latch and link.




Door reinforcement

Reinforcing unit is required to reinforce and help prevent the collapse of hollow metal doors when locksets are tightly mounted. This kit should be used with long backsets for ND Series lock installations in hollow metal doors to prevent lateral movement of the latchbolt. Specify door thickness, 1 3/8" (35 mm) or 1 3/4" (44 mm), when ordering reinforcement kits.

Reinforcement kit 37-001

Kit includes:

Reinforcement
A501-566 for 1 3/4" doors or
A501-565 for 1 3/8" doors



Strikes

All Schlage strikes are furnished complete with screws.


The standard ND Series strike has a $1\frac{3}{16}$ " lip.

When ordering separately specify quantity, product number, finish, and lip length. Standard strikes are shown in bold type.

Strikes - options

- $1\frac{1}{8}$ " x $2\frac{3}{4}$ " (28 mm x 70 mm) square corner, T-strike, box - $1\frac{1}{8}$ " (28 mm) lip length
- $1\frac{1}{8}$ " x $2\frac{3}{4}$ " (28 mm x 70 mm) square corner, T-strike, box - $1\frac{1}{2}$ " (38 mm) lip length
- $1\frac{1}{4}$ " x $4\frac{7}{8}$ " (32 mm x 124 mm) standard, no box, ANSI - $1\frac{3}{16}$ " (30 mm) lip length
- $1\frac{1}{4}$ " x $4\frac{7}{8}$ " (32 mm x 124 mm) ANSI, no box - $1\frac{3}{8}$ " (35 mm) lip length
- Box for 10-025 ANSI strike

ANSI strike—standard
(10-025)
 $1\frac{1}{4}$ " x $4\frac{7}{8}$ " x $\frac{3}{32}$ "



Square corner box strike
(10-013)
 $1\frac{1}{8}$ " x $2\frac{3}{4}$ " x $\frac{3}{32}$ "




Rabbeted latch and strike kit

Rabbeted latch and strike kit finishes: 605, 626.

This kit adapts square corner latches and $2\frac{3}{4}$ " (28 mm) high strikes for $\frac{1}{2}$ " (13 mm) rabbeted door and frame preparations.

Rabbeted latch and strike kit
(39-030)



Accessories

$1\frac{3}{8}$ " D Series lever door spacer*



XN12-012

*For installation on $1\frac{3}{8}$ " doors, two (2) spacers are required. Specify finish.

Specifications

Handing:

All ND Series lever locksets are non-handed.

Door thickness:

1⁵/₈" to 2¹/₈" (41 mm–54 mm) standard including Vandlgard® functions. 1³/₄" - 2" for function D85. See accessories (Page 21) for spacers required for 1³/₈" doors.

Backset:

2³/₄" (70 mm) standard. 2³/₈", 3³/₄" and 5" (60 mm, 95 mm, 127 mm) optional.

Faceplate:

Brass, bronze or stainless steel. 1¹/₈" x 2¹/₄" (29 mm x 57 mm) square corner, beveled.

Lock chassis:

Zinc plated for corrosion resistance.

Latch bolt:

Steel, 1/2" (12 mm) throw, deadlocking on keyed and exterior functions. 3/4" (19 mm) throw anti-friction latch available for pairs of fire doors.

Exposed trim:

Levers: Pressure cast zinc, plated to match finish symbols.
Roses: Brass, bronze or zinc.

Strike:

ANSI curved lip strike 1¹/₄" x 4⁷/₈" x 1³/₁₆" lip to center standard. Optional strikes, lip lengths and ANSI strike box available. See page 21.

Cylinder and keys:

6-pin Everest 29 S123 keyway standard with two patented nickel silver keys per lock.

Keying options:

Interchangeable core and Primus high security cylinders.
Master keying, grand master keying and construction keying.

Warranty:

Ten-year limited for all mechanical functions including Vandlgard; 1 year limited for electrified functions.

Certifications

ANSI:

Meets the requirements of ICC A117.1 Accessible and Usable Buildings and Facilities.

Federal:

Meets FF-H-106C Series 161.

California Referenced Standards Code:

(Formerly Title 19, California State Fire Marshal Standard)
All levers with a return to door of 1/2" (64 mm) or less comply. Most Schlage levers comply (see lever designs section for compliance).

MEA certification:

All electrified locking (fail-safe, unlocked by switch or power failures) functions accepted for use in New York City by the City of New York, Department of Buildings (MEA 24-04-E).

All levers with less than 1/2" (64 mm) returns comply with California Fire Safety Codes.

Florida Building Commission:

3/4" and 1/2" throw latch approved for Hurricane Resistance with Miami-Dade County, Florida.

UL / cUL:


All locks listed for A label single doors, 4' x 8'.
Letter F and UL symbol.

ADA compliant:

Schlage Lock Company offers a wide selection of locks designed to meet the Americans with Disabilities Act.

Cores

Full size interchangeable core cylinders for exit devices, aluminum door, etc.



Interchangeable core rim cylinders for exit devices

Number	Core mechanism
20-057	Conventional core
20-757	Primus core
20-757-XP	Primus XP core
20-079	Housing only, less core

Available in 605, 606, 609, 612, 613, 619, 625, 626, and 643e finish.



Cylinders for Adams Rite MS and 4700 Series
Lori 4500 Series and Corbin Russwin DL3000 Series

Number	Core mechanism	Collar
26-098	Conventional core	Compression ring & spring
20-062	Conventional core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-766	Primus core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-766-XP	Primus XP core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-060	Housing less core	None

These cylinders include set screw pack B220-050 for Adams Rite locks.



K510-711
Adams Rite
MS cam

Cylinders for Adams Rite 4070 Series deadlocks

Number	Core mechanism	Collar
20-091	Conventional core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-722	Primus core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-722-XP	Primus XP core	$\frac{3}{16}$ " + $\frac{3}{8}$ " blocking rings
20-090	Housing less core	None



B520-378
Adams Rite
4070 cam

- Notes
1. Mortise cylinders available 605, 606, 609, 612, 613, 619, 625, 626, and 643e finish. Cores furnished 606 and 626 only.
 2. To differentiate between Classic and Everest 29, specify keyway. Example: C or CP (Classic), S123 (Everest 29).
 3. All cylinders are $1\frac{1}{2}$ " long.
 4. Specify LKB if 0-bitted Primus XP cylinders are required less key blanks.



Allegion, PLC
6810 Hillsdale Ct.
Indianapolis, IN 46250 USA
Office 877.238.2022 Fax 317.715.4055
allegion.com

Submittal Review

Specification Section: 087100 Door Hardware

Date: 11/10/2016

Project: Webster University - ISB
Webster, MO

Firm: Cannon Design
Attn: Kelvin Patel
1100 Clark Ave
St. Louis, MO 63102
(314) 425-8756

Kelvin,

I have reviewed this submittal for the door hardware per specification section 087100. This review is for specification compliance based on the specifications submitted to you for the above referenced project. I did not review for doors and frames and nor did I respond to any questions or comments regarding doors and frames. The Contractor remains responsible for the accuracy and completeness of submittal including, but not limited to, dimensions, quantities, fabrication, and construction techniques. General Conditions of contract documents apply.

You will need to review the door and frame submittal for compliance based on your plans, door schedule, and door/frame elevations. If any changes were made through addenda or RFI please update my comments appropriately.

Submittal Action:

Door Hardware Submittal dated 10/31/16 -

Reviewed / Reviewed As Noted

Submittal Notes/Comments:

- Revise all closers to 4010/4110 DEL series per email revision
- Provide Exit Devices with NL-OP trim where specified versus the submitted NL trim

Door Hardware Submittal—

Note: The general comments are listed to save time for repetitious items, comments, and/or concerns. The specific comments listed for individual headings are subject to the general comments listed below.

1. General:
 - a. I did not review submittal for handing.
 - b. Operational Description: Operational Description, of openings with electrified hardware, needs to be included in the door hardware schedule. [Reference Section 087100, Article 1.3.C.3.]

Please remind the contractor to coordinate the hardware being supplied by the Aluminum Door supplier with the hardware from this package. The hardware for aluminum doors is specified in Section 087100. This submittal references aluminum hardware as “by others”. All the hardware is required to be of the same manufacturer and model and meet the requirements of Section 087100.

- ✓ Single Source Responsibility: Obtain each type of hardware (ie. latch and locksets, hinges, exit devices, closers, etc.) from a single manufacturer. [Reference Section 087100, Article 1.4.D.]

The door hardware specification includes some project controls to assist in a smooth project. Please remind the general contractor of the following specification items in Section 087100:

- ✓ Article 1.3.C.3.I.3. Riser and Wiring Diagram – Please advise hardware supplier to provide riser and (point-to-point) Wiring Diagrams per approved finish hardware schedule.
- ✓ Articles 1.3.D. and 2.6. Keying – Please advise the hardware supplier to schedule and complete the keying conference prior to ordering hardware to avoid issues with keying or lock functions.
- ✓ Articles 1.6. and 1.7. Coordination – Please advise general contractor to schedule pre-installation, installation coordination, and electrified hardware coordination conferences prior to installation of any finish hardware.

Also, put the following items on the check-list at project completion time:

- ✓ Article 3.1 Installation
- ✓ Articles 3.1.L and 3.2 Adjustment and Field Inspections

As a reminder the following services are available to you for this project:

- ✓ Provide product training to installers.
- ✓ Assist you with “Jobsite Inspection” and creation of a detailed punch-list.
- ✓ Provide product training to owner.

Please review and contact us at the above telephone number or via email at aaron.owens@allegion.com with any questions or if you need further assistance. Thank you for your time and allowing me to follow up on this project.

Sincerely,

Aaron Owens

<Aaron Owens>