



VON DUPRIN® 9875/9975 Mortise Lock Device



575 Strike

9875/9975 mortise lock device for all types of single or double doors, UL listed for Panic Exit Hardware. Devices are ANSI A156.3 – 2001 Grade 1. Fits stock hollow metal doors with 86 cutout and door stiles as narrow as 4 3/4" (121mm). The 9875 device has a smooth mechanism case and the 9975 device has a grooved case. The mortise lock device is non-handed except when the following device options are used: -2 (Double Cylinder) or SS (Signal Switch). See Opposite page for available outside trim and device functions.

The 9875/9975 devices are available in the following finishes: US3, US4, US10, US26, US26D, US28, 313AN, 315AN and US32D for the 9875 device only. See page 52 for component finishes and the inside cover for finish chips.



The 7500 Mortise lock is equipped with a 3/4" (19mm) anti-friction latch bolt which is field reversible without removing the lock from the door. It has a non-handed auxiliary bolt for deadlocking and a faceplate with an adjustable bevel.

Specifications

Device Functions	Device ships EO/DT/NL. Field selectable. For TP,K,or L adjust NL drive screw in mortise lock	
Device Lengths	3' 2'4" to 3' (711mm to 914 mm) Door Size	
	4' 2'10" to 4' (864 mm to 1219 mm) Door Size	
Strikes	575 – Dull Black Optional Strikes – see page 39	
Dogging Feature	Hex key dogging standard	
Dogging Options	CD Cylinder Dogging	see page 48
	LD Less Dogging	see page 48
Electric Option	RX Pushpad Monitor Switch	see page 42
	RX2 Double Pushpad Monitor Switch	see page 42
	E Electric Locking & Unlocking	see page 44
	EL Electric Latch Retraction	see page 43
	SS Signal Switch	see page 43
	CX Chexit Delayed Exit	see page 45
Miscellaneous Options	ALK Alarm Exit Kit	see page 42
	PN Pneumatic Latch Retraction	see page 48
	-2 Double Cylinder	see page 48
	GBK Glass Bead Kit	see page 49
Fasteners & Sex Bolts (SNB)	Includes 1 3/4" (19mm) – 2 1/4" (57mm) Wood & Metal Doors Optional SNB available for device, see next page for quantities	
Device Centerline from Finished Floor	39 5/8" (1006 mm)	
Center Case Dimensions	8" x 2 3/4" x 2 3/8" (203mm x 70mm x 60mm)	
Mechanism Case Dimensions	2 1/4" x 2 1/4" (57mm x 57mm)	
Projection	Pushbar Neutral – 3 13/16" (97 mm)	
	Pushbar Depressed – 3 1/16" (78 mm)	

See page 53 for How to Order specification

VON DUPRIN® 9875-F/9975-F Mortise Lock Fire Exit Device



575 Strike

9875-F/9975-F fire exit mortise lock devices for all types of single doors up to 4' x 10' (1219mm x 3048mm) or 8' x 10' (2438mm x 3048mm) double doors installations, UL listed for Fire Exit Hardware; See page 41 for detailed information on UL listed fire exit hardware label and door opening size information. Devices are ANSI A156.3 – 2001 Grade 1. Fits door stiles as narrow as 4 3/4" (121mm). The 9875-F device has a smooth mechanism case and the 9975-F device has a grooved case. The mortise lock device is non-handed except when the following device options are used: -2 (Double Cylinder) or SS (Signal Switch) devices. See Opposite page for available outside trim and functions.

The 9875-F/9975-F devices are available in the following finishes: US3, US4, US10, US26, US26D, US28, 313AN, 315AN and US32D for the 9875-F device only. See page 52 for component finishes and the inside cover for finish chips.

The 7500 Mortise lock is equipped with a 3/4" (19mm) anti-friction latch bolt which is field reversible without removing the lock from the door. It has a non-handed auxiliary bolt for deadlocking and a faceplate with an adjustable bevel.



Specifications

Device Functions	Device ships EO/DT/NL. Field selectable. For TP,K,or L remove NL drive screw from device		
Device Lengths	3'	2'4" to 3' (711mm to 914 mm)	Door Size
	4'	2'10" to 4' (864 mm to 1219 mm)	Door Size
Strikes	575 – Dull Black Optional Strikes – see page 39		
Dogging Feature	No Mechanical Dogging, EL option available		
Electric Options	RX	Pushpad Monitor Switch	see page 42
	RX2	Double Pushpad Monitor Switch	see page 42
	E	Electric Locking & Unlocking	see page 44
	EL	Electric Latch Retraction	see page 43
	SS	Signal Switch	see page 43
	CX	Chexit Delayed Exit	see page 45
	ALK	Alarm Exit Kit	see page 42
Miscellaneous Options	PN	Pneumatic Latch Retraction	see page 48
	-2	Double Cylinder	see page 48
	GBK	Glass Bead Kit	see page 49
Fasteners & Sex Bolts (SNB)	Includes 1 3/4" (19mm) – 2 1/4" (57mm) Wood & Metal Doors Optional SNB available for device, see next page for quantities Optional SLM Blocking Pkg for wood doors with SLM blocking SNB required for wood doors, unless SLM Blocking Pkg. specified		
Device Centerline from Finished Floor	39 5/8" (1006 mm)		
Center Case Dimensions	8" x 2 3/4" x 2 3/8" (203mm x 70mm x 60mm)		
Mechanism Case Dimensions	2 1/4" x 2 1/4" (57mm x 57mm)		
Projection	Pushbar Neutral – 3 1/16" (97 mm) Pushbar Depressed – 3 1/16" (78 mm)		

See page 53 for How to Order specification

VON DUPRIN® 9875-F/9975-F Mortise Lock Fire Exit Device Standard Trim

	Exit only	Dummy Trim Pull when Dogged (Not recommended for Fire Device)	Night Latch Key Retracts Latchbolt	Hospital Latch Key Locks & Unlocks
				
Product Description	9875EO-F 9975EO-F	—	9875NL-F 9975NL-F	9875HL-F 9975HL-F
Trim Description	—	990DT	990NL-R/V	HL6M
Escutcheon Plate Size	—	3" x 14 ³ / ₁₆ " x 3 ³ / ₃₂ " (76x360x2mm)	3" x 14 ³ / ₁₆ " x 3 ³ / ₃₂ " (76x360x2mm)	2 ⁹ / ₁₆ " x 5 ¹ / ₂ " x 2 ⁵ / ₈ " (65x140x67mm)
Pull Center to Center	—	5 ¹ / ₂ " (140mm)	5 ¹ / ₂ " (140mm)	—
Projection	—	2" (51mm)	2" (51mm)	2 ⁵ / ₈ " (67mm)
ANSI Function	01	02	03	—
Cylinder Type	—	—	1 ¹ / ₄ " Mortise	1 ¹ / ₄ " Mortise
Optional Trim (See pages 32 – 34)	x990EO x992EO x994EO x996EO	x991K-DT x992L-DT x994L-DT x996L-DT x696DT x697DT	x991K-NL x992L-NL x994L-NL x996L-NL x696NL x697NL	
#425 SNB optional-HMD Req. WD w/o SLM Pkg.	6	2	2	2


	Lever Key Locks & Unlocks	Lever – Night Latch Key Retracts Latchbolt	Lever – Blank Escutcheon Always operable (No Cylinder)	Lever Dummy Trim Pull when Dogged (Not recommended for Fire Device)
				
Product Description	9875L-F 9975L-F	9875L-NL-F 9975L-NL-F	9875L-BE-F 9975L-BE-F	—
Trim Description	996L-M	996L-NL-M	996L-BE-M	996L-DT-M
Escutcheon Plate Size	2 ³ / ₄ " x 10 ³ / ₄ " x 2 ⁷ / ₃₂ " (70x273x21mm)	2 ³ / ₄ " x 10 ³ / ₄ " x 2 ⁷ / ₃₂ " (70x273x21mm)	2 ³ / ₄ " x 10 ³ / ₄ " x 2 ⁷ / ₃₂ " (70x273x21mm)	2 ³ / ₄ " x 10 ³ / ₄ " x 2 ⁷ / ₃₂ " (70x273x21mm)
Pull Center to Center	—	—	—	—
Projection	2 ⁷ / ₈ " (73mm)	2 ⁷ / ₈ " (73mm)	2 ⁷ / ₈ " (73mm)	2 ⁷ / ₈ " (73mm)
ANSI Function	08	09	—	02
Cylinder Type	1 ¹ / ₄ " Mortise	1 ¹ / ₄ " Mortise	—	—
Optional Trim (See pages 32 – 34)	x992L x994L	x992L-NL x994L-NL	x992L-BE x994L-BE	x992L-DT x994L-DT
#425 SNB optional-HMD Req. WD w/o SLM Pkg.	2	2	2	2

For optional trims and functions see pages 32-34

Knob and Thumbpiece Trim

	Knob Key Locks & Unlocks	Knob – Night Latch Key Retracts Latchbolt	Knob – Blank Escutcheon Always Operable (No Cylinder)	Knob – Dummy Trim Pull when Dogged	Thumbpiece Key Locks & Unlocks	Thumbpiece Blank Escutcheon Always Operable (No Cylinder)
Trim Description	991K	991K-NL	991K-BE	991K-DT	990TP	990TP-BE
Escutcheon Plate Size	2¾" x 10¾" x 27/32" (70x273x21mm)	2¾" x 10¾" x 27/32" (70x273x21mm)	2¾" x 10¾" x 27/32" (70x273x21mm)	2¾" x 10¾" x 27/32" (70x273x21mm)	2¾" x 10¾" x 27/32" (70x273x21mm)	2¾" x 10¾" x 27/32" (70x273x21mm)
Pull Center to Center	—	—	—	—	5½" (140mm)	5½" (140mm)
Projection	3¼" (83mm)	3¼" (83mm)	3¼" (83mm)	3¼" (83mm)	2" (51mm)	2" (51mm)
ANSI Function	08	09	—	02	05	05
Cylinder Type	Rim	Rim	—	—	Rim	—
Rim or Vertical Rod Device						
Mortise Lock Device	1¼" Mortise	1¼" Mortise	—	—	1¼" Mortise	—
#425 SNB optional-HMD Req. WD w/o SLM Pkg.	2	2	2	2	2	2
#825 SNB Req. WD w/o SLM Pkg. F Rim device ONLY	2	2	2	2	2	2
#425 SNB Req. w/ 499F	2	2	2	2	2	2

Lever Design Options



Operation Options


Lever and Knob Operations




Standard operation, key locks and unlocks lever or knob. e.g., 996L (Classroom)



Night latch, key retracts latch bolt. Lever or knob is rigid. Use NL suffix, e.g., 996LNL. (Storeroom)



Blank escutcheon, lever or knob always active. Use BE suffix, e.g., 996L-BE. (Passage)



Dummy trim, lever or knob rigid for pull operation. Use DT suffix, e.g., 996L-DT.

374T/376T Series Thumbturn Control (Shown with 990DT Trim)



Standard operation, key locks and unlocks thumbturn. Optional operation, key unlocks thumbturn, re-locks when key is removed. This operation is created by changing the cylinder plate included with control. Use 1 1/4" mortise cylinder with a straight cam. Schlage cam reference B502-191.

HL6 Exit Device Trim Option




Von Duprin and Glynn-Johnson have collaborated on an exit device trim that answers the problem of accessibility and performance. Using the Von Duprin 98/9975 mortise lock exit device along with the Glynn-Johnson HL6 Push/Pull latch, Ingersoll-Rand has created an exit device with mortise lock durability that utilizes a fully ADA compliant Pull paddle trim. The 98/9975HL device is available in all standard architectural finished and can be found in the Von Duprin device price list for easy ordering.

Vandal Resistant Trim

VR910 & VR914 Series

Features:

- Stainless Steel construction, 11 gage (0.120" thick)
- Thru-bolts and rugged mounting screws for maximum fastening strength.
- 10-24 screws supplied with VR910 & VR914 models.
- Built-in lock protector prevents vandalism to mortise latchbolt (available on certain models).
- Extra-tough stainless steel cylinder collar prevents pipe wrench or similar tool from damaging cylinder. Tapered design prevents side impacts from transferring directly to cylinder. Collar spins freely.
- Furnished with mounting screws for door thicknesses of 1 3/4" to 2 1/4"
- Finish: US32D
- VR910 grip coated in black plastisol for softer touch and resilience to temperature extremes. Grip designed for comfortable operation.
- VR914 grip in all stainless steel.
- Meets ANSI/BHMA 156.13, Trim Security Test and California State Accessibility Standards Title 24.
- 1 1/2" (38mm) clearance from grip to door
- 1 7/8" (48mm) total projection from door
- Consult IVES catalog for specification/ordering information.



Model	For Use With	Size
VR910DT & VR914DT	98/99 Rim or Vert. Rod Device	5 1/4" (133mm) w x 11" (279mm)h
VR910NL & VR914NL	98/99 Rim or Vert. Rod Device	5 1/4" (133mm) w x 11" (279mm)h
VR910M-DT & VR914M-DT	9875/9975 Mortise Device	7 1/4" (184mm) w x 11" (279mm)h
VR910M-NL & VR914M-NL	9875/9975 Mortise Device	7 1/4" (184mm) w x 11" (279mm)h

Hardware

Manufacturer's

Accurate Lock, Doug Mockett, Glynn Johnson,
Ives, LCN, Brio, Schlage, Von Duprin, Zero

Hardware Finish

32D Satin Stainless Steel, 26D Satin Chrome,
Aluminum



PARIC
EXPERIENCE. EXCELLENCE.

77 Westport Plaza
Suite 250
St. Louis, MO 63146

TRANSMITTAL

No. 15051-0222

Paric Corporation

PROJECT: 15051-Webster University Interdisciplinary Science Building

DATE: 09/12/2016

TO: Cannon Design
1100 Clark Ave
St Louis MO 63102

RE: Hardware Product Data

ATTN: Kelvin Patel

JOB: 15051

WE ARE SENDING:		SUBMITTED FOR:	ACTION TAKEN:
☐ Shop Drawings		☒ Approval	☐ Approved as Submitted
☐ Letter		☐ Your Use	☐ Approved as Noted
☐ Prints		☐ As Requested	☐ Returned After Loan
☐ Change Order		☐ Review and Comment	☐ Resubmit
☐ Plans			☐ Submit
☐ Samples		SENT VIA:	☐ Returned
☐ Specifications		☐ Attached	☐ Returned for Corrections
☒ Other: Product Data		☐ Separate Cover Via:	☐ Due Date:

<u>Item</u>	<u>Package</u>	<u>Code</u>	<u>Rev.</u>	<u>Copies</u>	<u>Date</u>	<u>Description</u>	<u>Status</u>
Submittal		087100.03-002	1		09/12/2016	Hardware Product Data	Submitted

NOTES:

CC:

Signed: _____
Devin Gates