



POWDER COAT COLOR CHART

GORDON
INCORPORATED


STANDARD FINISHES


REGAL WHITE


PDR-20100
GLOSS 5 +/-5
LIGHT REFLECTANCE 75


CLEANROOM WHITE


PDR-20101
GLOSS 45 +/-5
LIGHT REFLECTANCE 83


PARCHMENT WHITE

PDR-20108
GLOSS 20 +/-5
LIGHT REFLECTANCE 70


SECURITY WHITE

PDR-20127
GLOSS 50 +/-5
LIGHT REFLECTANCE 78


BARONET BEIGE

PDR-20900
GLOSS 5 +/-5
LIGHT REFLECTANCE 48


DARK BRONZE

PDR-20205
GLOSS 15 +/- 5
LIGHT REFLECTANCE 9



GRAPHITE BLACK

PDR-20400
GLOSS 20 +/-5
LIGHT REFLECTANCE 8



BLACK JACK

PDR-20407
GLOSS 40 +/-5
LIGHT REFLECTANCE 5

PREMIUM FINISHES


DRIFTWOOD GRAY

PDR-20700
GLOSS 5 +/-5
LIGHT REFLECTANCE 36


ANODIZED ALUMINUM

PDR-20803
GLOSS 10 +/-5
LIGHT REFLECTANCE 36


ASTI II

PDR-20811
GLOSS 10 +/-5
LIGHT REFLECTANCE 27


COPPERPLATE

PDR-21408
GLOSS 15 +/- 5
LIGHT REFLECTANCE 15

Gordon stocks all finishes featured. Gordon has virtually unlimited custom color matching capabilities. Antimicrobial finishes are also available.

Finish samples shown on this card are digital replications of the actual paint finishes and may vary slightly in color. Color samples, supplied on an aluminum panel, provide an actual representation of color, gloss, texture, and hue and are available upon request.

Gloss levels are expressed from measurement on a 60° gloss meter.

5023 HAZEL JONES ROAD, BOSSIER CITY, LA 71111

POWDER COAT

TECHNICAL INFORMATION



Our durable powder coat finishes are offered in acrylics, polyesters, hybrids, and epoxies. Gordon powder coat finishes are environmentally friendly, solvent-free, and nonflammable. No volatile organic compounds (VOCs) are emitted into the atmosphere during or after application.

TECHNICAL DATA

GLOSS	5 - 85+	ASTM D523	MANDREL BEND	1/8"	ASTM D522
COLOR RANGE	Wide		ADHESION	5b	ASTM D3359
TEXTURE	Limited		MACHINE ABILITY	Pass	Drill 1/4" hole
IMPACT RESISTANCE	160 / 160	ASTM D2794	QUV-B 313	200 hours	ASTM D4587
SMOOTHNESS	8 - 10	Ford Scale	SALT SPRAY RESISTANCE	1000 hours	ASTM B117
PENCIL HARDNESS	2H	ASTM D3363	HUMIDITY RESISTANCE	1500 hours	ASTM 2247
TABER ABRASION	80	ASTM D4060			

All testing utilized a .063" aluminum substrate and a film thickness of 1.9 - 2.0 mils.

ENVIRONMENTAL POLICY

Our in-house finishing facility uses only water-soluble materials in our pre-treatment process. All overflow from this process is approved for introduction into our city water treatment plant without adverse impact to the environment. Gordon powder coat finishes are EPA compliant and contribute to the U.S. Green Building initiative.

Gordon's environmental commitment is affirmed within our core *Values, Beliefs, and Principles*. Waste reduction and recycling are key elements of our business culture and are embraced by all Gordon team members.



5023 HAZEL JONES ROAD, BOSSIER CITY, LA 71111
800.747.8954
800.877.8746 FAX
SALES@GORDON-INC.COM
GORDON-INC.COM
AN EMPLOYEE OWNED COMPANY



SUBMITTAL IDENTIFICATION SHEET

To be completed by Contractor/CM

WEBSTER UNIVERSITY ISB	
PROJECT NAME	
8274 BIG BEND BLVD	
ADDRESS	
NUMBER	
WEBSTER UNIVERSITY	
OWNER	
CANNON DESIGN	
ARCHITECT / ENGINEER	
DEVIN D GATES	
SUBMITTED BY	
092900-012	
CONTRACTOR / CM SUBMITTAL NO.	CANNON DESIGN SUBMITTAL NO.
	092900
DRAWING / DETAIL REFERENCE	SPECIFICATION SECTION / PARAGRAPH
MANUFACTURER / SUPPLIER	ITEM / PRODUCT ID
REQUIRED DATE	PRIORITY
	CRITICAL

ITEM BEING SUBMITTED (check only one)

- | | | |
|--------------------------------------|--|--|
| ☐ Shop Drawings | ☐ Certification / | ☐ Coordination Drawing |
| ☐ Samples | ☐ Qualifications | ☐ Calculations |
| ☐ (____ copies) | ☐ Record Documents | ☐ Schedules |
| ☐ LEED Submittal | ☐ Product Data | ☐ O&M Manuals |
| ☐ Other _____ | | |

ITEM BEING SUBMITTED FOR (check only one)

- ☒ Action ☐ Information Only ☐ Record

REMARKS OR DEVIATIONS

Extruded aluminum trim product data and schedule.
mullion mate
gordon 911
gordon 911-EC 200
gordon 234
gordon 314 - 5/8

CONTRACTOR / CM CERTIFICATION (SUBMITTALS NOT CERTIFIED WILL BE RETURNED WITHOUT REVIEW)



PARIC CORPORATION
SUBMITTAL STAMP

THIS SHOP DRAWING HAS BEEN REVIEWED BY PARIC CORPORATION

Subcontractor remains responsible for dimensions, quantities, coordination with other trades and compliance with contract documents.

By:

Devin D. Gates

DEVIN D GATES	02/07/17
REVIEWED BY	DATE

To be completed by Reviewer

09 2900-012
CANNON DESIGN SUBMITTAL NUMBER
2/27/17
RECEIVED DATE

- ☐ A. No Exceptions Taken
No further review of submittal is required.
- ☒ B. Make Corrections Noted
Incorporate corrections in work; resubmission is not required.
- ☐ C. Revise and Resubmit
Revise as noted, and resubmit for review.
- ☐ D. Rejected
Submittal is not in compliance with Contract Documents; provide new submittal.
- ☐ E. For Record / Information Only
Submittal was reviewed for Record / Information purposes only.
- ☐ F. Not Required for Review
Submittal is not required by Contract Documents and has not been reviewed.

Review is for conformance with the design concept of this project and for general compliance with contract documents. Contractor is responsible for quantities, dimensions and compliance with contract documents and for information that pertains to fabrication processes, construction techniques and coordination of this work with all trades which will be affected thereby. This review is null and void if submittal deviates from contract documents and does not indicate or note deviations.

A/E COMMENTS

☐ See attached sheet(s) for additional comments

For the Mullion Mate and for the other extruded trims on the project, we would like one of the four available standard whites – please provide samples of all white colors from Gordon for selection. See markups.

Design intent is to select the one that most closely matches Sherwin Williams SW 7004 Snowbound.

At ceiling trims, coordinate with shades for conflict with column covers. If there are conflicts revise trim dimensions accordingly.

Kelvin Patel	2/27/17
REVIEWED BY	DATE

Digitally signed by Kelvin Patel
DN: C=US, E=kpatel@cannondesign.com, O=Cannon Design,
OU=Architect, CN=Kelvin Patel
Date: 2017.02.27 19:47:12-06'00'