

PERFORMA®

Symphony® f
VOC Compliant

LOW
VOC

\$\$\$\$



LEED® v4

● MR: Environmental Product Declarations (EPDs)

● MR: Sourcing Raw Materials

● MR: Material Ingredients (HPDs)

● IEQ: Daylight

● IEQ: Low-Emitting Materials

● IEQ: Prereq. Min. Acoustic Performance (Schools)

● IEQ: Acoustic Performance

● MR: PBT Source Reduction (Healthcare)

● IEQ: Interior Lighting

● EA: Prereq. Min. Energy Performance

● EA: Optimize Energy Performance

● Recycled Content
Pre: 0% | Post: 28-34%

TOOLS

Visit CertainTeed.com/Ceilings
Download HPDs and EPDs
LEED® Information / BIM Objects
3-Part Specs / Data Pages




Recycled Content



EPD Available



HPD Available



IOF Finish

FEATURES & BENEFITS

- Superior sound absorption (NRC 0.90-0.95)
- Exceeds FGI guidelines for cleanability and acoustic performance
- Surface washability exceeds 1,000 cycles with sanitizing chemicals
- Certified clean room component to ISO Class 4 (highest among comparable products)
- IOF finish features extremely high light reflectance (LR 0.90)
- Perfect for enhanced speech privacy and exceptional productivity in open plan environment
- Third-party verified Environmental Product Declaration (EPD) available for this product
- Design with other IOF finish products Symphony® m and g for acoustical solutions
- Health Product Declaration (HPD) available for this product

APPLICATIONS

- Open Plan Areas
- Waiting Rooms
- Libraries
- Offices
- Nurses' Stations
- Computer Rooms
- Other Commercial Buildings / Space Applications

AVAILABLE EDGE DETAILS



Trim
15/16 Grid



Reveal
15/16 Grid



Narrow Reveal
9/16 Grid



ATTRIBUTES - IMPERIAL SIZES

ITEM NUMBER	DIMENSIONS (INCHES)	EDGE DETAIL	 NRC	 *CAC	 SAG RESISTANT	 MOLD RESISTANT	 LR	 WASHABLE	 SCRATCH RESISTANT	 FIRE RATING	 EMISSIONS	 RECYCLED CONTENT
1322-IOF-1	24 x 24 x 3/4	Trim	0.90	22	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	34%
1320-IOF-1	24 x 48 x 3/4	Trim	0.90	24	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	34%
1342-IOF-1	24 x 24 x 1	Trim Reveal Narrow Reveal	0.95	24	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1340-IOF-1	24 x 48 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1341-IOF-1	24 x 60 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1358-IOF-1	24 x 72 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36%
1347-IOF-1	20 x 60 x 1	Trim	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38%
1346-IOF-1	24 x 96 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1343-IOF-1	30 x 30 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1349-IOF-1	30 x 60 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1344-IOF-1	48 x 48 x 1	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1362-IOF-1	24 x 24 x 1-1/2	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38% 40% 40%
1360-IOF-1	24 x 48 x 1-1/2	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38% 40% 40%
1366-IOF-1	24 x 96 x 1-1/2	Trim	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38%
1364-IOF-1	48 x 48 x 1-1/2	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38% 40% 40%

*With optional foil backing

CAN'T FIND A SIZE? Contact your local Sales Representative 1-800-233-8990

PHYSICAL DATA

MATERIAL

Fiberglass Ceilings

ASTM E1264 CLASSIFICATION

Type XII, Form 2, Pattern E

FIRE PERFORMANCE

Per ASTM E1264: Class A, Flame Spread 25 or less

Per ASTM E84: Smoke Developed 50 or less

MOLD/MILDEW RESISTANCE

Fiberglass substrate is inherently resistant to the growth of mold and mildew.

VOC EMISSIONS

Independently certified compliant with California Department of Public Health CDPH/EHLB/Standard Method Version 1.1, 2010.

MAINTENANCE

Wipe with a soft cloth or vacuum with brush attachment. Cleanable with sanitizing chemicals.

WARRANTY

10 year 104/95 Limited Warranty



ATTRIBUTES – METRIC SIZES

ITEM NUMBER	DIMENSIONS (INCHES)	EDGE DETAIL	 NRC	 *CAC	 SAG RESISTANT	 MOLD RESISTANT	 LR	 WASHABLE	 SCRATCH RESISTANT	 FIRE RATING	 EMISSIONS	 RECYCLED CONTENT
1322M-IOF-1	600 x 600 x 19	Trim	0.90	22	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	34%
1320M-IOF-1	600 x 1200 x 19	Trim	0.90	24	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	34%
1347M-IOF-1	500 x 1500 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1342M-IOF-1	600 x 600 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1340M-IOF-1	600 x 1200 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1341M-IOF-1	600 x 1500 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1343M-IOF-1	750 x 750 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1349M-IOF-1	750 x 1500 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1344M-IOF-1	1200 x 1200 x 25	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	36% 38% 38%
1362M-IOF-1	600 x 600 x 38	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38% 40% 40%
1360M-IOF-1	600 x 1200 x 38	Trim Reveal Narrow Reveal	0.95	25	Yes	Inherent	0.90	Yes	Yes	Class A	Certified	38% 40% 40%

*With optional foil backing

CAN'T FIND A SIZE? Contact your local Sales Representative 1-800-233-8990

***Ordering Procedure:** To order preferences for edge details, select the item number above, then add the appropriate Edge Detail Code below.

Example:

Item Number	Edge Detail Code (Other than Trim)
Select from chart	B represents Reveal (15/16") F represents Narrow Reveal (9/16")
Example: 1342-IOF-1	1342 B -IOF-1 1342 MB -IOF-1

PHYSICAL DATA

MATERIAL

Fiberglass Ceilings

ASTM E1264 CLASSIFICATION

Type XII, Form 2, Pattern E

FIRE PERFORMANCE

Per ASTM E1264: Class A, Flame Spread 25 or less

Per ASTM E84: Smoke Developed 50 or less

MOLD/MILDEW RESISTANCE

Fiberglass substrate is inherently resistant to the growth of mold and mildew.

VOC EMISSIONS

Independently certified compliant with California Department of Public Health CDPH/EHLB/Standard Method Version 1.1, 2010.

MAINTENANCE

Wipe with a soft cloth or vacuum with brush attachment. Cleanable with sanitizing chemicals.

WARRANTY

10 year 104/95 Limited Warranty

CEILING CENTER
12964 St Charles Rock Rd
Bridgeton, MO. 63044
Phone 314/298-2502 EXT 102
Fax 314/739-1720

ACOUSTICAL CEILINGS
SUBMITTALS

PROJECT:
WEBSTER UNIVERSITY
INTERDISCIPLINARY SCIENCE BUILDING
8274 BIG BEND BLVD
WEBSTER GROVES, MO. 63119

GENERAL CONTRACTOR:
PARIC CONSTRUCTION
77 WESTPORT PLAZA
SUITE 250
ST LOUIS, MO. 63146

ACOUSTICAL CONTRACTOR:
ST CHARLES ACOUSTICS L.L.C

ACOUSTICAL MATERIALS

BOARD/TILE APC-1:	Certainteed 24" x 24" x 1" Narrow Reveal Edge Symphony F Item# 1342F-IOF-1
BOARD/TILE APC-2:	Certainteed 24" x 48" x 3/4" Narrow Reveal Edge Symphony M Item# 1220BF-IOF-1
BOARD/TILE APC-3A:	Certainteed 24" x 24" x 3/4" Narrow Reveal Edge Symphony M RXS Item# 1222F-RXS-1
BOARD/TILE APC-3B:	Certainteed 24" x 24" x 3/4" Square Edge Symphony M RXS Item# 1222-RXS-1
BOARD/TILE APC-5:	Certainteed 24" x 24" x 5/8" Square Edge Fine Fissured Item# HHF-157
BOARD/TILE APC-7:	Certainteed 24" x 48" x 3/4" Narrow Reveal Edge Symphony M Item# 1220BF-IOF-1
BOARD/TILE APC-8:	Certainteed 24" x 72" x 9/16" Narrow Reveal Edge Ecophon Gedina E 24 Item# 3540 4350
BOARD/TILE APC-9:	Certainteed 24" x 48" x 3/4" Narrow Reveal Edge Symphony M Item# 1220BF-IOF-1 with Kinetics Quiet tile

SUSPENSION SYS. FOR APC1/3A/3B Certainteed
Elite Narrow Stab Grid System
Item ES12-12-18 Color White

SUSPENSION SYS. FOR APC2/7/8/9: Chicago Metallic
4600 Ultraline Bolt Slot Grid System
Item 4600-01 Color White

SUSPENSION SYS. FOR APC5: Certainteed
Classic Stab Grid System
Item CS12-12-15 Color White