

Reducing Coupling


STYLE 750

211313 - Wet-Pipe Sprinkler System

The Style 750 Reducing Coupling permits direct reduction on the piping run. Designed to replace two couplings and a reducing fitting, the Style 750 features a special reducing gasket for pressure responsive sealing. A steel washer which prevents telescoping of the smaller pipe inside the larger pipe during vertical systems assembly is available upon request.



501



Exaggerated for clarity

MATERIAL SPECIFICATIONS

Housing: Ductile iron conforming to ASTM A-536, grade 65-45-12. Ductile iron conforming to ASTM A-395, grade 65-45-15, is available upon special request.

Housing Coating: Orange enamel

- **Optional:** Hot dipped galvanized and others

Gasket: (Specify choice*):

- **Grade "E" EPDM (All other sizes)**

EPDM (Green color code). Temperature range -30°F to $+230^{\circ}\text{F}$ / -34°C to $+110^{\circ}\text{C}$.

Recommended for cold and hot water service within the specified temperature range plus a variety of dilute acids, oil-free air and many chemical services. UL classified in accordance with ANSI/NSF 61 for cold $+86^{\circ}\text{F}/+30^{\circ}\text{C}$ and hot $+180^{\circ}\text{F}/+82^{\circ}\text{C}$ potable water service. NOT RECOMMENDED FOR PETROLEUM SERVICES.

- **Grade "T" nitrile**

Nitrile (Orange color code). Temperature range -20°F to $+180^{\circ}\text{F}$ / -29°C to $+82^{\circ}\text{C}$.

Recommended for petroleum products, air with oil vapors, vegetable and mineral oils within the specified temperature range. Not recommended for hot water services over $+150^{\circ}\text{F}/+66^{\circ}\text{C}$ or for hot dry air over $+140^{\circ}\text{F}/+60^{\circ}\text{C}$.

* Services listed are General Service Recommendations only. It should be noted that there are services for which these gaskets are not recommended. Reference should always be made to the latest Victaulic Gasket Selection Guide for specific gasket service recommendations and for a listing of services which are not recommended.

- **Optional:** Assembly Washer: Galvanized, carbon steel

Bolts/Nuts: Heat-treated plated carbon steel, trackhead meeting the physical and chemical requirements of ASTM A-449 and physical requirements of ASTM A-183.

JOB/OWNER

System No. _____

Location _____

CONTRACTOR

Submitted By _____

Date _____

ENGINEER

Spec Sect _____ Para _____

Approved _____

Date _____

www.victaulic.com

VICTAULIC IS A REGISTERED TRADEMARK OF VICTAULIC COMPANY. © 2012 VICTAULIC COMPANY. ALL RIGHTS RESERVED.

REV_J



06.08_1

Reducing Coupling

STYLE 750

DIMENSIONS

Size			Max. Work Pressure *	Max. End Load *	Allow. Pipe End Sep. †	Deflect. Fr. C _L †		Bolt/Nut@ No - Size	Dimensions – Inches/mm			Approx. Wgt. Each
Nominal Size			psi kPa	Lbs. N	Inches/ mm	Per Cplg. Deg.	Pipe In./Ft. mm/m	Inches	X	Y	Z	Lbs. kg
2	×	1	350	500	0 – 0.07	0° – 57°	0.20	2 – 3/8 x 2	3.38	5.28	1.88	2.7
50		25	2410	2225	0 – 1.8		17		85	134	48	1.2
		1½	350	1000	0 – 0.07	0° – 57°	0.20	2 – 3/8 x 2	3.38	5.28	1.88	2.0
		40	2410	4450	0 – 1.8		17		85	134	48	1.0
2½	×	2	500	2215	0 – 0.07	0° – 47°	0.16	2 – 3/8 x 2	4.00	5.93	1.88	3.1
65		50	3450	9850	0 – 1.8		14		102	151	48	1.4
76.1 mm	×	2	350	1550	0 – 0.07	0° – 47°	0.16	2 – ½ x 2 ¾	4.38	6.63	1.88	4.6
		50	2410	6900	0 – 1.8		14		111	168	48	2.1
3	×	2	350	1550	0 – 0.07	0° – 39°	0.13	2 – ½ x 2 ¾	4.75	7.13	1.88	4.9
80		50	2410	6900	0 – 1.8		11		121	181	48	2.2
		2½	500	3250	0 – 0.07	0° – 39°	0.13	2 – ½ x 2 ¾	4.75	7.13	1.88	4.3
		65	3450	14460	0 – 1.8		11		121	181	48	2.0
88.9 mm	×	76.1 mm	350	2475	0 – 0.07	0° – 39°	0.13	2 – ½ x 2 ¾	4.75	7.13	1.88	4.2
			2410	11010	0 – 1.8		11		121	181	48	1.9
4	×	2	350	1550	0 – 0.13	1° – 19°	0.28	2 – 5/8 x 3 ¼	6.25	8.90	2.25	8.1
100		50	2410	6900	0 – 3.2		25		159	226	57	3.7
		2½	350	2275	0 – 0.13	1° – 19°	0.28	2 – 5/8 x 3 ¼	6.25	8.90	2.25	8.6
		65	2410	10125	0 – 3.2		25		159	226	57	3.9
		3	500	4810	0 – 0.13	1° – 19°	0.28	2 – 5/8 x 3 ¼	6.00	8.90	2.25	6.7
		80	3450	21400	0 – 3.2		25		152	226	57	3.0
114.3 mm	×	76.1 mm	350	2475	0 – 0.13	1° – 19°	0.28	2 – 5/8 x 3 ¼	6.25	8.90	2.25	6.9
			2410	11014	0 – 3.2		25		159	226	57	3.1
5	×	4	350	5565	0 – 0.13	1° – 3°	0.22	2 – ¾ x 4 ¼	7.18	10.70	2.13	11.2
125		100	2410	24765	0 – 3.2		19		182	272	54	5.1
6	×	4	350	5565	0 – 0.13	0° – 52°	0.18	2 – ¾ x 4 ¼	8.63	11.90	2.25	16.7
150		100	2410	24765	0 – 3.2		15		181	302	57	7.6
		5	350	8500	0 – 0.13	0° – 52°	0.18	2 – ¾ x 4 ¼	8.31	11.90	2.25	12.9
		125	2410	37825	0 – 3.2		15		211	302	57	5.9
165.1 mm	×	4	350	5565	0 – 0.13	0° – 55°	0.19	2 – ¾ x 4 ¼	8.63	11.90	2.25	15.2
		100	2410	24765	0 – 3.2		16		219	302	57	6.9
8	×	6	350	12060	0 – 0.13	0° – 38°	0.13	2 – 7/8 x 5	10.81	14.88	2.50	22.4
200		150	2410	53645	0 – 3.2		11		275	378	64	10.2
219.1 mm	×	165.1 mm	350	11610	0 – 0.13	0° – 38°	0.13	2 – 7/8 x 5	10.75	14.88	2.50	23.2
			2410	51645	0 – 3.2		11		273	378	64	10.5
10	×	8	350	20450	0 – 0.13	0° – 25°	0.9	2 – 1 x 5 ½	13.12	17.26	2.62	31.4
273		219.1	2410	90970	0 – 3.2		8		333	438	67	14.2

Style 750 Reducing couplings should not be used with end caps (#60) in systems where a vacuum may be developed. Contact Victaulic for details.


* Working Pressure and End Load are total, from all internal and external loads, based on standard weight (ANSI) steel pipe, standard **roll** or **cut** grooved in accordance with Victaulic specifications. Contact Victaulic for performance on other pipe. Maximum working pressure rating based on larger pipe size. Maximum End Load rating based on smaller pipe size. WARNING: FOR ONE TIME FIELD TEST ONLY, the Maximum Joint Working Pressure may be increased to 1 ½ times the figures shown.

† Allowable Pipe End Separation and Deflection figures show the maximum nominal range of movement available at each joint for standard **roll** grooved pipe. Figures for standard **cut** grooved pipe may be doubled. These figures are maximums; for design and installation purposes these figures should be reduced by: 50% for ¾ – 3 ½/20 – 90 mm; 25% for 4"/100 mm and larger.

@ Number of bolts required equals number of housing segments.

Metric thread size bolts are available (color coded gold) for all coupling sizes upon request. Contact Victaulic for details.

WARNING: Depressurize and drain the piping system before attempting to install, remove, or adjust any Victaulic piping products.



Reducing Coupling

501

STYLE 750

FLOW DATA

HEAD LOSS

The head loss across Style 750 Reducing coupling is very small and is essentially the same as for standard short body reducing pipe fittings.

Equivalent lengths of standard weight steel pipe are shown in the tables. All data is based on water flowing at ambient temperature.

FLOW REDUCING

Size			Equiv. Pipe Length
Nominal Size Inches/mm			Sm. Dia. Feet/m
2 50	×	1 25	5.9 1.8
		1½ 40	2.0 0.6
2½ 65	×	2 50	1.9 0.6
76.1 mm	×	2 50	1.9 0.6
3 80	×	2 50	5.5 1.7
		2½ 65	3.8 1.2
88.9 mm	×	76.1 mm	3.8 1.2
4 100	×	2 50	6.0 1.8
		2½ 65	6.0 1.8
		3 80	6.0 1.8
114.3 mm	×	76.1 mm	6.0 1.8
5 125	×	4 100	3.0 0.9
6 150	×	4 100	6.0 1.8
		5 125	4.5 1.4
165.1 mm	×	4 100	6.0 1.8
8 200	×	6 150	7.3 2.2
		165.1 mm	7.3 2.23
10 273	×	8 219.1	8.7 2.65

FLOW EXPANDING

Size			Equiv. Pipe Length
Nominal Size Inches/mm			Sm. Dia. Feet/m
1 25	×	2 50	2.7 0.8
1½ 40	×	2 50	1.9 0.6
2 50	×	2½ 65	1.0 0.3
		76.1 mm	1.0 0.3
		3 80	3.5 1.1
		4 100	3.0 0.9
2½ 65	×	3 80	2.5 0.8
		4 100	3.0 0.9
76.1 mm	×	88.9 mm	2.5 0.8
		114.3 mm	3.0 0.9
3 80	×	4 100	2.5 0.8
4 100	×	5 125	3.3 1.0
		6 150	4.6 1.4
		165.1 mm	4.6 1.4
5 125	×	6 150	2.3 0.7
6 150	×	8 200	6.0 1.8
165.1 mm	×	219.1 mm	5.4 1.65
8 219.1	×	10 273	6.3 19.2

Reducing Coupling

501

STYLE 750

INSTALLATION

Reference should always be made to the I-100 Victaulic Field Installation Handbook for the product you are installing. Handbooks are included with each shipment of Victaulic products for complete installation and assembly data, and are available in PDF format on our website at www.victaulic.com.

WARRANTY

Refer to the Warranty section of the current Price List or contact Victaulic for details.

NOTE

This product shall be manufactured by Victaulic or to Victaulic specifications. All products to be installed in accordance with current Victaulic installation/assembly instructions. Victaulic reserves the right to change product specifications, designs and standard equipment without notice and without incurring obligations.

For complete contact information, visit www.victaulic.com

06.08 1536 REV J UPDATED 08/2012

VICTAULIC IS A REGISTERED TRADEMARK OF VICTAULIC COMPANY. © 2012 VICTAULIC COMPANY. ALL RIGHTS RESERVED.

06.08



Shop Drawing Submittal Review

Transmitted To: Cannon Design

Date: December 20, 2016

Attention: stl-cac@cannondesign.com

Contact Person / WTA Field Inspector:
Patrick Garner

Project Name: Webster University-**ISB**

Reviewed by: Mike Whitworth (WES)

Project No. WT 14127.01
WES 607

☐

UPS

☐

Courier

☒

Email

Copies	No.	Description
1 PDF	211313F02	(Submittal No.'s:)
		(Cannon #211313-015) - (Paric #15051-0349) – (WES #607)
		➤ Wet Pipe Sprinkler System Product Data

***Remarks: See Submittal Review from Webb Engineering.**

c: Kelvin Patel
Kpatel@cannondesign.com

☒

***Reviewed**

☒

***No Exceptions Taken -**

☒

***Amend and Resubmit**

☒

***Make Corrections As Noted,
No Resubmittal Required**

Corrections or comments made on shop drawings during this review do not relieve contractor from compliance with requirements of drawings and specifications. This check is only for review of general conformance with the design concept of project and general compliance with information given in contract documents. Contractor is responsible for: confirming and correlating all quantities and dimensions; selecting fabrication processes and techniques of construction; coordinating his work with that of all other trades; and performing his work in a safe and satisfactory manner.



1400 S. 3rd Street, Suite 201
St. Louis, Missouri 63104
Phone: (314) 588-0600
Fax: (314) 588-0604

Letter of Transmittal

To: wtashop@wmtao.com

From: Mike Whitworth

Date: December 20, 2016

Re: Webster University ISB

WES No: 607

☐ For your Files

☐ For Review

☐ Please Comment

☐ Please Reply

Item No.	Description	No. of Copies	Date
1	Shop Drawing Review – (213113-015) 211313 Wet Pipe Sprinkler System	1	12/20/16

•Signature: Mike Whitworth

The review of this submittal is limited to the general conformance with the designated design concept and intent of this project and with the general compliance of the information provided in the contract documents. All comments, remarks and notations made on the submittal(s) as a result of this review do not relieve the contractor from full compliance with requirements of the contract documents. Approval for a specific item shall not include approval of an assembly of which the item is not a component. The contractor is solely responsible for rough-in and installation confirming and correlating all quantities and dimensions; selecting fabrication processes and techniques of construction; coordination of this work with that of other trades on this project; and in a safe and satisfactory manner. All work shall be installed in full compliance with the manufacturer's recommendation, Federal, State and Local rules and regulation and the Authority Having Jurisdiction (AHJ) and applicable adopted codes and standards.

PROJECT NAME: Webster University I

LOCATION: St. Louis Missouri

CLIENT PROJ. NO.: N/A

WES PROJ. NO.: 607

SPECIFICATION 211313
SECTION: Wet Pipe Sprinkler System

SUBMITTAL ITEM: See Below -

CONTRACTOR: J.F. Ahern Co.
CTR. SUBMITTAL #: 21 1313-015
SUBMITTAL DATE: November 29, 2016
DATE RECEIVED: December 07, 2016
RECEIVED VIA: E-Mail
RECEIVED FROM: WTA
DATE RETURNED: DECEMBER 20, 2016
RETURNED VIA: E-MAIL
RETRURNED TO: WTASHOP@WMTAO.COM

STATUS KEY:

NO EXCEPTION TAKEN						
NEC	MCN	MAKE CORRECTIONS NOTED, NO RESUBMITTAL:				
		AAR	AMEND AND RESUBMIT			
			REJ	REJECTED, SEE REMARKS:		
				REV	REVIEWED ONLY	
					ITEM	REMARKS
Pages numbers have been added to cut sheets for referencing						
X					Page 001 Schedule 10 Pipe Various Manufacturers	
X					Page 002 Schedule 40 Pipe Various Manufacturers	
X					Pages 003 – 004 Test and Drain Valve AGF Manufacture ring Model – 1011A	
X					Pages 005 – 006 Backflow Preventer Zurn Industries Model – 350A	
X					Pages 007 – 008 Standard Duty Loop Hanger Caddy Model – 115 Series	

X				Pages 009 – 010 Universal Beam Clamp Caddy Model – 300 Series	
X				Pages 011 – 016 Carbon Steel Anchor Screw Hilti Model – 3.3.5 KWIK HUS- EZ (KH-EZ1)	
X				Page 017 Riser Clamp PHD Manufacturing Model – Fig. 550-551-553	
X				Page 018 Universal Restraining Strap Afcon Model - 162	
X				Pages 019 – 027 Sleeve Expansion Anchors Powers Fasteners Model – Lok-Bolt Hex Head and Rod Hanger	
X				Pages 028 – 031 Strut Channel Gregory Strut Products Model – G712OS, G712A, G5820S, G582A and G1320OS	
X				Page 032 Surge Restraint 115 Caddy Model – SR6	
X				Page 033 Screw Anchor/Hanger ITW Model – Sammy X-Press	
		X		Pages 034 – 039 Quick Response Dry Pendent Sprinkler Viking Model - SIN Not Specified	1. SIN numbers listed in submittal (VK172, VK176, VK180 on pages 037/038) is not listed on the FP drawings in the Sprinkler schedule.
X				Pages 040 -043 Microfast Quick Response Upright Sprinkler Viking Model – SIN VK300	
		X		Pages 044 -049 Microfast Quick Response Pendent Sprinkler Viking Model – SIN VK302	1. SIN number listed in submittal (VK302 on pages 047/048) is not listed on the FP drawings in the Sprinkler schedule.

X				Pages 050 – 055 Microfast Quick Response Horizontal Sidewall Sprinkler Viking Model – SIN VK305	
X				Pages 056 – 059 Microfast Quick Response Upright Sprinkler Viking Model – SIN VK350	
		X		Pages 060 – 065 Microfast Quick Response Pendent Sprinkler Viking Model – SIN VK352 (K8.0)	1. SIN number listed in submittal (VK352 on pages 063/064) is not listed on the FP drawings in the Sprinkler schedule.
		X		Pages 066 – 071 Microfast Quick Response Pendent Sprinkler Viking Model – SIN VK352 (K8.0)	1. SIN number listed in submittal (VK352 on pages 069/070) is not listed on the FP drawings in the Sprinkler schedule.
X				Pages 072 – 077 Mirage Standard and QR Concealed Pendent Sprinkler Viking Model – SIN VK462	
X				Page 078 Spare Sprinkler Head Cabinet FPPI Model – Not indicated	
X				Page 079 – 089-091 Spare Sprinkler Head Cabinet TYCO Model – Not Indicated	
X				Pages 080 – 088 Sprinkler Escutcheons Viking Model -	
X				Pages 092 – 094 Sprinkler Guards Viking Model – D-1	
X				Pages 095 – 100 Standard / QR Extended Coverage Upright Sprinkler Viking Model – SIN VK532	
X				Pages 101 – 106 Standard / QR Extended Coverage Pendent Sprinkler Viking Model – SIN VK534	

X				Pages 107 – 112 Mirage QR Extended Coverage Concealed Pendent Sprinkler Viking Model – SIN VK634	
		X		Pages 113 – 120 Concealed Dry Pendant Sprinkler Reliable Model – G5-56 Dry (SIN RA5114)	1. Manufacturer and model/SIN number listed in submittal is not listed on the FP drawings in the Sprinkler schedule. 2. Color/finish of cover plate to be submitted to the Architect for review and approval.
X				Pages 121 - 124 Flexible Coupling Victaulic Model – Style 75	
X				Pages 125 - 128 Reducing Coupling Victaulic Model – Style 750	
X				Pages 129 – 131 FireLock Fittings Victaulic Model – Fire lock	
X				Pages 132 – 134 FireLock Rigid Coupling Victaulic Model – Style 005H	
X				Pages 135 – 136 Fire lock Flange Adapter Victaulic Model – Style 744	
X				Pages 137 – 144 Mechanical T Bolted Branch Outlets Victaulic Model – Styles 920 and 920N	
X				Pages 145 – 149 Firelock Rigid Coupling Victaulic Model – Style 009N	
X				Pages 150 – 151 Threaded Mechanical Branch Tee Anvil Model – Fig. MT-30	
X				Pages 152 – 153 Grooved Welded Steel Pipe Outlets Vandewater International Inc. Model - Various	
X				Pages 154 – 155 Welded Steel Pipe Outlets Vandewater International Inc. Model - Various	

X					Page 156 DI Threaded Fitting – 90 Elbow Anvil Model – Fig 3201	
X					Page 157 DI Threaded Fitting – 45 Elbow Anvil Model – Fig 3202	
X					Page 158 DI Threaded Fitting – Reducing 90 Elbow Anvil Model – Fig 3201R	
X					Page 159 DI Threaded Fitting – Straight T Anvil Model – Fig 3205	
X					Pages 160 - 161 DI Threaded Fitting – Reducing T Anvil Model – Fig 3205R	
X					Page 162 DI Threaded Fitting Anvil Model – Bull Head T	
X					Page 163 DI Threaded Fitting Cross Anvil Model - 3207	
X					Page 164 DI Threaded Fitting Anvil Model – 3221R	
X					Page 165 DI Threaded Fitting Anvil Anvil Model - 3121	
X					Page 166 DI Threaded Fitting Cap Anvil Model - 3224	
X					Page 167-168 DI Threaded Fitting Bushing Anvil Model - 3283	

				X	Pages 169 – 183 Flexible Sprinkler Hose Victaulic Model – Series AH2 Bracket AB1, AB7 and AB7 Adjustable	1. This product is not listed in the construction documents for use on this project. Contractor has elected to incorporate into the delegated design.
X					Pages 184 – 185 Water Flow Detector System Sensor Model – WFD Series	
X					Pages 186 – 192 Supervisory Switch Potter Electrical Model – PCVS Series	
	X				Pages 193 – 194 Electric Bell Potter Electric Model – Not Indicated	1. Specified to be 10 inch diameter. Refer to specification section 211313, part 2.6, B4 and B-7.
X					Page 195 Service Gauge Ashcroft Model – 35W1005PH02LXUL300	
X					Pages 196 – 199 Intumescent Sealant STI Model - Series LCI	
X					Page 200 Fire Pump Suction and Discharge Gauges Alenco Series AG-1000L	
X					Page 201 Suction and Discharge Gauge Assembly A-C Fire Pump systems Model – Not Indicated	
	X				Pages 202 – 203 Fire Pump Test Header Potter Roemer Model – 5864-x-x-6-D- NST	1. Assembly to be mounted vertically, in space available.
Note: Fire protection drawings list sprinkler Viking model Mirage, SIN VK464 (31 total) and Viking model Dry, Sin VK194, (24 total) in the Sprinkler Schedule. These two sprinkler heads are not included in this submittal.						

REVIEWED BY: Michael R. Whitworth DATE: December 20, 2016

THESE COMMENTS ARE TO BE ATTACHED TO ALL COPIES OF THE SHOP DRAWING REFERENCED ABOVE.

SUBMITTAL IDENTIFICATION SHEET

To be completed by Contractor/CM

PROJECT NAME	
ADDRESS	
NUMBER	
OWNER	
ARCHITECT / ENGINEER	
SUBMITTED BY	
CONTRACTOR / CM SUBMITTAL NO.	CANNON DESIGN SUBMITTAL NO.
DRAWING / DETAIL REFERENCE	SPECIFICATION SECTION / PARAGRAPH
MANUFACTURER / SUPPLIER	ITEM / PRODUCT ID
REQUIRED DATE	PRIORITY
CRITICALITY	

To be completed by Reviewer

CANNON DESIGN SUBMITTAL NUMBER
RECEIVED DATE

- ☐ **A. No Exceptions Taken**
No further review of submittal is required.
- ☐ **B. Make Corrections Noted**
Incorporate corrections in work;
resubmission is not required.
- ☐ **C. Revise and Resubmit**
Revise as noted, and resubmit for review.
- ☐ **D. Rejected**
Submittal is not in compliance with Contract Documents;
provide new submittal.
- ☐ **E. For Record / Information Only**
Submittal was reviewed for Record / Information
purposes only.
- ☐ **F. Not Required for Review**
Submittal is not required by Contract Documents
and has not been reviewed.

Review is for conformance with the design concept of this project and for general compliance with contract documents. Contractor is responsible for quantities, dimensions and compliance with contract documents and for information that pertains to fabrication processes, construction techniques and coordination of this work with all trades which will be affected thereby. This review is null and void if submittal deviates from contract documents and does not indicate or note deviations.

ITEM BEING SUBMITTED (check only one)

- ☐ Shop Drawings ☐ Certification / Qualifications ☐ Coordination Drawing
☐ Samples ☐ Record Documents ☐ Calculations
 (_____ copies) ☐ Product Data ☐ Schedules
☐ LEED Submittal ☐ O&M Manuals
☐ Other

ITEM BEING SUBMITTED FOR (check only one)

- ☐ Action ☐ Information Only ☐ Record

REMARKS OR DEVIATIONS

CONTRACTOR / CM CERTIFICATION
(SUBMITTALS NOT CERTIFIED WILL BE RETURNED WITHOUT REVIEW)



PARIC CORPORATION
SUBMITTAL STAMP

THIS SHOP DRAWING HAS BEEN REVIEWED BY PARIC CORPORATION

Subcontractor remains responsible for dimensions, quantities, coordination with other trades and compliance with contract documents.

Ry:

By:
Devin D. Gates

REVIEWED BY	DATE

A/E COMMENTS

- ☐
- See attached sheet(s) for additional comments

REVIEWED BY	DATE



77 Westport Plaza
Suite 250
St. Louis, MO 63146

TRANSMITTAL

No. 15051-0349

Paric Corporation

PROJECT: 15051-Webster University Interdisciplinary Science Building

DATE: 11/29/2016

TO: Cannon Design
1100 Clark Ave
St Louis MO 63102

Fax;
314-241-2203

RE: Wet Pipe Sprinkler System Product Data

ATTN: Kelvin Patel

JOB: 15051

WE ARE SENDING:	SUBMITTED FOR:	ACTION TAKEN:
☐ Shop Drawings	☒ Approval	☐ Approved as Submitted
☐ Letter	☐ Your Use	☐ Approved as Noted
☐ Prints	☐ As Requested	☐ Returned After Loan
☐ Change Order	☐ Review and Comment	☐ Resubmit
☐ Plans		☐ Submit
☐ Samples	SENT VIA:	☐ Returned
☐ Specifications	☐ Attached	☐ Returned for Corrections
☒ Other: Product Data	☐ Separate Cover Via:	☐ Due Date:

Item	Package	Code	Rev.	Copies	Date	Description	Status
Submittal		211313-015	1		11/29/2016	Wet Pipe Sprinkler System Product Data	Submitted

NOTES:

CC:

Signed: _____
Devin Gates