

Product Environmental Profile

Middle Atlantic Products® RSH4A4M Fixed Rackmount Shelves



COMPANY OVERVIEW

• Designed to Be Better – Our Commitment to Sustainability

At Legrand®, our sustainability commitment translates into greater benefits and tangible value for our customers, business partners, employees, and the broader community.

• Better Performance

We provide building solutions to meet many building performance goals from sustainability and energy efficiency to productivity and occupant well being. The right choice in network and electrical infrastructure can play a key role in many facets of building performance. Our products help ensure electrical safety. They offer choice and flexibility in space design. They are designed to reduce installation time and material waste on site. Because we know buildings consume a great deal of energy, we offer a range of products and solutions that reduce energy consumption from lighting to plug load to data centers.

• Better Solutions

We offer a wide range of innovative solutions for the building, while constantly evolving our design and development processes to improve the environmental profile of our products. Through active monitoring and research, we serve as an expert resource for market trends and building and product performance standards to keep our customers at the top of their game.

• Better Operations

We focus on operational excellence because we believe optimizing the way we manage energy, water and waste is not only good for the environment, it's good for business. As part of the Department of Energy's Better Building, Better Plants Challenge (BBBP) Legrand has reduced its energy intensity by over 30% across 14 sites in the United States in just three years. Integrating sustainability into the way we run our operations makes us more competitive – and a better business partner.



For information on Legrand PEP's and our sustainability initiatives, scan the QR code to be brought to our High Performance Buildings page.



LEGRAND'S ENVIRONMENTAL COMMITMENTS

• Incorporate environmental management into our industrial sites

Of all Legrand sites worldwide, over 85% are ISO 14001 certified (sites belonging to Legrand for more than five years).

• Offer our customers environmentally friendly solutions

Develop innovative solutions to help our customers design more energy efficient, better managed and more environmentally friendly installations.

• Involve the environment in product design

Reduce the environmental impact of products over their whole life cycle.

Provide our customers with all relevant information (composition, consumption, end of life, etc.).



REFERENCE PRODUCT

Function	Protect persons during 20 years against direct contact with live parts and allow grouping monitoring, control and protection devices in a single enclosure or a cabinet having the following dimensions 19"x14.44"x3.50".
Reference Product	 Part Number: RSH4A4M Fixed rackmount shelf used to accommodate installed components.

Product Environmental Profile

Middle Atlantic Products® RSH4A4M Fixed Rackmount Shelves



PRODUCTS CONCERNED

The environmental data is representative of the following products:

Description - Fixed rackmount shelf products within of the following series:

MS	UFAF
RSH	UMS1
SH	UMSFP1
SH-DMP	WMS
UFA	



CONSTITUENT MATERIALS

This Reference Product contains no substances prohibited by the regulations applicable at the time of its introduction to the market. It respects the restrictions on use of hazardous substances as defined in the RoHS directive 2011/65/EC and does not contain, as far as we know, any substance on the candidate list from June 2015 for authorization of the REACH regulation (EC) no. 1907/2006 with a concentration above 0.1% w/w.

Total weight of Reference Product (with unit packaging)		7.3 lb (3.30 kg)			
Plastics as % of weight		Metals as % of weight		Other as % of weight	
		Steel	85.0%	Paint	1.0%
				Packaging as % of weight	
				Cardboard	13.9%
				Low density polyethylene (LDPE)	0.1%
Total plastics	0%	Total metals	85.0%	Total other and packaging	15.0%

Estimated recycled material content: 25% of weight.



MANUFACTURING

The Reference Product comes from sites that have received ISO 14001 certification.

Specific distances of transport before and after manufacturing were not available, but based on the use of local suppliers and sale within in North America, "Local transport" default distance of 621 miles (1,000 km) by heavy truck to the manufacturing site and to local distribution centers was included in the manufacturing stage.



DISTRIBUTION

Products are distributed from logistics centers located to optimize transport efficiency using EPA SmartWay® certified carriers to reduce greenhouse gases emissions. Information on the distance of distribution is not available so the PCR hypothesis for "Intercontinental transport", 2175 miles (3500 km) by heavy truck, was used. This represents transportation of the Reference Product from our warehouse to the local point of distribution in the North American market.

Product Environmental Profile

Middle Atlantic Products® RSH4A4M Fixed Rackmount Shelves



■ INSTALLATION

No electricity or a negligible amount is required for installing the Reference Product.



■ USE

Servicing and maintenance:

Under normal conditions of use, this type of product requires no servicing or maintenance.

Consumable:

No consumables are necessary to use this type of product.



■ END OF LIFE

• Hazardous waste* contained in the product: no hazardous waste

(*) Hazardous waste as defined by European Commission decision 2000/532/EC.

• Recycling rate:

Calculated using the method described in the IEC/TR 62635 technical report, the recyclability rate of the Reference Product without packaging is estimated as 95%. This value is based on data collected from a technological channel using industrial procedures. It does not pre-validate the effective use of this channel for end-of-life electrical and electronic products.

Separated into:

(% mass of Reference Product without packaging)

- plastic materials (excluding packaging): 0%
- metal materials (excluding packaging): 95%
- other materials (excluding packaging): 0%

Recycling rate of packaging (all types of materials): 70%



■ ENVIRONMENTAL IMPACTS

The evaluation of environmental impacts examines the stages of the Reference Product life cycle: manufacturing, distribution, installation, use, and end of life. It is representative of products marketed and used in North America.

The following modelling elements were taken into account:

Manufacturing	All transport for the manufacturing of the Reference Product, including materials and components, has been taken into account. Production of raw materials and packing, as well as the product manufacturing is accounted for. The waste generated during manufacturing phase has been included for non packaging materials. Manufacturing process have been accounted for using electricity, fuel and water use for the steel processing portion of the facility.
Distribution	Transport between the last distribution center and an average delivery to the sales area. The default scenario modelled maximizes the environmental impact.
Installation	The end of life of the packaging (1.0 lb or 460 g) and its transport to end of life treatment is taken into account at this phase.
Use	• Under normal conditions of use, this type of product requires no servicing or maintenance. • No consumables are necessary to use this type of product. • Product category: Enclosure. • Use scenario: Continuous operation for 20 years. • Energy model: This product does not use electricity
End of life	The end of life of the product is modelled as the transport of the product the default distance of 621 miles (1000 km) by truck, and landfilling of non-recycled (non-metal) product constituent materials.
Software used	EIME V5 and its database "CODDE-2015-04" and the indicators defined in the PCR ed 3 in alignment with the EN15804 standard

Product Environmental Profile


Middle Atlantic Products® RSH4A4M Fixed
Rackmount Shelves



ENVIRONMENTAL IMPACTS (continued)

	Total for Life cycle		Raw material and manufacturing		Distribution		Installation		Use		End of life	
Global warming (GW)	1.39E+01	kg CO ₂ eq.	1.25E+01	90%	5.75E-01	4%	6.53E-01	5%	0.00E+00	0%	1.87E-01	1%
Ozone depletion (OD)	1.02E-07	kg CFC-11 eq.	9.86E-08	97%	1.17E-09	1%	1.62E-09	2%	0.00E+00	0%	3.78E-10	<1%
Acidification of soil and water (A)	2.82E-02	kg SO ₂ eq.	2.46E-02	87%	2.59E-03	9%	1.23E-04	<1%	0.00E+00	0%	8.84E-04	3%
Water eutrophication (WE)	5.13E-03	kg PO ₄ ³⁻ eq.	3.08E-03	60%	5.94E-04	12%	1.25E-03	24%	0.00E+00	0%	2.05E-04	4%
Photochemical ozone creation (POCP)	4.55E-03	kg C ₂ H ₄ eq.	4.15E-03	91%	1.84E-04	4%	1.58E-04	3%	0.00E+00	0%	6.37E-05	1%
Depletion of abiotic resources - elements (ADPe)	1.55E-06	kg Sb eq.	1.51E-06	98%	2.30E-08	1%	1.02E-09	<1%	0.00E+00	0%	7.48E-09	<1%
Total use of primary energy (PE)	5.47E+02	MJ	5.36E+02	98%	7.72E+00	1%	4.00E-01	<1%	0.00E+00	0%	2.50E+00	<1%
Net use of fresh water (FW)	7.58E-02	m ³	7.57E-02	100%	5.15E-05	<1%	1.72E-05	<1%	0.00E+00	0%	1.67E-05	<1%
Depletion of abiotic resources – fossil fuels (ADPf)	1.48E+02	MJ	1.37E+02	92%	8.09E+00	5%	4.00E-01	<1%	0.00E+00	0%	2.62E+00	2%
Water pollution (WP)	6.69E+02	m ³	5.06E+02	76%	9.47E+01	14%	3.75E+01	6%	0.00E+00	0%	3.07E+01	5%
Air pollution (AP)	1.56E+03	m ³	1.53E+03	98%	2.36E+01	2%	3.02E+00	<1%	0.00E+00	0%	8.61E+00	<1%

The values of the 27 impacts defined in the PCR-ed3-EN-2015 04 02 are available in the digital database of pep-ecopassport.org website. The environmental impacts of the Reference Product are representative of the products covered by the PEP, which therefore constitute a homogeneous environmental family.



The environmental impact of the Reference Product occurs predominantly during the manufacturing phase.

Product Environmental Profile

Middle Atlantic Products® RSH4A4M Fixed
Rackmount Shelves



ENVIRONMENTAL IMPACTS (continued)

For products other than the Reference Product, the environmental impacts can be determined for each life cycle phase by multiplying the Reference Product impacts by the factors listed below. Values are generally consistent within a life cycle phase for each product.

Factor	Ratio to calculate factor
A	Mass of product without packaging / Mass of reference product without packaging
B	Total mass of product with packaging / Total mass of reference product with packaging
C	Mass of product packaging / Mass of reference product packaging
1	Use phase is the same for all products

Part Number	Manufacturing	Distribution	Installation	Use	End of Life
Series: MS, RSH, SH, SH-DMP, UFA, UFAF, UMS1, UMSFP1, WMS	A	B	C	1	A

Registration number: LGRP-00329-V01.01-EN	Drafting rules: "PCR-ed3-EN-2015 04" Supplemented by "PSR-0005-ed2-EN-2016 03 29"
Verifier's accreditation number: VH08	Information and reference documents: www.pep-ecopassport.org
Date of issue: 12-2016	Validity period: 5 years
Independent verification of the declaration and data, in compliance with ISO 14025:2010 Internal ☒ External ☐	
The PCR Review was conducted by a panel of experts chaired by Philippe Osset (SOLINNEN).	
The elements of the present PEP cannot be compared with elements from another program.	
Document in compliance with ISO 14025:2010: "Environmental labels and declarations - Type III environmental declarations"	
In compliance with ISO 14040:2006: "Environmental management - LCA - Principles and framework"	
In compliance with ISO 14044:2006: "Environmental management - LCA - Requirements and guidelines"	
In alignment with EN 15804:2012+A1:2013: "Sustainability of construction works - EPD's - Core rules for the product category of construction products"	